

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (23+91.00)	Lump Sum	L.S.	
0003	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0004	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0007	0106000000-E	230	BORROW EXCAVATION	12,010 CY		
0008	0134000000-E	240	DRAINAGE DITCH EXCAVATION	540 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	150 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	150 SY		
0011	0241000000-E	SP	GENERIC GRADING ITEM TEMPORARY FABRIC WALL	320 SY		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	21 TON		
0013	0343000000-E	310	15" SIDE DRAIN PIPE	40 LF		
0014	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	60 LF		
0015	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	96 LF		
0016	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	6 EA		
0017	0995000000-E	340	PIPE REMOVAL	56 LF		
0018	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,135 TON		
0020	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	605 TON		
0021	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	960 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	140 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	14 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	34 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	26 CY		
0026	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	150 LF		
0027	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	465 LF		
0033	3030000000-E	862	STEEL BM GUARDRAIL	862.5 LF		
0034	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0035	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0037	3649000000-E	876	PLAIN RIP RAP, CLASS B	105 TON		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	995		
					SY	
0039	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2		
					EA	
0040	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	90		
					SF	
0041	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	192		
					SF	
0042	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	20		
					SF	
0043	4430000000-N	1130	DRUMS	40		
					EA	
0044	4435000000-N	1135	CONES	30		
					EA	
0045	4446100000-E	SP	BARRICADES (TYPE III)	48		
					LF	
0046	4455000000-N	1150	FLAGGER	100		
					MD	
0047	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4		
					EA	
0048	4485000000-E	1170	PORTABLE CONCRETE BARRIER	1,870		
					LF	
0049	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	40		
					LF	
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	71		
					EA	
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,400		
					LF	
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,400		
					LF	
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	22,000		
					LF	
0054	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	30		
					EA	
0055	6000000000-E	1605	TEMPORARY SILT FENCE	1,450		
					LF	
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75		
					TON	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	400 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	400 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	5.5 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		
0062	6024000000-E	1622	TEMPORARY SLOPE DRAINS	80 LF		
0063	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0064	6029000000-E	SP	SAFETY FENCE	350 LF		
0065	6030000000-E	1630	SILT EXCAVATION	3,250 CY		
0066	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,400 SY		
0067	6042000000-E	1632	1/4" HARDWARE CLOTH	50 LF		
0068	6070000000-N	SP	SPECIAL STILLING BASINS	12 EA		
0069	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0070	6087000000-E	1660	MOWING	3.5 ACR		
0071	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0072	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0073	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0074	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0075	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0076	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0077	6123000000-E	1670	REFORESTATION	0.5 ACR		
STRUCTURE ITEMS						
0078	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (23+91.00 -L-)	Lump Sum	L.S.	
0079	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (23+91.00-L-)	Lump Sum	L.S.	
0080	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	142.75 LF		
0081	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	38.5 LF		
0082	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	70 LF		
0083	8113000000-N	SP	SID INSPECTION	1 EA		
0084	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0085	8116000000-E	SP	CSL TUBES	785 LF		
0086	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (23+91.00-L-)	Lump Sum	L.S.	
0087	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	79.5 CY		
0088	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (23+91.00-L-)	Lump Sum	L.S.	
0089	8217000000-E	425	REINFORCING STEEL (BRIDGE)	26,290 LB		
0090	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	5,248 LB		
0091	8364000000-E	450	HP12X53 STEEL PILES	490 LF		

County : Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0092	8503000000-E	460	CONCRETE BARRIER RAIL	270.21 LF		
0093	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	600 TON		
0094	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	667 SY		
0095	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0096	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,486.15 LF		

1556/Jul13/Q98161.61/D421451080000/E96

Total Amount Of Bid For Entire Project :

C201185 (B-3899)
COUNTY: Rockingham County

2/16/99

Contract No: C201185
County: Rockingham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General

Signature Sheet (Bid - Acceptance by Department)