

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

# SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201184

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	600	CY	UNDERCUT EXCAVATION
0080000000-E	SP	50	TON	CLASS IV SUBGRADE STABILIZA-TION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	16	TON	FOUNDATION CONDITIONING MATE-RIAL, MINOR STRS
0343000000-E	310	80	LF	15" SIDE DRAIN PIPE
0344000000-E	310	40	LF	18" SIDE DRAIN PIPE
0706000000-E	310	24	LF	12" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0805000000-E	310	2	EA	12" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	380	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	290	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	36	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	280	LF	SHOULDER BERM GUTTER
3030000000-E	862	650	LF	STEEL BM GUARDRAIL
3045000000-E	862	37.5	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3270000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350

ItemNumber	Sec #	Quantity	Unit	Description
3649000000-E	876	7	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	172	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	418	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	169	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	20	EA	DRUMS
4435000000-N	1135	20	EA	CONES
4446100000-E	SP	132	LF	BARRICADES (TYPE III)
4810000000-E	1205	10,400	LF	PAINT PAVEMENT MARKING LINES (4")
6000000000-E	1605	850	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	220	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	65	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEED-ING
6024000000-E	1622	250	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	6	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	350	LF	SAFETY FENCE
6030000000-E	1630	715	CY	SILT EXCAVATION
6036000000-E	1631	900	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	20	LF	1/4" HARDWARE CLOTH
6045000000-E	SP	150	LF	*** TEMPORARY PIPE (24")
6069000000-E	1638	330	CY	STILLING BASINS
6084000000-E	1660	2	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING

ItemNumber	Sec #	Quantity	Unit	Description
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.25	TON	FERTILIZER TOPDRESSING
6111000000-E	SP	45	LF	IMPERVIOUS DIKE
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL