



PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1 1/4" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 137 1/2 LBS. PER SQ. YD.
C2	PROP. APPROX. 2 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 137 1/2 LBS. PER SQ. YD. IN EACH OF TWO LAYERS
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE SF9.5A, AT AN AVERAGE RATE OF 110 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 1" OR GREATER THAN 1 1/2" IN DEPTH.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E2	PROP. APPROX. 4 1/2" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 513 LBS. PER SQ. YD.
E3	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5 1/2" IN DEPTH.
R	SHOULDER BERM GUTTER.
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
W	VARIABLE DEPTH ASPHALT PAVEMENT (SEE WEDGING DETAIL)

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.




Detail Showing Paved Shoulder in Relation to Guardrail

USE SHOULDER BERM GUTTER FOR THE FOLLOWING:  
LEFT SHOULDER -L- STA 14+97.00 TO -L- STA. 17+74.00




TYPICAL SECTION NO. 1

USE TYPICAL SECTION NO. 1 FOR THE FOLLOWING:  
-L- STA 12+50.00 TO -L- STA 13+50.00  
-L- STA 17+20.00 TO -L- STA 19+00.00




TYPICAL SECTION NO. 2

USE TYPICAL SECTION NO. 2 FOR THE FOLLOWING:  
-L- STA 13+50.00 TO -L- STA 17+20.00



Detail Showing Method of Wedging



TYPICAL SECTION NO. 3

USE TYPICAL SECTION NO. 3 FOR THE FOLLOWING:  
-DRIVE2- STA 10+00.00 TO -DRIVE2- STA. 11+93.40