

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
**SUMMARY OF QUANTITIES**

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS  
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201143

ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION	443500000-N	1135	30	EA	CONES
010600000-E	230	1,200	CY	BORROW EXCAVATION	445000000-N	1150	60	HR	FLAGGER
272400000-E	857	269	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED	446000000-N	1155	8	EA	WARNING LIGHTS (TYPE B)
303000000-E	862	64,550	LF	STEEL BM GUARDRAIL	448000000-N	1165	6	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
304500000-E	862	187.5	LF	STEEL BM GUARDRAIL, SHOP CURVED	608700000-E	1660	60	ACR	MOWING
315000000-N	862	40	EA	ADDITIONAL GUARDRAIL POSTS	611400000-N	SP	20	HR	SPECIALIZED HAND MOWING
318000000-N	862	27	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** (BP III)					
319500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1					
321000000-N	862	49	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1					
327000000-N	SP	111	EA	GUARDRAIL ANCHOR UNITS, TYPE 350					
328500000-N	SP	16	EA	GUARDRAIL ANCHOR UNITS, TYPE M-350					
331700000-N	862	5	EA	GUARDRAIL ANCHOR UNITS, TYPE B-77					
336000000-E	863	28,250	LF	REMOVE EXISTING GUARDRAIL					
342000000-E	SP	2,100	LF	GENERIC GUARDRAIL ITEM MEDIAN CABLE BARRIER (SOCKETED POST, WRSF)					
342000000-E	SP	2,100	LF	GENERIC GUARDRAIL ITEM REMOVE EXISTING CABLE GUIDERAIL					
343500000-N	SP	2	EA	GENERIC GUARDRAIL ITEM MEDIAN CABLE BARRIER ANCHOR (WRSF)					
343500000-N	SP	2	EA	GENERIC GUARDRAIL ITEM REMOVE & RESET GUARDRAIL ANCHOR UNIT, TYPE 350					
441210000-E	SP	2,376	SF	WORK ZONE SIGNS (PORTABLE)					
441500000-N	1115	6	EA	FLASHING ARROW PANELS, TYPE C					
442000000-N	1120	2	EA	CHANGEABLE MESSAGE SIGNS					
442500000-N	1125	8	EA	WARNING FLAG SETS					
443000000-N	1130	1,000	EA	DRUMS					

5/28/99

06 JAN-2005 16:4  
E:\ADouglas\p\rd-4404-rd-  
EADouglas