

PROJECT NO. Prim. Resurfacing 2CR.10741.3	SHEET NO. 7	TOTAL NO.
---	----------------	-----------

2CR.10741.3 - SUMMARY OF QUANTITIES

TREATMENT	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	PAY ITEM NUMBER														
								124500000-E SHOULDER RECONSTRUCTION SMI	129700000-E 2.5" MILLING SY	184000000-E MILLED RUMBLE STRIPS LF	133000000-E INCIDENTAL MILLING SY	149100000-E BASE COURSE, B25.0C TONS	150300000-E INTERMEDIATE COURSE, 119.0C TONS	152300000-E SURFACE COURSE, S9.5C TONS	156000000-E PG 64-22 PLANT MIX TONS	156500000-E PG 70-22 PLANT MIX TONS	170400000-E PATCHING EXISTING PAVEMENT TONS	608400000-E SEED & MULCHING AC	609000000-E SEED FOR REPAIR SEEDING LB	609300000-E FERTILIZER FOR REPAIR SEEDING TON	610800000-E FERTILIZER FOR TOPDRESSING TON	
Overlay 3"	Pitt	1	US 264	WESTBOUND FROM SR1467 TO SR 1419	1	5.5	32	11		58,080	540	6,074	2,381	19,379	373	1,163	300	11.00	120	0.38	8.00	
Overlay 3"		2	US 264	EASTBOUND LANE FROM US 264 TO THE BEGINNING OF TEST PAVEMENT	1	0.5	32	1		5,280	161	552	216	1,775	34	107	50	1.00	44	0.03	1.00	
Mill 2 1/2" / Fill 2 1/2" / Overlay 3"		3	US 264	EASTBOUND LANE FROM BEGIN TEST PAVEMENT TO END TEST PAVEMENT AT SR 1419	2	5	32	10	93,867	52,800	412	5,521	15,039	17,753	944	1,065	1,500	10.00	109	0.35	7.00	
Overlay 1 1/2"		4	US 264	WESTBOUND LANE FROM SR 1419 TO NC 11 (END 70 MPH)	3	1.5	32	3		15,840	127	1,656	649	2,632	102	158	100	3.00	33	0.09	3.00	
Overlay 1 1/2"		5	US 264	EASTBOUND LANE FROM SR 1419 TO NC 11 (END 70 MPH)	3	1.5	32	3		15,840	127	1,656	649	2,632	102	158	100	3.00	33	0.09	3.00	
Overlay 3"		6	US 264	RAMPS AT MP #73 (BEGIN BYPASS, SR 1467, STANTONSBURG RD.)	4	1.5	22	3		15,840				3,700		222	50	3.00	33	0.09	3.00	
Overlay 1 1/2"		7	US 264	RAMPS AT EXIT 75 (NC 43)	5	2	22							2,426		146	50	5.00	55	0.15	5.00	
Overlay 1 1/2"		8	US 264	RAMPS AT EXIT #77 (NC33)	5	2	22							2,426		146	50	5.00	55	0.15	5.00	
Overlay 1 1/2"		9	US 264	RAMPS AT EXIT 80 (NC 11)	5 & 8	2	22							2,426		146	50	4.00	44	0.12	4.00	
Overlay 1 1/2"		10	US 264	WESTBOUND LANE FROM NC 11 (EXIT 80) TO NC 33 (PACTOLUS HWY)	6	3.5	29				127			5,573		334	200	7.00	76	0.24	5.00	
Overlay 1 1/2"		11	US 264	EASTBOUND LANE FROM NC 11 (EXIT 80) TO US 264/NC 33 (PACTOLUS HWY.)	6	3.5	29				127			5,573		334	200	7.00	76	0.24	5.00	
Overlay 1 1/2"		12	US 264	SIGNALIZED INTERSECTION AT DSM	7	0.15	24							198		12						
Overlay 1 1/2"		13	US 264	SIGNALIZED INTERSECTION AT SR 1579 (OVERTON'S)	7	0.15	36							296		18						
Overlay 1 1/2"		14	US 264	SIGNALIZED INTERSECTION AT GRADY WHITE	7	0.15	12							101		6						
Overlay 1 1/2"		15	US 264	SIGNALIZED INTERSECTION AT OLD CREEK	7	0.15	24							198		12						
Overlay 1 1/2"		16	US 264	SIGNALIZED INTERSECTION AT US 264/NC 33 PACTOLUS HWY.	7	0.15	24							198		12						
Overlay 1 1/2"		17	US 264	5 CROSSOVERS WITH LEFT TURN LANES LOCATED BETWEEN DSM & WHICHARDS RD.	N/A	0.5	12							335		20						
Overlay 1 1/2"		18	US 264	INTERSECTION OF WHICHARD RD. (SR 1523)	7	0.15	24							198		12						
TOTAL FOR EACH PAY ITEM NUMBER						10.50			31	93,867	163,680	1,621	15,459	18,934	67,819	1,555	4,071	2,650	59	678	1.93	49