

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (35+66.50)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	3,000 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	2,000 TON		
0008	0106000000-E	230	BORROW EXCAVATION	17,000 CY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	3,000 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	3,500 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	105 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	808 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	16 LF		
0014	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	140 LF		
0015	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	10 EA		
0016	0995000000-E	340	PIPE REMOVAL	236 LF		
0017	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0018	1330000000-E	607	INCIDENTAL MILLING	930 SY		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	5,200 TON		
0020	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	2,000 TON		
0021	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	3,375 TON		
0022	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	318 TON		
0023	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	203 TON		
0024	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	100 TON		
0025	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	2 EA		
0026	2253000000-E	840	PIPE COLLARS	0.45 CY		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	16 EA		
0028	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	3 LF		
0029	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	4 EA		
0030	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	11 EA		
0031	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0032	2556000000-E	846	SHOULDER BERM GUTTER	285 LF		
0033	2570000000-N	SP	MODIFIED CONCRETE FLUME	1 EA		
0034	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	660 LF		
0035	2619000000-E	850	4" CONCRETE PAVED DITCH	9 SY		
0036	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0038	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0039	2905000000-N	859	CONVERT EXISTING DROP INLET TO JUNCTION BOX	1 EA		
0040	3030000000-E	862	STEEL BM GUARDRAIL	2,112.5 LF		
0041	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
0042	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0043	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0044	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	1 EA		
0045	3285000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE M-350	4 EA		
0046	3319000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-83	4 EA		
0047	3345000000-E	864	REMOVE & RESET EXISTING GUARDRAIL	1,200 LF		
0048	3360000000-E	863	REMOVE EXISTING GUARDRAIL	1,650 LF		
0049	3595000000-E	869	RELAPPING GUARDRAIL	390 LF		
0050	3649000000-E	876	PLAIN RIP RAP, CLASS B	10 TON		
0051	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	1,035 SY		
0052	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	2,060 SF		
0053	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	562 SF		
0054	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	68 SF		
0055	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0057	4430000000-N	1130	DRUMS	224 EA		
0058	4446100000-E	SP	BARRICADES (TYPE III)	232 LF		
0059	4460000000-N	1155	WARNING LIGHTS (TYPE B)	5 EA		
0060	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2 EA		
0061	4485000000-E	1170	PORTABLE CONCRETE BARRIER	2,100 LF		
0062	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	700 LF		
0063	4510000000-N	SP	POLICE	100 HR		
0064	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARKING LINES (4")	3,439 LF		
0065	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	966 EA		
0066	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	41,710 LF		
0067	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	800 LF		
0068	4847000000-E	SP	POLYUREA PAVEMENT MARKING LINES (4")	14,930 LF		
0069	4847110000-E	SP	POLYUREA PAVEMENT MARKING LINES (8")	400 LF		
0070	4847140000-E	SP	POLYUREA PAVEMENT MARKING LINES (24")	40 LF		
0071	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	7,425 LF		
0072	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	400 LF		
0073	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	103 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	6 TON		
0075	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (II)	6 TON		
0076	5396000000-E	1510	*** DI RESTRAINED JOINT WATER PIPE, CLASS ***** (12,50)	118 LF		
0077	5402000000-E	1510	DI RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP	1,490 LB		
0078	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#)	2 EA		
0079	5636000000-E	1510	12" TRANSITION COUPLING, ***** (CI TO DI)	2 EA		
0080	5888000000-E	SP	GENERIC UTILITY ITEM 16" HDPE WATER PIPE, DR 9, 200# WP BY DIRECTIONAL BORE	907 LF		
0081	6000000000-E	1605	TEMPORARY SILT FENCE	1,400 LF		
0082	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	250 TON		
0083	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	350 TON		
0084	6012000000-E	1610	SEDIMENT CONTROL STONE	500 TON		
0085	6015000000-E	1615	TEMPORARY MULCHING	5.5 ACR		
0086	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0087	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.75 TON		
0088	6024000000-E	1622	TEMPORARY SLOPE DRAINS	140 LF		
0089	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	4 EA		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	6029000000-E	SP	SAFETY FENCE	1,250 LF		
0091	6030000000-E	1630	SILT EXCAVATION	1,600 CY		
0092	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0093	6042000000-E	1632	1/4" HARDWARE CLOTH	500 LF		
0094	6070000000-N	SP	SPECIAL STILLING BASINS	10 EA		
0095	6084000000-E	1660	SEEDING & MULCHING	10.5 ACR		
0096	6087000000-E	1660	MOWING	3.5 ACR		
0097	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0098	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0099	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0100	6108000000-E	1665	FERTILIZER TOPDRESSING	4.5 TON		
0101	6114000000-N	SP	SPECIALIZED HAND MOWING	5 HR		
0102	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
<b>STRUCTURE ITEMS</b>						
0103	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (38+66.50-L-)	Lump Sum	L.S.	
0104	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (38+66.50-L-)	Lump Sum	L.S.	
0105	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	209.2 LF		
0106	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	80 LF		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	221.2 LF		
0108	8113000000-N	SP	SID INSPECTION	5 EA		
0109	8114000000-N	SP	SPT TESTING	10 EA		
0110	8115000000-N	SP	CROSSHOLE SONIC LOGGING	5 EA		
0111	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (38+66.50-L-)	Lump Sum	L.S.	
0112	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	25,620 SF		
0113	8161000000-E	420	GROOVING BRIDGE FLOORS	22,896 SF		
0114	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	272.2 CY		
0115	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (38+66.50-L-)	Lump Sum	L.S.	
0116	8217000000-E	425	REINFORCING STEEL (BRIDGE)	56,946 LB		
0117	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	7,244 LB		
0118	8259000000-E	430	36" PRESTRESSED CONCRETE GIR- DERS	3,231.67 LF		
0119	8364000000-E	450	HP12X53 STEEL PILES	540 LF		
0120	8384000000-E	450	HP14X73 STEEL PILES	1,890 LF		
0121	8391000000-N	450	STEEL PILE POINTS	56 EA		
0122	8406000000-N	SP	GALVANIZING STEEL PILES AT STA ***** (38+66.50-L-)	Lump Sum	L.S.	
0123	8503000000-E	460	CONCRETE BARRIER RAIL	1,313.83 LF		
0124	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	610 TON		

County : Anson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0125	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	680 SY		
0126	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0127	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0128	8897000000-N	SP	GENERIC STRUCTURE ITEM PDA ASSISTANCE	5 EA		
0129	8897000000-N	SP	GENERIC STRUCTURE ITEM PDA TESTING	5 EA		

1046/Dec15/Q257133.05/D591574930000/E129

Total Amount Of Bid For Entire Project :



C201365 (B-4009)  
COUNTY: Anson

2/16/99

Contract No: C201365  
County: Anson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General