

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	170 TON		
0007	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,580 LF		
0008	1121000000-E	520	AGGREGATE BASE COURSE	1,050 TON		
0009	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
001C	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	69,340 SY		
0011	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	710 SY		
0012	1330000000-E	607	INCIDENTAL MILLING	1,250 SY		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	675 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	240 TON		
0015	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	6,420 TON		
0016	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	41 TON		
0017	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	386 TON		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
001S	1704000000-E	SP	PATCHING EXISTING PAVEMENT	25 TON		
002C	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	27 EA		
0021	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	11 EA		
0022	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0023	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	3 EA		
0024	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	6 EA		
002E	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0026	2440000000-N	840	CONCRETE APRON FOR CATCH BASIN	7 EA		
0027	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	11 EA		
002E	2507000000-E	842	BRICK MASONRY RETAINING WALLS	36 CY		
002S	2535000000-E	846	***X *** CONCRETE CURB (8" X 18")	150 LF		
003C	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	7,410 LF		
0031	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,350 LF		
0032	2591000000-E	848	4" CONCRETE SIDEWALK	75 SY		
0033	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	27 SY		
0034	2612000000-E	848	6" CONCRETE DRIVEWAY	95 SY		
003E	2647000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)	2,250 SY		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2830000000-N	858	ADJUSTMENT OF MANHOLES	19 EA		
0037	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	25 EA		
003E	2860000000-N	859	CONVERT EXISTING CATCH BASIN TO JUNCTION BOX	1 EA		
003E	3030000000-E	862	STEEL BM GUARDRAIL	687.5 LF		
004C	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0041	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	4 EA		
0042	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
004E	3375000000-E	SP	REMOVE & STOCKPILE EXISTING GUARDRAIL	687.5 LF		
0044	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	504 SF		
004E	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	320 SF		
004E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	1 EA		
0047	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
004E	4430000000-N	1130	DRUMS	763 EA		
004E	4446100000-E	SP	BARRICADES (TYPE III)	36 LF		
005C	4460000000-N	1155	WARNING LIGHTS (TYPE B)	2 EA		
0051	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	1 EA		
0052	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	344 EA		
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	148,082 LF		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,538	LF	
005E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	64	EA	
005E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	226	EA	
0057	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	117,390	LF	
005E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	702	LF	
005E	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	40	EA	
006C	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	104	EA	
0061	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	18	EA	
0062	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	575	EA	
0063	4950000000-N	1267	FLEXIBLE DELINEATORS (YELLOW & RED)	26	EA	
0064	6000000000-E	1605	TEMPORARY SILT FENCE	543	LF	
006E	6012000000-E	1610	SEDIMENT CONTROL STONE	8	TON	
006E	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50	LB	
0067	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.1	TON	
006E	6042000000-E	1632	1/4" HARDWARE CLOTH	2,100	LF	
006E	6084000000-E	1660	SEEDING & MULCHING	0.35	ACR	
007C	6090000000-E	1661	SEED FOR REPAIR SEEDING	25	LB	
0071	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.13	TON	

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	6900000000-E	SP	TOPSOIL	3,784 CY		
0073	7060000000-E	1705	SIGNAL CABLE	685 LF		
0074	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	7 EA		
0075	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2 EA		
0076	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	2 EA		
0077	7264000000-E	1710	MESSENGER CABLE (3/8")	480 LF		
0078	7279000000-E	1715	TRACER WIRE	150 LF		
0079	7288000000-E	1715	TRENCHING (PAVED)	30 LF		
0080	7300000000-E	1715	TRENCHING (UNPAVED)	615 LF		
0081	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 1)	150 LF		
0082	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	6 EA		
0083	7336000000-N	1716	JUNCTION BOX (OVER-SIZED)	2 EA		
0084	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	1 EA		
0085	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	1,220 LF		
0086	7456000000-E	1726	LEAD-IN CABLE	1,320 LF		
0087	7528000000-E	1730	DROP CABLE	1,825 LF		
0088	7540000000-N	1731	AERIAL SPLICE ENCLOSURE	1 EA		
0089	7552000000-N	1731	INTERCONNECT CENTER	1 EA		
0090	7566000000-N	1733	DELINEATOR MARKER	2 EA		

County : Cumberland

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0091	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORATION KIT	1	EA	
0092	7576000000-N	1740	METAL STRAIN SIGNAL POLE	4	EA	
0093	7613000000-N	SP	SOIL TEST	4	EA	
0094	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1	EA	
0095	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1	EA	
0096	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	5	EA	
0097	7980000000-N	SP	GENERIC SIGNAL ITEM CABINET BASE EXTENDER	1	EA	
0098	7980000000-N	SP	GENERIC SIGNAL ITEM FIBER-OPTIC TRANSCEIVER, SELF HEALING RING	1	EA	
0099	7992000000-E	SP	GENERIC SIGNAL ITEM DRILLED PIER FOUNDATION	48	CY	

1559/Dec14/Q378827.58/D432663700000/E99

Total Amount Of Bid For Entire Project :

C201259 (U-4719)
COUNTY: Cumberland

2/16/99

Contract No: C201259
County: Cumberland

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General