



| PAVEMENT SCHEDULE | |
|-------------------|--|
| C | PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD. |
| C-1 | PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, TO BE APPLIED AT AN AVERAGE RATE OF 168 LBS PER SQ YD. |
| C-2 | ASPHALT CONCRETE SURFACE COURSE, TYPE S 9.5B, LEVELING COURSE, TO BE APPLIED AT A VARIABLE RATE, TO BE DETERMINED BY THE ENGINEER. |
| M | MILLING ASPHALT PAVEMENT, 1.5" DEPTH, FULL WIDTH |
| M-1 | MILLING ASPHALT PAVEMENT, 0" TO 1.5" DEPTH |