TIP PROJECT: B-3652

CONTRACT: C201181

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

STATE PROJECT REFERENCE NO.		SHEET NO.
B-3652		TCP-1
STATE WBS NO.	F.A. PROJ. NO.	DESCRIPTION
33198.3.1	BRSTP-4121(2)	CONST.

PLAN FOR PROPOSED TRAFFIC CONTROL, MARKING & DELINEATION

GUILFORD COUNTY

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS"-ROADWAY DESIGN UNIT-N.C. DEPARTMENT OF TRANSPORTATION-RALEIGH, N.C., DATED JANUARY 2002 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1101.02	TEMPORARY LANE CLOSURES
1101.03	TEMPORARY ROAD CLOSURES
1101.11	TRAFFIC CONTROL DESIGN TABLES
1110.01	STATIONARY WORK ZONE SIGNS
1110.02	PORTABLE WORK ZONE SIGNS
1135.01	CONES
1150.01	FLAGGERS
1160.01	TEMPORARY CRASH CUSHION
1165.01	TRUCK MOUNTED IMPACT ATTENUATOR
1170.01	PORTABLE CONCRETE BARRIER
1205.01	PAVEMENT MARKINGS - LINE TYPES & OFFSETS
1205.02	PAVEMENT MARKINGS - 2 LANE & MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.12	PAVEMENT MARKINGS - BRIDGES
1250.01	PAVEMENT MARKER SPACING
1251.01	RAISED PAVEMENT MARKERS (TEMPORARY & PERMANENT)
1261.01	GUARDRAIL & BARRIER DELINEATOR SPACING
1261.02	GUARDRAIL & BARRIER DELINEATOR TYPES
1262.01	GUARDRAIL END DELINEATION

INDEX OF SHEETS

SHEET NO.	TITLE
TCP-1	LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, LEGEND, AND INDEX OF SHEETS
TCP-2	GENERAL NOTES
TCP-3	PHASING AND TEMP. PAVEMENT MARKING SCHEDULE
TCP-4	PHASE I & PHASE II
TCP-5	PHASE III
TCP-6	REPLACEMENT DETAIL FOR RSD DRAWING 1130.01
TCP-7	DETAIL FOR TWO-WAY UNDIVIDED WORK ZONE SIGNS
TCP-8	REPLACEMENT DETAIL FOR RSD DRAWING 1145.01
TCP-9	REPLACEMENT DETAIL FOR RSD DRAWING 1101.04
PM-1	FINAL PAVEMENT MARKING SCHEDULE
PM-2	FINAL PAVEMENT MARKING PLAN

LEGEND

GENERAL

- DIRECTION OF TRAFFIC FLOW
- NORTH ARROW
- PROPOSED PVMT. --------- EXIST. PVMT.
- WORK AREA
- REMOVAL OF EXISTING PAVEMENT

TRAFFIC CONTROL DEVICES

- TYPE I BARRICADE
- TYPE II BARRICADE
- TYPE III BARRICADE
- CONE
- DRUM
- FLASHING ARROW PANEL (TYPE C)
- TYPE 'B' WARNING LIGHT
- STATIONARY SIGN
- PORTABLE SIGN
- STATIONARY OR PORTABLE SIGN
- WARNING FLAGS
- CRASH CUSHION
- CHANGEABLE MESSAGE SIGN
- TRUCK MOUNTED IMPACT ATTENUATOR (TMIA)
- POLICE
- FLAGGER

PAVEMENT MARKINGS

- CRYSTAL/CRYSTAL PAVEMENT MARKER
- YELLOW/YELLOW PAVEMENT MARKER
- CRYSTAL/RED PAVEMENT MARKER
- PAVEMENT MARKING SYMBOLS

PLAN REVIEWED BY: N.C.D.O.T. TRAFFIC CONTROL, MARKING & DELINEATION SECTION

J. STUART BOURNE, PE	TRAFFIC CONTROL ENGINEER
JOSEPH ISHAK, PE	TRAFFIC CONTROL PROJECT ENGINEER
BETSY WATSON, PE	TRAFFIC CONTROL PROJECT DESIGN ENGINEER
JOE FUTRELL	TRAFFIC CONTROL DESIGN ENGINEER

APPROVED: _____
DATE: _____

SEAL — NORTH CAROLINA PROFESSIONAL SEAL 20104 ENGINEER SEPEHR S. ASERNIA — 12-6-04

PLAN PREPARED FOR N.C.D.O.T. BY: SEPI ENGINEERING GROUP
2300 Rexwoods Drive, Suite 370, Raleigh, NC 27607, Tel:919-789-9977 Fax:789-9591

R.L. WEBBER	PROJECT ENGINEER
N. HARRIS	DESIGN ENGINEER

$$$$$SYSTIME$$$$
$$$$$DGN$$$$
$$$$$USERNAME$$$$