

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (22+00.00)	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0007	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	100 TON		
0008	0106000000-E	230	BORROW EXCAVATION	9,300 CY		
0009	0134000000-E	240	DRAINAGE DITCH EXCAVATION	312 CY		
0010	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0011	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0012	0206000000-E	SP	TEMPORARY SHORING - BARRIER SUPPORTED	620 SF		
0013	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	99 TON		
0014	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	248 LF		
0015	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	76 LF		
0016	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56 LF		
0017	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	556 LF		
0018	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	4 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	6	EA	
0020	0995000000-E	340	PIPE REMOVAL	356	LF	
0021	1121000000-E	520	AGGREGATE BASE COURSE	900	TON	
0022	1220000000-E	545	INCIDENTAL STONE BASE	200	TON	
0023	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	370	TON	
0024	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	620	TON	
0025	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	770	TON	
0026	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	92	TON	
0027	2022000000-E	815	SUBDRAIN EXCAVATION	33.6	CY	
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	25.2	CY	
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	150	LF	
0030	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	6	EA	
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1	EA	
0032	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6	LF	
0033	2253000000-E	840	PIPE COLLARS	0.5	CY	
0034	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	9	EA	
0035	2355000000-N	840	FRAME WITH GRATE, STD 840.29	3	EA	
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	2	EA	

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	3 EA		
0038	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	470 LF		
0039	2556000000-E	846	SHOULDER BERM GUTTER	290 LF		
0040	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	14 SY		
0041	2738000000-E	SP	GENERIC PAVING ITEM BRICK PAVER SIDEWALK	240 SY		
0042	2995000000-N	SP	GENERIC DRAINAGE ITEM ADJUSTMENT OF JUNCTION BOX	1 EA		
0043	3030000000-E	862	STEEL BM GUARDRAIL	537.5 LF		
0044	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0045	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	5 EA		
0046	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	5 EA		
0047	3360000000-E	863	REMOVE EXISTING GUARDRAIL	606 LF		
0048	3649000000-E	876	PLAIN RIP RAP, CLASS B	192 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	955 SY		
0050	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
0051	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (D)	24.33 SF		
0052	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	52.66 SF		
0053	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	254 LF		
0054	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	4102000000-N	904	SIGN ERECTION, TYPE E	13 EA		
0056	4129000000-N	906	RELOCATE SIGN, TYPE ***** (D)	2 EA		
0057	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	16 EA		
0058	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	142 SF		
0059	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	112 SF		
0060	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	36 SF		
0061	4430000000-N	1130	DRUMS	21 EA		
0062	4435000000-N	1135	CONES	30 EA		
0063	4446100000-E	SP	BARRICADES (TYPE III)	96 LF		
0064	4455000000-N	1150	FLAGGER	200 MD		
0065	4460000000-N	1155	WARNING LIGHTS (TYPE B)	2 EA		
0066	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0067	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (45 MPH)	1 EA		
0068	4485000000-E	1170	PORTABLE CONCRETE BARRIER	180 LF		
0069	4615000000-E	1205	REMOVABLE TAPE PAVEMENT MARK- ING LINES (4")	900 LF		
0070	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	105 EA		
0071	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,300 LF		
0072	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,763 LF		
0073	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	200 LF		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	44 LF		
0075	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	6 EA		
0076	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,953 LF		
0077	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	200 LF		
0078	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	64 LF		
0079	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	690 LF		
0080	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	48 EA		
0081	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	200 TON		
0082	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	150 TON		
0083	5312000000-E	1505	SELECT BACKFILL MATERIAL, UTILITIES CLASS **** (II)	200 TON		
0084	5360000000-E	1510	6" DI WATER PIPE, PC 350	20 LF		
0085	5396000000-E	1510	*** DI RESTRAINED JOINT WATER PIPE, CLASS ***** (36", 53)	230 LF		
0086	5402000000-E	1510	DI RESTRAINED JOINT WATER PIPE FITTINGS, 250# MIN WP	10,195 LB		
0087	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#)	1 EA		
0088	5564000000-E	SP	*** BUTTERFLY VALVE & VALVE BOX (36")	1 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	5612000000-E	1510	*** TRANSITION COUPLING, ***** (36", CI TO DI)	2 EA		
0090	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	1 EA		
0091	5690000000-E	1520	*** PVC SEWER PIPE, SDR ** (4", SDR 35)	30 LF		
0092	5768000000-N	1520	SANITARY SEWER CLEAN-OUT	2 EA		
0093	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (12", PVC WATER)	480 LF		
0094	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (30", CI WATER)	190 LF		
0095	5848000000-E	1540	**** STEEL ENCASMENT PIPE, **** THICK, BY TRENCHLESS METHOD (54", 0.563")	90 LF		
0096	5888000000-E	SP	GENERIC UTILITY ITEM 12" DI RESTRAINED JOINT, WATER PIPE, PC 350	672 LF		
0097	6000000000-E	1605	TEMPORARY SILT FENCE	1,100 LF		
0098	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
0099	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	400 TON		
0100	6012000000-E	1610	SEDIMENT CONTROL STONE	330 TON		
0101	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0102	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0103	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0104	6024000000-E	1622	TEMPORARY SLOPE DRAINS	185 LF		
0105	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0106	6029000000-E	SP	SAFETY FENCE	375 LF		
0107	6030000000-E	1630	SILT EXCAVATION	2,600 CY		
0108	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,175 SY		
0109	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	720 SY		
0110	6042000000-E	1632	1/4" HARDWARE CLOTH	160 LF		
0111	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		
0112	6084000000-E	1660	SEEDING & MULCHING	3.8 ACR		
0113	6087000000-E	1660	MOWING	1.5 ACR		
0114	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0115	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0116	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0117	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0118	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0119	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	12 EA		
0120	6123000000-E	1670	REFORESTATION	0.4 ACR		
0121	6147000000-E	SP	GENERIC EROSION CONTROL ITEM TREE PROTECTION FENCE	935 LF		
0122	6685000000-E	SP	GENERIC PLANTING ITEM WATER FOR EXISTING TREES	20 M/G		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>STRUCTURE ITEMS</b>						
0123	8007000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (21+87.50 -L-)	Lump Sum	L.S.	
0124	8017000000-N	SP	CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP ACCESS AT STA ***** (21+87.50 -L-)	Lump Sum	L.S.	
0125	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (21+87.50 -L-)	Lump Sum	L.S.	
0126	8105560000-E	SP	4'-0" DIA DRILLED PIERS IN SO IL	87.3 LF		
0127	8105660000-E	SP	4'-0" DIA DRILLED PIERS NOT IN SOIL	55 LF		
0128	8111600000-E	SP	PERMANENT STEEL CASING FOR 4'-0" DIA DRILLED PIER	94.3 LF		
0129	8113000000-N	SP	SID INSPECTION	2 EA		
0130	8115000000-N	SP	CROSSHOLE SONIC LOGGING	1 EA		
0131	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (21+87.50 -L-)	Lump Sum	L.S.	
0132	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	10,819 SF		
0133	8161000000-E	420	GROOVING BRIDGE FLOORS	10,817 SF		
0134	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	181.3 CY		
0135	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (21+87.50 -L-)	Lump Sum	L.S.	
0136	8217000000-E	425	REINFORCING STEEL (BRIDGE)	43,558 LB		
0137	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	6,498 LB		
0138	8265000000-E	430	54" PRESTRESSED CONCRETE GIR- DERS	1,334.09 LF		



County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0139	8364000000-E	450	HP12X53 STEEL PILES	650 LF		
0140	8475000000-E	460	TWO BAR METAL RAIL	370.67 LF		
0141	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-2" X 2'-10")	192.83 LF		
0142	8517000000-E	460	1'-**X ***** CONCRETE PARA- PET (1'-2" X 3'-6 3/4")	192.83 LF		
0143	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	750 TON		
0144	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	834 SY		
0145	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0146	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	
0147	8727000000-N	SP	ELECTRICAL CONDUIT SYSTEM, STA ***** (21+87.50 -L-)	Lump Sum	L.S.	
0148	8741000000-N	SP	STRUCTURE DRAINAGE SYSTEM, STA ***** (21+87.50-L-)	Lump Sum	L.S.	

0947/Dec07/Q134455.81/D676909720000/E148

Total Amount Of Bid For Entire Project :

C201181  
COUNTY: Guilford

2/16/99

Contract No: C201181  
County: Guilford

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General