COMPUTED BY: CBH	DATE: 07.12.06
CHECKED BY: MTM	DATE: 07.15.06

PROJECT REFERENCE NO.	SHEET NO.
B-3847	3

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201479

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ********** (14+60 -L-)
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0080000000-E	SP	100	TON	CLASS IV SUBGRADE STABILIZATION
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	5	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0366000000-E	310	44	LF	15" RC PIPE CULVERTS, CLASS III
1489000000-E	610	120	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	140	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1519000000-E	610	780	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B
1560000000-E	620	61	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2000000000-N	806	8	EA	RIGHT OF WAY MARKERS
2022000000-E	815	25	CY	SUBDRAIN EXCAVATION
2033000000-E	815	20	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	100	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	3	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29

ItemNumber	Sec #	Quantity	Unit	Description
2556000000-E	846	38	LF	SHOULDER BERM GUTTER
3030000000-E	862	550	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3656000000-E	876	225	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4025000000-E	901	41.25	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	82	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	11	EA	SIGN ERECTION, TYPE E
4155000000-N	907	12	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4412000000-E	SP	443	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	63	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	4	EA	WARNING FLAG SETS
4430000000-N	1130	43	EA	DRUMS
4446100000-E	SP	48	LF	BARRICADES (TYPE III)
4450000000-N	1150	32	HR	FLAGGER
4685000000-E	1205	8,740	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4686000000-E	1205	8,740	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
6000000000-E	1605	1,280	LF	TEMPORARY SILT FENCE
6006000000-E	1610	115	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	35	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1	ACR	TEMPORARY MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6029000000-E	SP	350	LF	SAFETY FENCE
6030000000-E	1630	45	CY	SILT EXCAVATION
6036000000-E	1631	150	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	50	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	1	ACR	SEEDING & MULCHING
6087000000-E	1660	0.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	0.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

7/12/2005
11:10:56
H:\Roadway\Proj\b3847_rdy_sum.dgn