

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201253														
ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description	ItemNumber	Sec #	Quantity	Unit	Description
000010000-N	800	Lump Sum		MOBILIZATION	205400000-E	815	3	EA	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS	468500000-E	1205	2,700	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
004300000-N	226	Lump Sum		GRADING	206600000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	468600000-E	1205	2,700	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)
005000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING	207600000-E	815	6	LF	4" OUTLET PIPE (SUBDRAINS)	481000000-E	1205	10,800	LF	PAINT PAVEMENT MARKING LINES (4")
005700000-E	226	500	CY	UNDERCUT EXCAVATION	219000000-N	828	2	EA	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	490000000-N	1252	34	EA	PERMANENT RAISED PAVEMENT MARKERS
013400000-E	240	450	CY	DRAINAGE DITCH EXCAVATION	228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES	600000000-E	1605	520	LF	TEMPORARY SILT FENCE
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL	236700000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29	600600000-E	1610	115	TON	STONE FOR EROSION CONTROL, CLASS A
019600000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION	255600000-E	846	260	LF	SHOULDER BERM GUTTER	600900000-E	1610	380	TON	STONE FOR EROSION CONTROL, CLASS B
019900000-E	SP	525	SF	TEMPORARY SHORING	303000000-E	862	237.5	LF	STEEL BM GUARDRAIL	601200000-E	1610	100	TON	SEDIMENT CONTROL STONE
031800000-E	300	72	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS	601500000-E	1615	2	ACR	TEMPORARY MULCHING
034300000-E	310	140	LF	15" SIDE DRAIN PIPE	327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350	601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
034400000-E	310	200	LF	18" SIDE DRAIN PIPE	338700000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W-BEAM)	602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
037200000-E	310	332	LF	18" RC PIPE CULVERTS, CLASS III	362800000-E	876	36	TON	PLAIN RIP RAP, CLASS I	602900000-E	SP	460	LF	SAFETY FENCE
099500000-E	340	201	LF	PIPE REMOVAL	364900000-E	876	55	TON	PLAIN RIP RAP, CLASS B	603000000-E	1630	1,235	CY	SILT EXCAVATION
112100000-E	520	370	TON	AGGREGATE BASE COURSE	365600000-E	876	348	SY	FILTER FABRIC FOR DRAINAGE	603600000-E	1631	1,100	SY	MATting FOR EROSION CONTROL
122000000-E	545	250	TON	INCIDENTAL STONE BASE	441200000-E	SP	164	SF	WORK ZONE SIGNS (STATIONARY)	604200000-E	1632	20	LF	1/4" HARDWARE CLOTH
133000000-E	607	90	SY	INCIDENTAL MILLING	441210000-E	SP	180	SF	WORK ZONE SIGNS (PORTABLE)	606900000-E	1638	40	CY	STILLING BASINS
148900000-E	610	990	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B	441220000-E	SP	20	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)	608400000-E	1660	2.5	ACR	SEEDING & MULCHING
149800000-E	610	690	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	443000000-N	1130	170	EA	DRUMS	608700000-E	1660	1.5	ACR	MOWING
151900000-E	610	800	TON	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	443500000-N	1135	46	EA	CONES	609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
156000000-E	620	123	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	444610000-E	SP	48	LF	BARRICADES (TYPE III)	609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
169300000-E	654	50	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR	445000000-N	1150	2,200	HR	FLAGGER	609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
200000000-N	806	18	EA	RIGHT OF WAY MARKERS	445000000-N	1150	2,200	HR	FLAGGER	610800000-E	1665	1.75	TON	FERTILIZER TOPDRESSING
202200000-E	815	22.4	CY	SUBDRAIN EXCAVATION	446500000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS	611100000-E	SP	210	LF	IMPERVIOUS DIKE
203300000-E	815	16.8	CY	SUBDRAIN FINE AGGREGATE	448500000-E	1170	430	LF	PORTABLE CONCRETE BARRIER	611400000-N	SP	1	HR	SPECIALIZED HAND MOWING
204300000-E	815	100	LF	4" PERFORATED SUBDRAIN PIPE	465000000-N	1251	34	EA	TEMPORARY RAISED PAVEMENT MARKERS	611700000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
										612300000-E	1670	0.15	ACR	REFORESTATION

5/28/99

I:\NOV-2004\B2\Roadway\Proc\B3662.sum