

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB-BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	500 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	450 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	100 SY		
0009	0199000000-E	SP	TEMPORARY SHORING	525 SF		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	72 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	140 LF		
0012	0344000000-E	310	18" SIDE DRAIN PIPE	200 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	332 LF		
0014	0995000000-E	340	PIPE REMOVAL	201 LF		
0015	1121000000-E	520	AGGREGATE BASE COURSE	370 TON		
0016	1220000000-E	545	INCIDENTAL STONE BASE	250 TON		
0017	1330000000-E	607	INCIDENTAL MILLING	90 SY		
0018	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	990 TON		
0019	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	690 TON		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	800 TON		
0021	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	123 TON		
0022	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0023	2000000000-N	806	RIGHT OF WAY MARKERS	18 EA		
0024	2022000000-E	815	SUBDRAIN EXCAVATION	22.4 CY		
0025	2033000000-E	815	SUBDRAIN FINE AGGREGATE	16.8 CY		
0026	2043000000-E	815	4" PERFORATED SUBDRAIN PIPE	100 LF		
0027	2054000000-E	815	4" SUBDRAIN PIPE WYES, TEES, & ELBOWS	3 EA		
0028	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
0029	2076000000-E	815	4" OUTLET PIPE (SUBDRAINS)	6 LF		
0030	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	2 EA		
0031	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0032	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0033	2556000000-E	846	SHOULDER BERM GUTTER	260 LF		
0034	3030000000-E	862	STEEL BM GUARDRAIL	237.5 LF		
0035	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4 EA		
0037	3387000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (W- BEAM)	2 EA		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	3628000000-E	876	PLAIN RIP RAP, CLASS I	36	TON	
0039	3649000000-E	876	PLAIN RIP RAP, CLASS B	55	TON	
0040	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	348	SY	
0041	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	164	SF	
0042	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	180	SF	
0043	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	20	SF	
0044	4430000000-N	1130	DRUMS	170	EA	
0045	4435000000-N	1135	CONES	46	EA	
0046	4446100000-E	SP	BARRICADES (TYPE III)	48	LF	
0047	4450000000-N	1150	FLAGGER	2,200	HR	
0048	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0049	4485000000-E	1170	PORTABLE CONCRETE BARRIER	430	LF	
0050	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	34	EA	
0051	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,700	LF	
0052	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	2,700	LF	
0053	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,800	LF	
0054	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	34	EA	
0055	6000000000-E	1605	TEMPORARY SILT FENCE	520	LF	
0056	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	115	TON	

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	380 TON		
0058	6012000000-E	1610	SEDIMENT CONTROL STONE	100 TON		
0059	6015000000-E	1615	TEMPORARY MULCHING	2 ACR		
0060	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0061	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0062	6029000000-E	SP	SAFETY FENCE	460 LF		
0063	6030000000-E	1630	SILT EXCAVATION	1,235 CY		
0064	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,100 SY		
0065	6042000000-E	1632	1/4" HARDWARE CLOTH	20 LF		
0066	6069000000-E	1638	STILLING BASINS	40 CY		
0067	6084000000-E	1660	SEEDING & MULCHING	2.5 ACR		
0068	6087000000-E	1660	MOWING	1.5 ACR		
0069	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0070	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0071	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0072	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0073	6111000000-E	SP	IMPERVIOUS DIKE	210 LF		
0074	6114000000-N	SP	SPECIALIZED HAND MOWING	1 HR		
0075	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0076	6123000000-E	1670	REFORESTATION	0.15 ACR		

County : Henderson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
0077	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (18 + 28.00 -L-)	Lump Sum	L.S.	
0078	8126000000-N	414	CULVERT EXCAVATION, STA ***** (18 + 28.00 -L-)	Lump Sum	L.S.	
0079	8133000000-E	414	FOUNDATION CONDITIONING MATERIAL, BOX CULVERT	136 TON		
0080	8196000000-E	420	CLASS A CONCRETE (CULVERT)	205.7 CY		
0081	8245000000-E	425	REINFORCING STEEL (CULVERT)	39,762 LB		
1505/Dec13/Q71539.05/D299883900000/E81			Total Amount Of Bid For Entire Project :			

C201253
COUNTY: Henderson

2/16/99

Contract No: C201253
County: Henderson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General