

DIVISION OF HIGHWAYS
 STATE OF NORTH CAROLINA

SUMMARY OF EARTHWORK
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT+%	BORROW	WASTE
-L- 12+50.00 TO 21+50.00	527		2677	2150	
SUBTOTAL	527		2677	2150	
PROJECT TOTAL	527		2677	2150	
UNDERCUT AT GRADE POINTS	-11			11	
LOSS DUE TO CLEARING AND GRUBBING	-110			110	
5 % TO REPLACE BORROW				114	
TOTAL	406		2677	2385	
SAY	425			2400	

UNDERCUT EXCAVATION = 500 CY

SUMMARY OF PAVEMENT REMOVAL
 IN SQUARE YARDS

LOCATION	ASPHALT REMOVAL	ASPHALT BREAK UP	CONCRETE REMOVAL	CONCRETE BREAK UP
-L- 13+60 TO 14+10	71			
-L- 14+10 TO 16+95		570		
-L- 16+95 TO 20+52	210			
TOTAL	281	570		
SAY	290	590		

Note: Approximate quantities only. Unclassified Excavation, Shoulder Borrow, Fine Grading, Clearing and Grubbing, BORROW, Breaking of Existing Pavement and Removal of Existing Pavement will be paid for at the contract Lump Sum price for "Grading".

6/4/99
 5/27/2005 11:32:24 AM
 F:\Roadway\Proj\B3665_rdy_sum.dgn