

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS



SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201229

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0043000000-N	226	Lump Sum		GRADING
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0057000000-E	226	500	CY	UNDERCUT EXCAVATION
0080000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZATION
0134000000-E	240	335	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	45	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0343000000-E	310	60	LF	15" SIDE DRAIN PIPE
0344000000-E	310	60	LF	18" SIDE DRAIN PIPE
0366000000-E	310	152	LF	15" RC PIPE CULVERTS, CLASS III
0378000000-E	310	60	LF	24" RC PIPE CULVERTS, CLASS III
0732000000-E	310	52	LF	36" BIT COAT CS PIPE CULVERTS, TYPE B 0.079" THICK
0995000000-E	340	184	LF	PIPE REMOVAL
1220000000-E	545	100	TON	INCIDENTAL STONE BASE
1330000000-E	607	50	SY	INCIDENTAL MILLING
1489000000-E	610	340	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	350	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	37	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	65	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2022000000-E	815	112	CY	SUBDRAIN EXCAVATION
2033000000-E	815	84	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	500	LF	6" PERFORATED SUBDRAIN PIPE

ItemNumber	Sec #	Quantity	Unit	Description
2055000000-E	815	15	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	1	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	6	LF	6" OUTLET PIPE (SUBDRAINS)
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
2365000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.22
2367000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	275	LF	SHOULDER BERM GUTTER
3030000000-E	862	537.5	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3569000000-E	867	230	LF	BARBED WIRE FENCE RESET
3628000000-E	876	104	TON	PLAIN RIP RAP, CLASS I
3649000000-E	876	155	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	1,292	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4412000000-E	SP	255	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	32	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4435000000-N	1135	20	EA	CONES
4446100000-E	SP	96	LF	BARRICADES (TYPE III)
4450000000-N	1150	48	HR	FLAGGER
4810000000-E	1205	7,200	LF	PAINT PAVEMENT MARKING LINES (4")
6000000000-E	1605	730	LF	TEMPORARY SILT FENCE
6006000000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	200	TON	STONE FOR EROSION CONTROL, CLASS B

ItemNumber	Sec #	Quantity	Unit	Description
6012000000-E	1610	70	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	60	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	300	LF	SAFETY FENCE
6030000000-E	1630	640	CY	SILT EXCAVATION
6036000000-E	1631	465	SY	MATting FOR EROSION CONTROL
6042000000-E	1632	80	LF	1/4" HARDWARE CLOTH
6069000000-E	1638	200	CY	STILLING BASINS
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6111000000-E	SP	110	LF	IMPERVIOUS DIKE
6114000000-N	SP	1.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6120000000-E	SP	270	CY	CULVERT DIVERSION CHANNEL