

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+06.00)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	600 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	600 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	14 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	40 TON		
0011	0343000000-E	310	15" SIDE DRAIN PIPE	40 LF		
0012	0345000000-E	310	24" SIDE DRAIN PIPE	32 LF		
0013	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	224 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	44 LF		
0015	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	20 LF		
0016	0806000000-E	310	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2 EA		
0017	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	170 TON		
001E	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	340 TON		
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	30 TON		
0021	2022000000-E	815	SUBDRAIN EXCAVATION	112 CY		
0022	2033000000-E	815	SUBDRAIN FINE AGGREGATE	84 CY		
002E	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	500 LF		
0024	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
002E	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	1 EA		
002E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	6 LF		
0027	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	5 EA		
002E	2355000000-N	840	FRAME WITH GRATE, STD 840.29	4 EA		
002E	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
003C	2556000000-E	846	SHOULDER BERM GUTTER	405 LF		
0031	3030000000-E	862	STEEL BM GUARDRAIL	350 LF		
003E	3045000000-E	862	STEEL BM GUARDRAIL, SHOP CURVED	25 LF		
003E	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0034	3195000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE AT-1	2 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0037	3628000000-E	876	PLAIN RIP RAP, CLASS I	55 TON		
0038	3649000000-E	876	PLAIN RIP RAP, CLASS B	3 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	460 SY		
0040	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1 EA		
0041	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	230 SF		
0042	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	56 SF		
0043	4446100000-E	SP	BARRICADES (TYPE III)	96 LF		
0044	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	2,600 LF		
0045	6000000000-E	1605	TEMPORARY SILT FENCE	725 LF		
0046	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0047	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	180 TON		
0048	6012000000-E	1610	SEDIMENT CONTROL STONE	165 TON		
0049	6015000000-E	1615	TEMPORARY MULCHING	1 ACR		
0050	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0051	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0052	6029000000-E	SP	SAFETY FENCE	185 LF		
0053	6030000000-E	1630	SILT EXCAVATION	210 CY		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	6036000000-E	1631	MATTING FOR EROSION CONTROL	725 SY		
005E	6042000000-E	1632	1/4" HARDWARE CLOTH	80 LF		
005E	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0057	6084000000-E	1660	SEEDING & MULCHING	1 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
005E	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
006C	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0061	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0062	6108000000-E	1665	FERTILIZER TOPDRESSING	0.75 TON		
006E	6114000000-N	SP	SPECIALIZED HAND MOWING	1.5 HR		
0064	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
006E	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
006E	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (17+06.00 -L-)	Lump Sum	L.S.	
0067	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (17+06.00 -L-)	Lump Sum	L.S.	
006E	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	29.4 CY		
006E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (17+06.00 -L-)	Lump Sum	L.S.	
007C	8217000000-E	425	REINFORCING STEEL (BRIDGE)	4,824 LB		

County : Macon

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	8364000000-E	450	HP12X53 STEEL PILES	180 LF		
0072	8391000000-N	450	STEEL PILE POINTS	18 EA		
0073	8503000000-E	460	CONCRETE BARRIER RAIL	145.5 LF		
0074	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	230 TON		
0075	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	254 SY		
0076	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0077	8753000000-E	SP	3'-0" X 2'-3" PRESTRESSED CONC BOX BEAMS	800.25 LF		

1332/Dec06/Q17279.5/D311172400000/E77

Total Amount Of Bid For Entire Project :

C201508
COUNTY: Macon

2/16/99

Contract No: C201508
County: Macon

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General