

RAMP. TERMINAL SIGNS

NEAR TERMINAL

SHOULD ALSO BE PLACED

## **GENERAL NOTES**


ROAD

WORK

AHEAD

W20-1

- USE FLUORESCENT ORANGE SHEETING (TYPE VII OR HIGHER) ON ALL ADVANCED WORK ZONE SIGNS.
- DO NOT INSTALL ADVANCE WARNING SIGNS MORE THAN 3 DAYS PRIOR TO BEGINNING OF WORK.
- ALL SIGN SPACING DIMENSIONS ARE APPROXIMATE, FIELD ADJUST AS NECESSARY OR AS DIRECTED.
- USE PORTABLE WORK ZONE SIGNS ONLY WITH PORTABLE WORK ZONE SIGN STANDS SPECIFICALLY DESIGNED FOR ONE ANOTHER. PORTABLE WORK ZONE SIGNS MAY BE ROLL UP OR APPROVED COMPOSITE.
- PROVIDE PORTABLE WORK ZONE SIGN STANDS, PORTABLE SIGNS AND SIGN SHEETING WHICH ARE LISTED ON THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION'S APPROVED PRODUCT LIST OR ACCEPTED AS TRAFFIC QUALIFIED BY THE TRAFFIC CONTROL UNIT.
- \*\* TWO-WAY UNDIVIDED ADVANCE WARNING SIGN CONFIGURATION MAY BE USED ON MULTI-LANE FACILITIES WHERE CONDITIONS LIMIT THE USE OF DUAL MOUNTED SIGNS AS DETERMINED BY THE ENGINEER.



CONSTRUCTION

DUAL MOUNT SIGNS ON DIVIDED HIGHWAYS AND INCREASE SIGN SPACING TO 1000'+/-.

LIMITS

ROAD

WORK


AHEAD

W20-1

48"X48'

DETAIL DRAWING
FOR FREEWAYS
WORK ZONE WARNING SIG
SHORT-DURATION LANE CLOS

SHEET 1 OF 1



G20-2a

END

ROAD WORK

\\DOT\DFSROOTOO\\
\\DOT\DFSROOTOO\\
DSEVMORE AT W7TC206427

SIGN NOT REQUIRED IF ADVANCE WARNING SIGNS HAVE BEEN PLACED

ALONG -Y- LINE THAT RAMP INTERSECTS.
IF CONSTRUCTION LIMITS ARE AT END

OF RAMP, PLACE SIGN AT END OF RAMP.

END

ROAD WORK

G20-2a