

SUMMARY OF QUANTITIES

Work Order No	County/City	Map No	Route No/ Route Name	Description (To/From)	Typical No	Length	Width	Incidental Stone Base	Mill Asph Pvmnt, 1 1/2" Depth	Mill Asph Pvmnt, 0" to 1 1/2" Depth	ACIC Type I19.0C	ACSC Type S9.5B	ACSC Leveling Course Type S9.5B	ACSC Type S9.5C	PG 64-22 Plant Mix	PG 70-22 Plant Mix	Patching Existing Pavement	Adjust Drop Inlet	Adjust Manholes	Adjust Meter or Valve Box
						MI	FT		TONS	SY	SY	TONS	TONS	TONS	TONS	TONS	TONS	TONS	TONS	EA
9CR10801.4	Rowan	1	US 601 N Jake Alexander Blvd	Salisbury NCL to Pvmnt Jt at SR 2200 (W. Innes St)	6	0.536	24	21						714		43	10			
Total For Work Order No. 9CR10801.4						0.536		21	0	0	0	0	0	714	0	43	10	0	0	0
9CR.20801.4	Rowan	2	SR 2356 Old Beatty Ford Rd	Pvmnt Jt at US 52 to Pvmnt Jt at Island at SR 1004 (Stokes Ferry Rd)	1, 9	4.035	20	161				4,402	2,000		384		40			
		3	SR 1506 Shue Rd	China Grove NCL to Pvmnt Jt Before SR 1503 (Grace Church Rd)	1	2.448	22	98				2,936			176		60			
		4	SR 2561 Castor Rd	Pvmnt Jt at NC 152 to Pvmnt Jt at SR 1006 (Faith Rd)	1	2.012	22	80				2,413			145		30			
		5	SR 1221 Old Beatty Ford Rd	Pvmnt Jt at SR 1006 (Organ Church Rd) to New Pavement at SR 2335 (Lower Stone Church Rd)	1	1.736	20	69				1,894			114		45			
		6	SR 2004 Woodleaf Quarry Rd	Pvmnt Jt at NC 801 to Railroad Crossing	2, 8	0.845	26	51		289	1,893			1,223	89	74	40			
		7	SR 2312 Barringer St	Granite Quarry CL to SR 1006 (Faith Rd)	1	0.577	20	23	110	340		629			38		20		4	
		8	SR 2120 Long Ferry Rd	Spencer CL to I-85 Project Limits	1	0.420	19	17				435			26		25			1
Total For Work Order No. 9CR.20801.4						12.073		499	110	629	1,893	12,709	2,000	1,223	972	74	260	0	4	1
9CR.308008.4	Granite Quarry	10	SR 2312 Barringer St	SR 2313 (Peeler St) to Change in Pavement Width	1	0.400	18	20				436			26		20			
		10	SR 2312 Barringer St	Change in Pavement Width to Granite Quarry CL	1	0.152	20	8				166			10		10		2	
Total For Work Order No. 9CR.308008.4						0.552		28	0	0	0	602	0	0	36	0	30	0	2	0
9CR.308014.4	Salisbury	11	US 601 N Jake Alexander Blvd	End of Divided Roadway North of Woodleaf Rd to 2nd Salisbury NCL	6	1.215	24	49						2,006		120	50			
		11	US 601 SB N Jake Alexander Blvd	Divided Roadway from Just Past Woodleaf Rd to US 70	3	0.156	24							332		20	10		1	
		11	US 601 NB N Jake Alexander Blvd	Divided Roadway from US 70 to Just Past Woodleaf Rd	3	0.156	24	6						329		20	10	1	1	
Sub - Total For Map No 11						1.527		55	0	0	0	0	0	2,667	0	160	70	1	2	0
		12	SR 1002 Bringle Ferry Rd	EOP of SR 2100 (N Long Ferry Rd) to Pavement Joint Before Bridge #127 (I-85)	5	0.654	24					899		54		20		12	6	
		13	SR 2200 W Innes St	Pvmnt Jt at Lee St (NS) to Pvmnt Jt at US 29/70 (Main St)	7	0.088	66			1,200				315		19	12		4	8
		13	SR 2200 W Innes St	Pvmnt Jt at US 29/70 (Main St) to Divided Roadway at Church St (NS)	7	0.089	66			1,253				319		19	10		2	5
		13	SR 2200 W Innes St WB	Beg Divided Roadway at Church St (NS) to Jackson St (NS)	4	0.086	24		1,211					115		7	10			
		13	SR 2200 W Innes St WB	Jackson St (NS) Thru Int at Fulton St (NS)	4	0.085	22		1,097					127		8	10			
		13	SR 2200 W Innes St EB	Fulton St (NS) to Jackson St (NS)	4	0.085	22		1,097					124		8	10			
		13	SR 2200 W Innes St EB	Jackson St (NS) to Church St (NS)	4	0.086	24		1,211					115		7	10			
Sub - Total For Map No 13						0.519		0	4,616	2,453	0	0	0	1,115	0	68	62	0	6	13
Total For Work Order No. 9CR.308014.4						2.700		55	4,616	2,453	0	899	0	3,782	54	228	152	1	20	19
9CR.308015.4	Spencer	9	US 29/70/NC 150	SR 2120 (Long Ferry Rd) Pvmnt Jt to End of Curb & Gutter	6, 7	0.686	46			9,659				1,715		103	12			
		9	US 29/70/NC 150	End of Curb & Gutter to Spencer ECL	2	0.495	42	20						1,130		68	10			2
Total For Work Order No. 9CR.308015.4						1.181		20	0	9,659	0	0	0	2,845	0	171	22	0	0	2
GRAND TOTAL						17.042		623	4,726	12,741	1,893	14,210	2,000	8,564	1,062	516	474	1	26	22