

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	2,600 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	2,000 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	2,770 TON		
0007	0106000000-E	230	BORROW EXCAVATION	6,900 CY		
0008	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	200 SY		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	100 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	6,000 SY		
0011	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	610 TON		
0012	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	3,176 LF		
0013	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	512 LF		
0014	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	748 LF		
0015	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	344 LF		
0016	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	500 LF		
0017	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	452 LF		
0018	0995000000-E	340	PIPE REMOVAL	1,830 LF		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0020	1220000000-E	545	INCIDENTAL STONE BASE	1,000 TON		
0021	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	7,900 TON		
0022	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	6,600 TON		
0023	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	9,200 TON		
0024	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,210 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	640 TON		
0026	2000000000-N	806	RIGHT OF WAY MARKERS	41 EA		
0027	2022000000-E	815	SUBDRAIN EXCAVATION	210 CY		
0028	2033000000-E	815	SUBDRAIN FINE AGGREGATE	160 CY		
0029	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	900 LF		
0030	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	27 EA		
0031	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2 EA		
0032	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12 LF		
0033	2253000000-E	840	PIPE COLLARS	1 CY		
0034	2264000000-E	840	PIPE PLUGS	1 CY		
0035	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	58 EA		
0036	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	32 LF		
0037	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	20 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	3 EA		
0039	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	19 EA		
0040	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	12 EA		
0041	2396000000-N	840	FRAME WITH COVER, STD 840.54	4 EA		
0042	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	18 EA		
0043	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	8,300 LF		
0044	2612000000-E	848	6" CONCRETE DRIVEWAY	180 SY		
0045	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	1,660 SY		
0046	2830000000-N	858	ADJUSTMENT OF MANHOLES	8 EA		
0047	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	23 EA		
0048	3649000000-E	876	PLAIN RIP RAP, CLASS B	20 TON		
0049	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	650 SY		
0050	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	96 SF		
0051	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	264 SF		
0052	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
0053	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0054	4425000000-N	1125	WARNING FLAG SETS	2 EA		
0055	4430000000-N	1130	DRUMS	233 EA		
0056	4435000000-N	1135	CONES	34 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	4446100000-E	SP	BARRICADES (TYPE III)	120 LF		
0058	4450000000-N	1150	FLAGGER	240 HR		
0059	4475000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (45 MPH)	1 EA		
0060	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	10,970 LF		
0061	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	13,532 LF		
0062	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	338 LF		
0063	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	282 LF		
0064	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	70 EA		
0065	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	48,920 LF		
0066	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	338 LF		
0067	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	472 LF		
0068	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	2 EA		
0069	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	80 EA		
0070	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	385 EA		
0071	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (IV)	145.3 TON		
0072	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	145.3 TON		
0073	5318000000-E	1505	PAVEMENT REPAIR FOR UTILITY WORK	50 TON		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0074	5324000000-E	1510	*** DI WATER PIPE, CLASS ***** (16",CLASS 50)	525 LF		
0075	5330000000-E	1510	6" DI WATER PIPE, CLASS ***** (CLASS 50)	83 LF		
0076	5342000000-E	1510	12" DI WATER PIPE, CLASS ***** (CLASS 50)	1,697 LF		
0077	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	10 LF		
0078	5420000000-E	1510	1" COPPER WATER PIPE, TYPE K	7 LF		
0079	5480000000-E	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP	5,390 LB		
0080	5510000000-E	1510	3/4" CORPORATION STOP	1 EA		
0081	5516000000-E	1510	1" CORPORATION STOP	2 EA		
0082	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (16", 200#)	1 EA		
0083	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	6 EA		
0084	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#)	6 EA		
0085	5576000000-E	1510	***X*** TAPPING SLEEVE, VALVE & VALVE BOX, *****WP (12" X 6", 200# WP)	2 EA		
0086	5576000000-E	1510	***X*** TAPPING SLEEVE, VALVE & VALVE BOX, *****WP (16" X 12", 200# WP)	1 EA		
0087	5582000000-E	1510	***X*** TAPPING SADDLE (12" X 1")	1 EA		
0088	5582000000-E	1510	***X*** TAPPING SADDLE (12" X 3/4")	1 EA		
0089	5648000000-N	1510	RELOCATE EXISTING WATER METER	2 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0090	5666000000-E	1510	FIRE HYDRANT, *****# WP 200#	1 EA		
0091	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	5 EA		
0092	5702000000-E	1520	12" PVC SEWER PIPE, SDR ** (35)	374 LF		
0093	5776000000-E	1525	5' DIA PRECAST CONC SEWER MAN- HOLE 0-6' DEPTH	1 EA		
0094	5780000000-E	1525	PRECAST CONC MANHOLE WALL, *' DIA, OVER 6' HT (5')	9 LF		
0095	5804000000-E	1530	FILL OR REMOVE ABANDONED 12" PIPE, ***** DI WATER	1,487 LF		
0096	5804000000-E	1530	FILL OR REMOVE ABANDONED 12" PIPE, ***** PVC SEWER	405 LF		
0097	5810000000-E	1530	FILL OR REMOVE ABANDONED 16" PIPE, ***** DI WATER	510 LF		
0098	5822000000-N	1530	BREAK DOWN & REBUILD EXISTING MANHOLE	2 EA		
0099	5828000000-N	1530	REMOVE EXISTING MANHOLE	1 EA		
0100	6000000000-E	1605	TEMPORARY SILT FENCE	4,700 LF		
0101	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	300 TON		
0102	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	770 TON		
0103	6012000000-E	1610	SEDIMENT CONTROL STONE	590 TON		
0104	6015000000-E	1615	TEMPORARY MULCHING	5 ACR		
0105	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0106	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 TON		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0107	6024000000-E	1622	TEMPORARY SLOPE DRAINS	50 LF		
0108	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	2 EA		
0109	6029000000-E	SP	SAFETY FENCE	180 LF		
0110	6030000000-E	1630	SILT EXCAVATION	2,255 CY		
0111	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,000 SY		
0112	6042000000-E	1632	1/4" HARDWARE CLOTH	1,200 LF		
0113	6084000000-E	1660	SEEDING & MULCHING	5.5 ACR		
0114	6087000000-E	1660	MOWING	3 ACR		
0115	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0116	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0117	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	125 LB		
0118	6108000000-E	1665	FERTILIZER TOPDRESSING	4 TON		
0119	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0120	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0121	7060000000-E	1705	SIGNAL CABLE	2,190 LF		
0122	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	18 EA		
0123	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	7 EA		
0124	7264000000-E	1710	MESSENGER CABLE (3/8")	970 LF		
0125	7300000000-E	1715	TRENCHING (UNPAVED)	1,250 LF		
0126	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	9 EA		

County : Wilson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0127	7360000000-N	1720	WOOD POLE	1 EA		
0128	7372000000-N	1721	GUY ASSEMBLY	2 EA		
0129	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1 EA		
0130	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,900 LF		
0131	7456000000-E	1726	LEAD-IN CABLE	6,500 LF		
0132	7576000000-N	1740	METAL STRAIN SIGNAL POLE	1 EA		
0133	7613000000-N	SP	SOIL TEST	1 EA		
0134	7636000000-N	1745	SIGN FOR SIGNALS	2 EA		
0135	7684000000-N	1750	SIGNAL CABINET FOUNDATION	1 EA		
0136	7756000000-N	1751	CONTROLLER WITH CABINET (TYPE 2070L, BASE MOUNTED)	1 EA		
0137	7780000000-N	SP	DETECTOR CARD (TYPE 2070L)	12 EA		
0138	7980000000-N	SP	GENERIC SIGNAL ITEM CABINET BASE EXTENDER	1 EA		
0139	7992000000-E	SP	GENERIC SIGNAL ITEM DRILLED PIER FOUNDATION (42")	7 CY		

0826/Dec16/Q182237.1/D600656300000/E139

Total Amount Of Bid For Entire Project :

C201301 (U-3823B)
COUNTY: Wilson

2/16/99

Contract No: C201301
County: Wilson

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General