

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	345 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	8.49 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	2,115 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	2,185 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	29,838 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	3,004 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	5,278 SY		
0009	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	124 TON		
0010	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	107 TON		
0011	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	16,025 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	11,108 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	972 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	667 TON		
0015	1704000000-E	SP	PATCHING EXISTING PAVEMENT	13 TON		
0016	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CEMENT CONCRETE)	32,010 LF		
0017	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	39 EA		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	6 EA		
0019	2830000000-N	858	ADJUSTMENT OF MANHOLES	171 EA		
0020	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	96 EA		
0021	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	61,354 LF		
0022	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	54,710 LF		
0023	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	797 LF		
0024	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	4,645 LF		
0025	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	508 LF		
0026	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	170 LF		
0027	4702000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 120 MILS)	2,226 LF		
0028	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,207 LF		
0029	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	36 EA		
0030	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	227 EA		
0031	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	174,272 LF		
0032	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	15 EA		
0033	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0034	6084000000-E	1660	SEEDING & MULCHING	3.05 ACR		
0035	6110000000-E	SP	RESIDENTIAL SEEDING	1.24 ACR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	50 LF		
0037	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	300 LF		
0038	7312000000-N	1716	JUNCTION BOX (*****) (STANDARD SIZE)	5 EA		
0039	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	7,100 LF		
0040	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	500 LF		
0041	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	500 LF		
0756/Sep11/Q412739.78/D150968100000/E41			Total Amount Of Bid For Entire Project :			

Contract No: C 201652

County: Guilford

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General