

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	18,350 CY		
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	675 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	2,280 CY		
0008	0141000000-E	240	BERM DITCH CONSTRUCTION	180 LF		
0009	0195000000-E	265	SELECT GRANULAR MATERIAL	25,250 CY		
0010	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	24,900 SY		
0011	0199000000-E	SP	TEMPORARY SHORING	360 SF		
0012	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	2,290 TON		
0013	0342000000-E	310	*** SIDE DRAIN PIPE (30")	28 LF		
0014	0343000000-E	310	15" SIDE DRAIN PIPE	52 LF		
0015	0344000000-E	310	18" SIDE DRAIN PIPE	144 LF		
0016	0345000000-E	310	24" SIDE DRAIN PIPE	136 LF		
0017	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	10,160 LF		
0018	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	4,164 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	3,276	LF	
002C	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	1,104	LF	
0021	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	652	LF	
0022	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	72	LF	
002E	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	8	LF	
0024	0414000000-E	310	60" RC PIPE CULVERTS, CLASS III	84	LF	
002E	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	544	LF	
002E	0588000000-E	310	18" CS PIPE CULVERTS, 0.064" THICK	828	LF	
0027	0594000000-E	310	24" CS PIPE CULVERTS, 0.064" THICK	204	LF	
002E	0648000000-E	SP	*** SADDLE BRANCH CONNECTOR (18")	2	EA	
002E	0708000000-E	310	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	32	LF	
003C	0714000000-E	310	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK	56	LF	
0031	0807000000-E	310	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK	2	EA	
0032	0962000000-E	320	*** X *** CAA STRUCTURAL PLATE PIPE ARCH, ***** THICK (137" x 85", 0.125")	126	LF	
003E	0995000000-E	340	PIPE REMOVAL	5,142	LF	
0034	1121000000-E	520	AGGREGATE BASE COURSE	500	TON	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	1220000000-E	545	INCIDENTAL STONE BASE	500 TON		
003E	1330000000-E	607	INCIDENTAL MILLING	3,500 SY		
0037	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	25,400 TON		
003E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	26,200 TON		
003E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	23,650 TON		
004C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	3,743 TON		
0041	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	1,020 TON		
0042	2022000000-E	815	SUBDRAIN EXCAVATION	450 CY		
0043	2033000000-E	815	SUBDRAIN FINE AGGREGATE	340 CY		
0044	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	2,000 LF		
004E	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	60 EA		
004E	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	24 LF		
0047	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	4 EA		
004E	2190000000-N	828	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE	16 EA		
004E	2209000000-E	838	ENDWALLS	5 CY		
005C	2220000000-E	838	REINFORCED ENDWALLS	13 CY		
0051	2253000000-E	840	PIPE COLLARS	6 CY		
0052	2264000000-E	840	PIPE PLUGS	2 CY		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	265	EA	
0054	2297000000-E	840	MASONRY DRAINAGE STRUCTURES	6	CY	
005E	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	38	LF	
005E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	59	EA	
0057	2366000000-N	840	FRAME WITH TWO GRATES, STD 840.24	2	EA	
005E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	19	EA	
005E	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	71	EA	
006C	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	78	EA	
0061	2396000000-N	840	FRAME WITH COVER, STD 840.54	37	EA	
0062	2440000000-N	840	CONCRETE APRON FOR CATCH BASIN	3	EA	
0063	2451000000-N	840	CONCRETE APRON FOR DROP INLETS	13	EA	
0064	2529000000-E	SP	GENERIC GRADING ITEM (SF) TEMPORARY FABRIC WALL	382	SF	
006E	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	3,500	LF	
006E	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	27,500	LF	
0067	2580000000-E	846	CONCRETE VALLEY GUTTER	200	LF	
006E	2591000000-E	848	4" CONCRETE SIDEWALK	14,000	SY	
006E	2598000000-E	848	CONCRETE WHEELCHAIR RAMPS	730	SY	
007C	2612000000-E	848	6" CONCRETE DRIVEWAY	2,000	SY	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0071	2619000000-E	850	4" CONCRETE PAVED DITCH	10 SY		
0072	2626000000-E	852	3" CONCRETE ISLAND COVERS	1,900 SY		
0073	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	3,400 SY		
0074	2830000000-N	858	ADJUSTMENT OF MANHOLES	60 EA		
007E	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	140 EA		
007E	3030000000-E	862	STEEL BM GUARDRAIL	525 LF		
0077	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	10 EA		
007E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6 EA		
007E	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	6 EA		
008C	3360000000-E	863	REMOVE EXISTING GUARDRAIL	450 LF		
0081	3628000000-E	876	PLAIN RIP RAP, CLASS I	30 TON		
0082	3649000000-E	876	PLAIN RIP RAP, CLASS B	91 TON		
0083	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	2,810 SY		
0084	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	2 EA		
008E	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	927 LF		
008E	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
0087	4102000000-N	904	SIGN ERECTION, TYPE E	73 EA		
008E	4108000000-N	904	SIGN ERECTION, TYPE F	5 EA		
008E	4129000000-N	906	RELOCATE SIGN, TYPE ***** (E)	2 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009C	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	41	EA	
0091	4192000000-N	907	DISPOSAL OF SUPPORT, U-CHANNEL	2	EA	
0092	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	1,100	SF	
0093	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	240	SF	
0094	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	354	SF	
009E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2	EA	
009E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	4	EA	
0097	4425000000-N	1125	WARNING FLAG SETS	6	EA	
009E	4430000000-N	1130	DRUMS	900	EA	
009E	4435000000-N	1135	CONES	200	EA	
010C	4446100000-E	SP	BARRICADES (TYPE III)	360	LF	
0101	4450000000-N	1150	FLAGGER	6,720	HR	
0102	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2	EA	
0103	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2	EA	
0104	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)	2	EA	
010E	4485000000-E	1170	PORTABLE CONCRETE BARRIER	200	LF	
010E	4500000000-E	1170	RESET PORTABLE CONCRETE BARRIER	200	LF	
0107	4507000000-E	SP	WATER FILLED BARRIER	1,412	LF	
010E	4508000000-E	SP	RESET WATER FILLED BARRIER	643	LF	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0109	4510000000-N	SP	POLICE	720 HR		
011C	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,489 EA		
0111	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	4,550 LF		
0112	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	36,127 LF		
0113	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	671 LF		
0114	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	3,122 LF		
0115	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	200 LF		
0116	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,375 LF		
0117	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	6 EA		
011E	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	195 EA		
0119	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	224,727 LF		
012C	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,378 LF		
0121	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	1,600 LF		
0122	4830000000-E	1205	PAINT PAVEMENT MARKING LINES (16")	344 LF		
0123	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	2,836 LF		
0124	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	14 EA		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
012E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	232	EA	
012E	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	52,324	LF	
0127	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	827	LF	
012E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	261	LF	
012E	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	130	EA	
013C	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	1,532	EA	
0131	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	1,300	TON	
0132	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)	1,300	TON	
013E	5318000000-E	1505	PAVEMENT REPAIR FOR UTILITY WORK	282	TON	
0134	5420000000-E	1510	1" COPPER WATER PIPE, TYPE K	1,534	LF	
013E	5432000000-E	1510	2" PVC WATER PIPE, SDR ***** (21, 200# WP)	297	LF	
013E	5438000000-E	1510	4" PVC WATER PIPE, SDR ***** (21, 200# WP)	49	LF	
0137	5444000000-E	1510	6" PVC WATER PIPE, SDR ***** (21, 200# WP)	1,722	LF	
013E	5462000000-E	1510	12" PVC WATER PIPE, SDR ***** (21, 200# WP)	364	LF	
013E	5468000000-E	1510	*** PVC WATER PIPE, (C900), DR **, *****WP (12", 18, 150#)	12,447	LF	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
014C	5474000000-E	1510	8" PVC WATER PIPE, (C900), DR **, *****WP (18, 150#)	511	LF	
0141	5476000000-E	1510	**** PVC WATER PIPE, (C-900), DR ****, *****WP (6", 14, 200#)	4,847	LF	
0142	5476000000-E	1510	**** PVC WATER PIPE, (C-900), DR ****, *****WP (6", 18, 150#)	765	LF	
0143	5498000000-E	SP	**** PE WATER TUBING, SDR 9, *****WP (1", 200#)	109	LF	
0144	5516000000-E	1510	1" CORPORATION STOP	52	EA	
0145	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (4", 200#)	1	EA	
0146	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	42	EA	
0147	5546000000-E	1510	8" GATE VALVE & VALVE BOX, *****WP (200#)	8	EA	
0148	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#)	19	EA	
0149	5582000000-E	1510	***X*** TAPPING SADDLE (12" X 1")	37	EA	
015C	5582000000-E	1510	***X*** TAPPING SADDLE (12" X 2")	5	EA	
0151	5582000000-E	1510	***X*** TAPPING SADDLE (2" X 1")	2	EA	
0152	5582000000-E	1510	***X*** TAPPING SADDLE (6" X 1")	12	EA	
0153	5582000000-E	1510	***X*** TAPPING SADDLE (8" X 1")	1	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0154	5636000000-E	1510	12" TRANSITION COUPLING, ***** (PVC TO AC)	2	EA	
015E	5666000000-E	1510	FIRE HYDRANT, *****# WP (150#)	1	EA	
015E	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	15	EA	
0157	5708000000-E	1520	*** PVC FORCE MAIN SEWER PIPE, ***** (4", SDR 21, 200# WP)	50	LF	
015E	5708000000-E	1520	*** PVC FORCE MAIN SEWER PIPE, ***** (8", SDR 21, 200# WP)	2,851	LF	
015E	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (12", AC)	336	LF	
016C	5822000000-N	1530	BREAK DOWN & REBUILD EXISTING MANHOLE	7	EA	
0161	5852000000-E	SP	*** STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (16", 0.250")	120	LF	
0162	5852000000-E	SP	*** STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (16", 0.281")	150	LF	
016E	5858000000-E	SP	12-3/4" STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (0.188")	180	LF	
0164	5864000000-E	SP	18" STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (0.312")	150	LF	
016E	5870000000-E	SP	24" STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (0.250")	184	LF	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0166	5870000000-E	SP	24" STEEL ENCASMENT PIPE, ***** THICK, BY BORING & JACKING (0.375")	150	LF	
0167	5882000000-N	SP	GENERIC UTILITY ITEM 12" INSERTING GATE VALVE & VALVE BOX, 200# WP (WATER)	2	EA	
016E	5882000000-N	SP	GENERIC UTILITY ITEM 12" RESTRAINED RETAINER GLAND 200# WP	14	EA	
016E	5882000000-N	SP	GENERIC UTILITY ITEM 12" X 12" DI LOCKING TEE	2	EA	
017C	5882000000-N	SP	GENERIC UTILITY ITEM 12" X 6" DI LOCKING TEE	25	EA	
0171	5882000000-N	SP	GENERIC UTILITY ITEM 12" X 8" DI LOCKING TEE	7	EA	
0172	5882000000-N	SP	GENERIC UTILITY ITEM 2" BALL VALVE	5	EA	
0173	5882000000-N	SP	GENERIC UTILITY ITEM 4" INSERTING GATE VALVE & VALVE BOX, 200# WP (SEWER)	1	EA	
0174	5882000000-N	SP	GENERIC UTILITY ITEM 6" INSERTING GATE VALVE & VALVE BOX, 200# WP (WATER)	1	EA	
017E	5882000000-N	SP	GENERIC UTILITY ITEM 6" RESTRAINED RETAINER GLAND 200# WP	8	EA	
0176	5882000000-N	SP	GENERIC UTILITY ITEM 6" X 4" DI LOCKING TEE	1	EA	
0177	5882000000-N	SP	GENERIC UTILITY ITEM 6" X 6" DI LOCKING TEE	11	EA	
017E	5882000000-N	SP	GENERIC UTILITY ITEM 8" RESTRAINED RETAINER GLAND 200# WP	14	EA	
017E	5882000000-N	SP	GENERIC UTILITY ITEM 8" SEWER LINE GATE VALVE AND VALVE BOX, 200# WP	2	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
018C	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN REBUILD & ROTATE TOP FOR EXISTING MANHOLE	3 EA		
0181	5882000000-N	SP	GENERIC UTILITY ITEM BREAKDOWN REBUILD & ROTATE TOP FOR EXISTING MANHOLE (CONCENT- RIC TOP)	2 EA		
0182	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 4" SANITARY SEWER CLEANOUT	15 EA		
0183	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE 6" SANITARY SEWER CLEANOUT	5 EA		
0184	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING RPZ BACKFLOW PREVENTION SYSTEM	12 EA		
018E	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER	47 EA		
0186	5882000000-N	SP	GENERIC UTILITY ITEM RELOCATE EXISTING WATER METER WITH NEW VAULT	1 EA		
0187	5882000000-N	SP	GENERIC UTILITY ITEM ROTATE TOP FOR EXISTING MAN- HOLE	4 EA		
018E	5882000000-N	SP	GENERIC UTILITY ITEM ROTATE TOP FOR EXISTING MAN- HOLE (CONCENTRIC TOP)	3 EA		
0189	5888000000-E	SP	GENERIC UTILITY ITEM 10" HDPE FORCE MAIN SEWER PIPE SDR 9, 200# WP BY DIRECTIONAL BORE	300 LF		
019C	5888000000-E	SP	GENERIC UTILITY ITEM 12" DI WATER PIPE, PC 350	20 LF		
0191	5888000000-E	SP	GENERIC UTILITY ITEM 14" HDPE WATER PIPE, SDR 9, 200# WP BY DIRECTIONAL BORE	600 LF		
0192	5888000000-E	SP	GENERIC UTILITY ITEM 4" PVC SEWER PIPE, SCH 40	1,000 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0193	5888000000-E	SP	GENERIC UTILITY ITEM 6" PVC SEWER PIPE, SCH 40	400 LF		
0194	5888000000-E	SP	GENERIC UTILITY ITEM 8" DI FORCE MAIN SEWER PIPE, PC 350	100 LF		
0195	5888000000-E	SP	GENERIC UTILITY ITEM 8" HDPE WATER PIPE, SDR 9, 200# WP BY DIRECTIONAL BORE	250 LF		
0196	5888000000-E	SP	GENERIC UTILITY ITEM CEMENT GROUT FOR FILLING 4" PVC ABANDONED PIPE & ENCASE- MENT	140 LF		
0197	5888000000-E	SP	GENERIC UTILITY ITEM CEMENT GROUT FOR FILLING 6" PVC ABANDONED PIPE & ENCASE- MENT	140 LF		
0198	5888000000-E	SP	GENERIC UTILITY ITEM CEMENT GROUT FOR FILLING 8" PVC ABANDONED PIPE & ENCASE- MENT	140 LF		
0199	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON SEWER PIPE FITTINGS, 250# MIN WP	6,500 LB		
0200	5906000000-E	SP	GENERIC UTILITY ITEM DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP	10,325 LB		
0201	5912000000-N	SP	GENERIC UTILITY ITEM INSTALL 4" MDPE GAS MAIN	Lump Sum	L.S.	
0202	6000000000-E	1605	TEMPORARY SILT FENCE	16,600 LF		
0203	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	790 TON		
0204	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,220 TON		
0205	6012000000-E	1610	SEDIMENT CONTROL STONE	1,575 TON		
0206	6015000000-E	1615	TEMPORARY MULCHING	35 ACR		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0207	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	1,250 LB		
0208	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	5 TON		
0209	6024000000-E	1622	TEMPORARY SLOPE DRAINS	230 LF		
0210	6027000000-N	1622	INLET PROTECTION AT TEMPORARY SLOPE DRAINS	5 EA		
0211	6029000000-E	SP	SAFETY FENCE	750 LF		
0212	6030000000-E	1630	SILT EXCAVATION	3,340 CY		
0213	6036000000-E	1631	MATTING FOR EROSION CONTROL	2,900 SY		
0214	6037000000-E	SP	COIR FIBER MAT	250 SY		
0215	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	4,000 SY		
0216	6042000000-E	1632	1/4" HARDWARE CLOTH	6,000 LF		
0217	6045000000-E	SP	*** TEMPORARY PIPE (18")	455 LF		
0218	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0219	6084000000-E	1660	SEEDING & MULCHING	35 ACR		
0220	6087000000-E	1660	MOWING	21 ACR		
0221	6090000000-E	1661	SEED FOR REPAIR SEEDING	300 LB		
0222	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.75 TON		
0223	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	850 LB		
0224	6108000000-E	1665	FERTILIZER TOPDRESSING	27 TON		
0225	6111000000-E	SP	IMPERVIOUS DIKE	275 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
022E	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0227	6123000000-E	1670	REFORESTATION	0.2 ACR		
022E	6126000000-E	SP	STREAMBANK REFORESTATION	0.2 ACR		
022E	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FAIRCLOTH SKIMMER (2")	8 EA		
023C	6132000000-N	SP	GENERIC EROSION CONTROL ITEM FAIRCLOTH SKIMMER (2-1/2")	3 EA		
0231	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	36 EA		
0232	7000000000-E	1705	PEDESTRIAN SIGNAL HEAD (***, ** SECTION) (16", 1 SECTION W/COUNTDOWN)	38 EA		
023E	7060000000-E	1705	SIGNAL CABLE	16,751 LF		
0234	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	73 EA		
023E	7132000000-E	1705	VEHICLE SIGNAL HEAD (12", 4 SECTION)	2 EA		
023E	7144000000-E	1705	VEHICLE SIGNAL HEAD (12", 5 SECTION)	20 EA		
0237	7180000000-N	1706	BACKPLATE	12 EA		
023E	7252000000-E	1710	MESSENGER CABLE (1/4")	14,300 LF		
023E	7264000000-E	1710	MESSENGER CABLE (3/8")	1,648 LF		
024C	7276000000-E	1715	JACK & BORE	150 LF		
0241	7279000000-E	1715	TRACER WIRE	825 LF		
0242	7288000000-E	1715	TRENCHING (PAVED)	460 LF		
024E	7300000000-E	1715	TRENCHING (UNPAVED)	9,252 LF		

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0244	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 1)	495	LF	
024E	7301000000-E	SP	DIRECTIONAL DRILL POLYETHYLENE CONDUIT, ***** (** CONDUIT) (2", 2)	1,465	LF	
024E	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	58	EA	
0247	7336000000-N	1716	JUNCTION BOX (OVER-SIZED)	11	EA	
024E	7360000000-N	1720	WOOD POLE	12	EA	
024E	7372000000-N	1721	GUY ASSEMBLY	24	EA	
025C	7408000000-E	1722	1" RISER WITH WEATHERHEAD	3	EA	
0251	7420000000-E	1722	2" RISER WITH WEATHERHEAD	15	EA	
025E	7432000000-E	1722	2" RISER WITH HEAT SHRINK TUBING	8	EA	
025E	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	12,326	LF	
0254	7456000000-E	1726	LEAD-IN CABLE	24,971	LF	
025E	7516000000-E	1730	COMMUNICATIONS CABLE (**FIBER) (12)	18,095	LF	
025E	7552000000-N	1731	INTERCONNECT CENTER	6	EA	
0257	7564000000-N	1732	FIBER-OPTIC TRANSCEIVER	7	EA	
025E	7566000000-N	1733	DELINEATOR MARKER	11	EA	
025E	7568000000-N	SP	FURNISH FIBER-OPTIC RESTORATION KIT	1	EA	
026C	7574000000-N	SP	FURNISH FIBER-OPTIC TRANSCEIVER	1	EA	
0261	7613000000-N	SP	SOIL TEST	22	EA	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0262	7624000000-N	1743	SIGNAL PEDESTAL WITH FOUNDATION	5	EA	
0263	7636000000-N	1745	SIGN FOR SIGNALS	11	EA	
0264	7684000000-N	1750	SIGNAL CABINET FOUNDATION	6	EA	
026E	7828000000-N	1751	CONTROLLER WITH CABINET (NEMA TS-2, TYPE 2 CONTROLLER, TYPE 1 CABINET, BASE MOUNTED)	6	EA	
026E	7852000000-N	SP	DETECTOR CARD (NEMA TS-2)	44	EA	
0267	7980000000-N	SP	GENERIC SIGNAL ITEM CCTV CAMERA ASSEMBLY	1	EA	
026E	7980000000-N	SP	GENERIC SIGNAL ITEM FIBER OPTIC VIDEO/DATA RECEIVER	1	EA	
026E	7980000000-N	SP	GENERIC SIGNAL ITEM FIBER OPTIC VIDEO/DATA TRANSMITTER	1	EA	
027C	7980000000-N	SP	GENERIC SIGNAL ITEM LUMINAIRE MAST ARM	23	EA	
0271	7980000000-N	SP	GENERIC SIGNAL ITEM MAST ARM WITH METAL POLE DESIGN	22	EA	
0272	7980000000-N	SP	GENERIC SIGNAL ITEM METAL POLE W/ SINGLE MAST ARM	21	EA	
0273	7980000000-N	SP	GENERIC SIGNAL ITEM METAL POLE WITH DUAL MAST ARM	1	EA	
0274	7990000000-E	SP	GENERIC SIGNAL ITEM UNDERGROUND POLETHYLENE CONDUIT, (2", 1)	165	LF	
027E	7992000000-E	SP	GENERIC SIGNAL ITEM DRILLED PIER FOUNDATION	188	CY	

County : Pitt

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
CULVERT ITEMS						
027E	8063000000-N	SP	PRECAST REINFORCED CONC BOX CULVERT AT STA ***** (33+52.00 -L-)	Lump Sum	L.S.	
0277	8126000000-N	414	CULVERT EXCAVATION, STA ***** (33+52.00 -L-)	Lump Sum	L.S.	
027E	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	112 TON		
027E	8590000000-E	876	PLAIN RIP RAP, CLASS ** (1)	56 TON		
028C	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	63 SY		
WALL ITEMS						
0281	8832000000-N	SP	GENERIC RETAINING WALL ITEM MODULAR BLOCK RETAINING WALL AT STA 143+00.00 -WALL 2-	Lump Sum	L.S.	
0282	8832000000-N	SP	GENERIC RETAINING WALL ITEM VIBRATION MONITORING	Lump Sum	L.S.	
0283	8847000000-E	SP	GENERIC RETAINING WALL ITEM PILE / PANEL RETAINING WALL AT STA 110+43.50 -WALL 1-	2,007 SF		
1249/Sep12/Q789710.15/D1333188900000/E283				Total Amount Of Bid For Entire Project :		

C201654 (U-3613B)
COUNTY: PITT

2/16/99

Contract No: C201654
County: Pitt

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General