

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0036000000-E	225	UNDERCUT EXCAVATION	500 CY		
0004	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0005	0080000000-E	SP	CLASS IV SUBGRADE STABILIZATION	100 TON		
0006	0106000000-E	230	BORROW EXCAVATION	500 CY		
0007	0156000000-E	250	REMOVAL OF EXISTING ASPHALT PAVEMENT	100 SY		
0008	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	600 SY		
0009	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	156 TON		
0010	0360000000-E	310	12" RC PIPE CULVERTS, CLASS III	96 LF		
0011	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	1,296 LF		
0012	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	62 LF		
0013	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	16 LF		
0014	0995000000-E	340	PIPE REMOVAL	1,450 LF		
0015	1220000000-E	545	INCIDENTAL STONE BASE	400 TON		
0016	1245000000-E	SP	SHOULDER RECONSTRUCTION	4 SMI		
0017	1264000000-E	SP	DITCHING	1,000 LF		
0018	1308000000-E	607	MILLING ASPHALT PAVEMENT, ***** TO ***** DEPTH (0" TO 4")	1,280 SY		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1330000000-E	607	INCIDENTAL MILLING	400 SY		
0020	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,107 TON		
0021	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	9,011 TON		
0022	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	5,407 TON		
0023	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	514 TON		
0024	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	324 TON		
0025	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	80 TON		
0026	1704000000-E	SP	PATCHING EXISTING PAVEMENT	600 TON		
0027	1880000000-E	SP	GENERIC PAVING ITEM INCIDENTAL ASPHALT	60 TON		
0028	2253000000-E	840	PIPE COLLARS	1 CY		
0029	2264000000-E	840	PIPE PLUGS	1 CY		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0031	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16 (840.16)	1 EA		
0032	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	5 EA		
0033	2612000000-E	848	6" CONCRETE DRIVEWAY	500 SY		
0034	2752000000-E	SP	GENERIC PAVING ITEM INCIDENTAL CONCRETE CURB	40 LF		
0035	2830000000-N	858	ADJUSTMENT OF MANHOLES	3 EA		
0036	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	8 EA		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	3628000000-E	876	RIP RAP, CLASS I	10 TON		
0038	3649000000-E	876	RIP RAP, CLASS B	40 TON		
0039	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	115 SY		
0040	4510000000-N	SP	POLICE	60 HR		
0041	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	46,500 LF		
0042	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	47,500 LF		
0043	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	800 LF		
0044	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	30 LF		
0045	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	12 EA		
0046	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	300 EA		
0047	5270000000-N	SP	GENERIC LIGHTING ITEM PORTABLE LIGHTING	10 EA		
0048	5648000000-N	1515	RELOCATE WATER METER	2 EA		
0049	6000000000-E	1605	TEMPORARY SILT FENCE	5,000 LF		
0050	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	600 TON		
0051	6012000000-E	1610	SEDIMENT CONTROL STONE	300 TON		
0052	6030000000-E	1630	SILT EXCAVATION	500 CY		
0053	6036000000-E	1631	MATTING FOR EROSION CONTROL	500 SY		
0054	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	200 SY		

County : Union

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0055	6084000000-E	1660	SEEDING & MULCHING	16 ACR		

0900/Sep13/Q129121.0/D142495100000/E55

Total Amount Of Bid For Entire Project :

**Contract No: C 201646**

**County: Union**

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General