

County : Guilford, Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	974 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	2.18 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	459 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1")	14,688 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	14,665 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4")	7,184 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	2,290 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3")	583 SY		
0010	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 4-1/2")	875 SY		
0011	1330000000-E	607	INCIDENTAL MILLING	2,447 SY		
0012	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	18,919 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	25,065 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,637 TON		
0015	1775000000-E	660	ASPHALT SURFACE TREATMENT, MAT COAT, #78M STONE	159,264.7 SY		
0016	2600000000-N	SP	RETROFIT EXISTING WHEELCHAIR RAMPS	20 EA		

County : Guilford, Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0017	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	16 EA		
0018	2830000000-N	858	ADJUSTMENT OF MANHOLES	74 EA		
0019	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	84 EA		
0020	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	8,303 LF		
0021	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	62,157 LF		
0022	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	128 LF		
0023	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	957 LF		
0024	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	798 LF		
0025	4705000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS)	150 LF		
0026	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,250 LF		
0027	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	90 EA		
0028	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	294 EA		
0029	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	1,108,022 LF		
0030	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	30 LF		
0031	6084000000-E	1660	SEEDING & MULCHING	0.6 ACR		
0032	6110000000-E	SP	RESIDENTIAL SEEDING	0.46 ACR		
0033	7288000000-E	1715	PAVED TRENCHING (***** (1, 2")	350 LF		

County : Guilford, Rockingham

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0034	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	700 LF		
0035	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	14 EA		
0036	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	4,600 LF		
0037	7456000000-E	1726	LEAD-IN CABLE (*****) (18-2)	1,500 LF		
0038	7456000000-E	1726	LEAD-IN CABLE (*****) (18-4)	900 LF		

1143/Oct19/Q1440491.94/D138611100000/E38

Total Amount Of Bid For Entire Project :

Contract No: C 201664

County: Guilford, Rockingham

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General