

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0029000000-N	SP	REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+30.25)	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0005	0057000000-E	226	UNDERCUT EXCAVATION	100 CY		
0006	0080000000-E	SP	CLASS IV SUBGRADE STABILIZA- TION	500 TON		
0007	0134000000-E	240	DRAINAGE DITCH EXCAVATION	20 CY		
0008	0195000000-E	265	SELECT GRANULAR MATERIAL	500 CY		
0009	0196000000-E	270	FABRIC FOR SOIL STABILIZATION	500 SY		
0010	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0011	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	355 TON		
0012	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	210 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	29 TON		
0014	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	25 TON		
0015	2000000000-N	806	RIGHT OF WAY MARKERS	15 EA		
0016	2022000000-E	815	SUBDRAIN EXCAVATION	225 CY		
0017	2033000000-E	815	SUBDRAIN FINE AGGREGATE	170 CY		
0018	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	1,000 LF		

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2055000000-E	815	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS	30	EA	
0020	2066000000-N	815	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET	2	EA	
0021	2077000000-E	815	6" OUTLET PIPE (SUBDRAINS)	12	LF	
0022	2556000000-E	846	SHOULDER BERM GUTTER	30	LF	
0023	2570000000-N	SP	MODIFIED CONCRETE FLUME	1	EA	
0024	3030000000-E	862	STEEL BM GUARDRAIL	200	LF	
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5	EA	
0026	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4	EA	
0027	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	4	EA	
0028	3649000000-E	876	PLAIN RIP RAP, CLASS B	95	TON	
0029	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	650	SY	
0030	3659000000-N	SP	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON	1	EA	
0031	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	15.25	SF	
0032	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	28	LF	
0033	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (E)	2	EA	
0034	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	4	EA	
0035	4238000000-N	907	DISPOSAL OF SIGN, D, E OR F	4	EA	
0036	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	78	SF	

County : Mcdowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0037	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	180 SF		
003E	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	20 SF		
003E	4430000000-N	1130	DRUMS	22 EA		
004C	4435000000-N	1135	CONES	22 EA		
0041	4446100000-E	SP	BARRICADES (TYPE III)	50 LF		
0042	4450000000-N	1150	FLAGGER	240 HR		
0043	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
0044	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	100 LF		
004E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	10,400 LF		
004E	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	100 LF		
0047	6000000000-E	1605	TEMPORARY SILT FENCE	1,185 LF		
004E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
004E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65 TON		
005C	6012000000-E	1610	SEDIMENT CONTROL STONE	160 TON		
0051	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0052	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	50 LB		
0053	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.25 TON		
0054	6029000000-E	SP	SAFETY FENCE	250 LF		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
005E	6030000000-E	1630	SILT EXCAVATION	145 CY		
005E	6036000000-E	1631	MATTING FOR EROSION CONTROL	505 SY		
0057	6070000000-N	SP	SPECIAL STILLING BASINS	6 EA		
005E	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
005E	6087000000-E	1660	MOWING	0.5 ACR		
006C	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0061	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0062	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0063	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0064	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
006E	6123000000-E	1670	REFORESTATION	0.28 ACR		
006E	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8 EA		

**STRUCTURE ITEMS**

0067	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+30.25 -L-)	Lump Sum	L.S.	
006E	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SOIL	85.7 LF		
006E	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	40 LF		
007C	8111400000-E	SP	PERMANENT STEEL CASING FOR 3'-6" DIA DRILLED PIER	41.7 LF		
0071	8113000000-N	SP	SID INSPECTION	1 EA		

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	8114000000-N	SP	SPT TESTING	6 EA		
0073	8115000000-N	SP	CROSSHOLE SONIC LOGGING	2 EA		
0074	8121000000-N	SP	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13+30.25 -L-)	Lump Sum	L.S.	
007E	8147000000-E	420	REINFORCED CONCRETE DECK SLAB	3,794.9 SF		
007E	8161000000-E	420	GROOVING BRIDGE FLOORS	3,393 SF		
0077	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	110.3 CY		
007E	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (13+30.25 -L-)	Lump Sum	L.S.	
007E	8217000000-E	425	REINFORCING STEEL (BRIDGE)	30,254 LB		
008C	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	2,819 LB		
0081	8259000000-E	430	36" PRESTRESSED CONCRETE GIRDERS	524.33 LF		
0082	8364000000-E	450	HP12X53 STEEL PILES	200 LF		
0083	8391000000-N	450	STEEL PILE POINTS	16 EA		
0084	8468000000-E	460	ONE BAR METAL RAIL	200.95 LF		
008E	8517000000-E	460	1'-***X ***** CONCRETE PARAPET (1'-0 x 1'-6")	215.95 LF		
008E	8608000000-E	876	PLAIN RIP RAP CLASS II (2'-0" THICK)	224 TON		
0087	8622000000-E	876	FILTER FABRIC FOR DRAINAGE	249 SY		
008E	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

County : McDowell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0089	8692000000-N	SP	EVAZOTE JOINT SEALS	Lump Sum	L.S.	

0745/Oct06/Q60714.86/D433247080000/E89

Total Amount Of Bid For Entire Project :

C201445  
COUNTY: McDowell

2/16/99

Contract No: C201445  
County: McDowell

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General