

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	
0003	0008000000-E	200	SUPPLEMENTARY CLEARING & GRUBBING	2 ACR		
0004	0022000000-E	225	UNCLASSIFIED EXCAVATION	11,200 CY		
0005	0036000000-E	225	UNDERCUT EXCAVATION	1,000 CY		
0006	0106000000-E	230	BORROW EXCAVATION	850 CY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	300 TON		
0008	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	132 LF		
0009	0390000000-E	310	36" RC PIPE CULVERTS, CLASS III	268 LF		
001C	0396000000-E	310	42" RC PIPE CULVERTS, CLASS III	68 LF		
0011	0402000000-E	310	48" RC PIPE CULVERTS, CLASS III	144 LF		
0012	0995000000-E	340	PIPE REMOVAL	2,113 LF		
0013	1011000000-N	500	FINE GRADING	Lump Sum	L.S.	
0014	1220000000-E	545	INCIDENTAL STONE BASE	3,000 TON		
0015	1245000000-E	SP	SHOULDER RECONSTRUCTION	11 SMI		
0016	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	15,300 SY		
0017	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	13,800 TON		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	5,150	TON	
001E	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	24,600	TON	
002C	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	2,312	TON	
0021	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	200	TON	
0022	2209000000-E	838	ENDWALLS	10.2	CY	
0023	2253000000-E	840	PIPE COLLARS	10	CY	
0024	2264000000-E	840	PIPE PLUGS	0.12	CY	
002E	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4	EA	
002E	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	3	EA	
0027	2396000000-N	840	FRAME WITH COVER, STD 840.54	1	EA	
002E	2535000000-E	846	***X *** CONCRETE CURB (8" X 12")	600	LF	
002E	2538000000-E	846	**'-*** CONCRETE CURB & GUTTER (2'-0")	60	LF	
003C	2612000000-E	848	6" CONCRETE DRIVEWAY	245	SY	
0031	2830000000-N	858	ADJUSTMENT OF MANHOLES	17	EA	
0032	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	42	EA	
0033	3030000000-E	862	STEEL BM GUARDRAIL	825	LF	
0034	3165000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE ***** (TL -2)	1	EA	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
003E	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	6 EA		
003E	3215000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0037	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	9 EA		
003E	3435000000-N	SP	GENERIC GUARDRAIL ITEM 25' CLEAR SPAN GUARDRAIL SECTION	2 EA		
003E	3642000000-E	876	PLAIN RIP RAP, CLASS A	60 TON		
004C	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	325 SY		
0041	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	815 SF		
0042	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	212 SF		
0043	4412200000-E	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	119 SF		
0044	4425000000-N	1125	WARNING FLAG SETS	6 EA		
004E	4430000000-N	1130	DRUMS	100 EA		
004E	4435000000-N	1135	CONES	150 EA		
0047	4446100000-E	SP	BARRICADES (TYPE III)	80 LF		
004E	4450000000-N	1150	FLAGGER	3,000 HR		
004E	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	4 EA		
005C	4470000000-N	1160	RESET TEMPORARY CRASH CUSHIONS	2 EA		
0051	4490000000-E	1170	PORTABLE CONCRETE BARRIER (ANCHORED)	240 LF		
0052	4495000000-E	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	240 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0053	4505000000-E	1170	RESET PORTABLE CONCRETE BARRIER (ANCHORED)	380	LF	
0054	4650000000-N	1251	TEMPORARY RAISED PAVEMENT MARKERS	1,444	EA	
005E	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	88,809	LF	
005E	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	92,805	LF	
0057	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	858	LF	
005E	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	368	LF	
005E	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS)	4	EA	
006C	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	122	EA	
0061	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	363,228	LF	
0062	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	1,716	LF	
0063	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	736	LF	
0064	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	4	EA	
006E	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	122	EA	
006E	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	1,444	EA	
0067	5300000000-E	1505	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)	1,000	TON	

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
006E	5306000000-E	SP	BEDDING MATERIAL, UTILITIES CLASS ***** (VI)	1,000 TON		
006E	5318000000-E	1505	PAVEMENT REPAIR FOR UTILITY WORK	250 TON		
007C	5330000000-E	1510	6" DI WATER PIPE, CLASS ***** (CLASS 50)	65 LF		
0071	5336000000-E	1510	8" DI WATER PIPE, CLASS ***** (CLASS 50)	42 LF		
0072	5342000000-E	1510	12" DI WATER PIPE, CLASS ***** (CLASS 50)	372 LF		
0073	5414000000-E	1510	3/4" COPPER WATER PIPE, TYPE K	1,300 LF		
0074	5432000000-E	1510	2" PVC WATER PIPE, SDR ***** (SDR 21)	370 LF		
007E	5444000000-E	1510	6" PVC WATER PIPE, SDR ***** (SDR 21)	1,265 LF		
007E	5462000000-E	1510	12" PVC WATER PIPE, SDR ***** (SDR 21)	6,470 LF		
0077	5480000000-E	1510	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP	690 LB		
007E	5504000000-E	1510	**** CORPORATION STOP (3/4")	33 EA		
007E	5534000000-E	1510	*** GATE VALVE & VALVE BOX, *****WP (2", 200#WP)	2 EA		
008C	5540000000-E	1510	6" GATE VALVE & VALVE BOX, 200# WP	17 EA		
0081	5546000000-E	1510	8" GATE VALVE & VALVE BOX, *****WP (200#WP)	1 EA		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0082	5558000000-E	1510	12" GATE VALVE & VALVE BOX, *****WP (200#WP)	12 EA		
0083	5582000000-E	1510	***X*** TAPPING SADDLE (12" X 3/4")	22 EA		
0084	5582000000-E	1510	***X*** TAPPING SADDLE (2" X 3/4")	8 EA		
008E	5582000000-E	1510	***X*** TAPPING SADDLE (6" X 3/4")	3 EA		
008E	5648000000-N	1510	RELOCATE EXISTING WATER METER	22 EA		
0087	5672000000-N	1510	RELOCATE EXISTING FIRE HYDRANT	10 EA		
008E	5690000000-E	1520	*** PVC SEWER PIPE, SDR ** (4", SDR 35)	200 LF		
008E	5708000000-E	1520	*** PVC FORCE MAIN SEWER PIPE, ***** (3", SDR 21)	150 LF		
009C	5708000000-E	1520	*** PVC FORCE MAIN SEWER PIPE, ***** (4", SDR 21)	300 LF		
0091	5714000000-E	1520	*** DI SEWER PIPE, CLASS ***** (3", 50)	42 LF		
0092	5714000000-E	1520	*** DI SEWER PIPE, CLASS ***** (4", 50)	65 LF		
009E	5756000000-E	1520	DUCTILE IRON SEWER PIPE FIT- TINGS, ***** (250# WP)	140 LB		
0094	5798000000-E	1530	FILL OR REMOVE ABANDONED *** PIPE, ***** (12", PVC WATER)	2,460 LF		
009E	5852000000-E	SP	*** STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (10", 0.188")	87 LF		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
009E	5864000000-E	SP	18" STEEL ENCASEMENT PIPE, ***** THICK, BY BORING & JACKING (0.250")	45 LF		
0097	6000000000-E	1605	TEMPORARY SILT FENCE	11,000 LF		
009E	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	100 TON		
009E	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	1,100 TON		
010C	6012000000-E	1610	SEDIMENT CONTROL STONE	105 TON		
0101	6015000000-E	1615	TEMPORARY MULCHING	16.6 ACR		
0102	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	830 LB		
0103	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	3.4 TON		
0104	6029000000-E	SP	SAFETY FENCE	200 LF		
010E	6030000000-E	1630	SILT EXCAVATION	700 CY		
010E	6033000000-E	1631	SYNTHETIC ROVING	800 SY		
0107	6036000000-E	1631	MATTING FOR EROSION CONTROL	800 SY		
010E	6042000000-E	1632	1/4" HARDWARE CLOTH	200 LF		
010E	6045000000-E	SP	*** TEMPORARY PIPE (36")	400 LF		
011C	6070000000-N	SP	SPECIAL STILLING BASINS	4 EA		
0111	6084000000-E	1660	SEEDING & MULCHING	16.6 ACR		
0112	6087000000-E	1660	MOWING	16.6 ACR		
0113	6090000000-E	1661	SEED FOR REPAIR SEEDING	300 LB		

County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0114	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	1.2 TON		
0115	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	200 LB		
0116	6108000000-E	1665	FERTILIZER TOPDRESSING	4.2 TON		
0117	6111000000-E	SP	IMPERVIOUS DIKE	230 LF		
0118	6114000000-N	SP	SPECIALIZED HAND MOWING	2 HR		
0119	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	20 EA		
012C	8126000000-N	414	CULVERT EXCAVATION, STA ***** (403+72.89)	Lump Sum	L.S.	
0121	8133000000-E	414	FOUNDATION CONDITIONING MATER- IAL, BOX CULVERT	24 TON		
0122	8196000000-E	420	CLASS A CONCRETE (CULVERT)	51.9 CY		
0123	8245000000-E	425	REINFORCING STEEL (CULVERT)	5,672 LB		

\*\*\*\*\* BEGIN SCHEDULE AA \*\*\*\*\*  
\*\*\*\*\* ( 3 ALTERNATES ) \*\*\*\*\*

0124 AA1	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	636 LF		
0125 AA1	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	1,444 LF		
0126 AA1	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	64 LF		
*** OR ***						
0127 AA2	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	236 LF		
0128 AA2	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	488 LF		
0129 AA2	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	24 LF		



County : Robeson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
013C AA2	0986000000-E	SP	GENERIC PIPE ITEM 15" HDPE PIPE CULVERTS	400 LF		
0131 AA2	0986000000-E	SP	GENERIC PIPE ITEM 18" HDPE PIPE CULVERTS	956 LF		
0132 AA2	0986000000-E	SP	GENERIC PIPE ITEM 30" HDPE PIPE CULVERTS	40 LF		
*** OR ***						
0133 AA3	0366000000-E	310	15" RC PIPE CULVERTS, CLASS III	236 LF		
0134 AA3	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	488 LF		
013E AA3	0384000000-E	310	30" RC PIPE CULVERTS, CLASS III	24 LF		
0136 AA3	0986000000-E	SP	GENERIC PIPE ITEM 15" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, 0.064" THICK	400 LF		
0137 AA3	0986000000-E	SP	GENERIC PIPE ITEM 18" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, 0.064" THICK	956 LF		
013E AA3	0986000000-E	SP	GENERIC PIPE ITEM 30" ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, 0.064" THICK	40 LF		
***** END SCHEDULE AA *****						
1144/Oct19/Q685376.82/D537087500000/E138			Total Amount Of Bid For Entire Project :			

C201630  
COUNTY: ROBESON

2/16/99

Contract No: C201630  
County: Robeson

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General