

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0022000000-M	225	UNCLASSIFIED EXCAVATION	10,200 M3		
0003	0050000000-M	226	SUPPLEMENTARY CLEARING & GRUB- BING	0.4 HA		
0004	0057000000-M	226	UNDERCUT EXCAVATION	200 M3		
0005	0063000000-N	SP	GRADING	Lump Sum	L.S.	
0006	0080000000-M	SP	CLASS IV SUBGRADE STABILIZA- TION	75 MTN		
0007	0134000000-M	240	DRAINAGE DITCH EXCAVATION	550 M3		
0008	0195000000-M	265	SELECT GRANULAR MATERIAL	100 M3		
0009	0196000000-M	270	FABRIC FOR SOIL STABILIZATION	100 M2		
0010	0318000000-M	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS	70 MTN		
0011	0366000000-M	310	375MM RC PIPE CULVERTS, CLASS III	136.8 M		
0012	0372000000-M	310	450MM RC PIPE CULVERTS, CLASS III	51.6 M		
0013	0378000000-M	310	600MM RC PIPE CULVERTS, CLASS III	16.8 M		
0014	1004000000-M	462	GENERIC GRADING ITEM 100MM SLOPE PROTECTION	190 M2		
0015	1110000000-M	510	STABILIZER AGGREGATE	50 MTN		
0016	1220000000-M	545	INCIDENTAL STONE BASE	100 MTN		
0017	1491000000-M	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,140 MTN		
0018	1503000000-M	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,032 MTN		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1523000000-M	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	800 MTN		
0020	1560000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	141 MTN		
0021	1565000000-M	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	48 MTN		
0022	1840000000-M	665	MILLED RUMBLE STRIPS	270 M		
0023	2022000000-M	815	SUBDRAIN EXCAVATION	83 M3		
0024	2033000000-M	815	SUBDRAIN FINE AGGREGATE	63 M3		
0025	2044000000-M	815	150MM PERFORATED SUBDRAIN PIPE	150 M		
0026	2055000000-M	815	150MM SUBDRAIN PIPE WYES, TEES, & ELBOWS	15 EA		
0027	2077000000-M	815	150MM OUTLET PIPE (SUBDRAINS)	2 M		
0028	2132000000-N	816	CONCRETE PAD FOR SHOULDER DRAIN PIPE OUTLET	1 EA		
0029	2253000000-M	840	PIPE COLLARS	1 M3		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	8 EA		
0031	2364200000-N	840	FRAME WITH TWO GRATES, STD 840.20	1 EA		
0032	2365000000-N	840	FRAME WITH TWO GRATES, STD 840.22	1 EA		
0033	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (F)	2 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	1 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0037	2542000000-M	846	450MM CONCRETE CURB & GUTTER	155 M		
0038	2549000000-M	846	750MM CONCRETE CURB & GUTTER	380 M		
0039	2577000000-M	846	CONCRETE EXPRESSWAY GUTTER	110 M		
0040	2655000000-M	852	125MM MONOLITHIC CONCRETE ISLANDS (KEYED IN)	15 M2		
0041	2703000000-M	854	CONCRETE BARRIER, TYPE ***** (T2)	40 M		
0042	2738000000-M	SP	GENERIC PAVING ITEM 125MM MONOLITHIC CONC ISLAND, (REINFORCED SURFACE MOUNT)	125 M2		
0043	3060000000-M	862	STEEL BM GUARDRAIL, DOUBLE FACED	163.83 M		
0044	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0045	3210000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE CAT-1	1 EA		
0046	3270000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE 350	2 EA		
0047	3317000000-N	862	GUARDRAIL ANCHOR UNITS, TYPE B-77	1 EA		
0048	3360000000-M	863	REMOVE EXISTING GUARDRAIL	150 M		
0049	3649000000-M	876	PLAIN RIP RAP, CLASS B	85 MTN		
0050	3656000000-M	876	FILTER FABRIC FOR DRAINAGE	300 M2		
0051	4054000000-M	902	PLAIN CONCRETE SIGN FOOTINGS	1 M3		
0052	4060000000-M	903	SUPPORTS, BREAKAWAY STEEL BEAM	123 KG		
0053	4072000000-M	903	SUPPORTS, 4.5KG STEEL U-CHANNEL	75 M		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0054	4096000000-N	904	SIGN ERECTION, TYPE D	3 EA		
005E	4102000000-N	904	SIGN ERECTION, TYPE E	3 EA		
005E	4108000000-N	904	SIGN ERECTION, TYPE F	4 EA		
0057	4110000000-N	904	SIGN ERECTION, TYPE *** (GROUND MOUNTED) (A)	1 EA		
005E	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	3 EA		
005E	4412000000-M	SP	WORK ZONE SIGNS (STATIONARY)	43 M2		
006C	4412100000-M	SP	WORK ZONE SIGNS (PORTABLE)	33 M2		
0061	4412200000-M	SP	WORK ZONE SIGNS (BARRICADE MOUNTED)	1 M2		
0062	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	2 EA		
006E	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	2 EA		
0064	4430000000-N	1130	DRUMS	90 EA		
006E	4446100000-M	SP	BARRICADES (TYPE III)	4 M		
006E	4460000000-N	1155	WARNING LIGHTS (TYPE B)	4 EA		
0067	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	1 EA		
006E	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	3 EA		
006E	4485000000-M	1170	PORTABLE CONCRETE BARRIER	311 M		
007C	4495000000-M	1170	PORTABLE CONCRETE BARRIER (DRAINAGE)	101 M		
0071	4510000000-N	SP	POLICE	24 HR		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0072	4685000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 2.3MM)	462 M		
0073	4686000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (100MM, 3.1MM)	121 M		
0074	4695000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (200MM, 2.3MM)	200 M		
0075	4710000000-M	1205	THERMOPLASTIC PAVEMENT MARKING LINES (600MM, 3.1MM)	8 M		
0076	4725000000-M	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (2.3MM)	8 EA		
0077	4770000000-M	1205	COLD APPLIED PLASTIC PAVEMENT MARKING LINES (100MM)	36 M		
0078	4805000000-N	1205	COLD APPLIED PLASTIC PAVEMENT MARKING SYMBOL	1 EA		
0079	4810000000-M	1205	PAINT PAVEMENT MARKING LINES (100MM)	100 M		
0080	4820000000-M	1205	PAINT PAVEMENT MARKING LINES (200MM)	100 M		
0081	4850000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (100MM)	171 M		
0082	4870000000-M	1205	REMOVAL OF PAVEMENT MARKING LINES (600MM)	12 M		
0083	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	7 EA		
0084	4900000000-N	1252	PERMANENT RAISED PAVEMENT MARKERS	2 EA		
0085	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	61 EA		
0086	4935000000-N	1267	FLEXIBLE DELINEATORS (CRYSTAL)	15 EA		
0087	4940000000-N	1267	FLEXIBLE DELINEATORS (YELLOW)	22 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
008E	5155000000-M	1409	ELECTRICAL DUCT, TYPE BD, SIZE **** TS-3)	11.2 M		
008E	5220000000-M	1410	***#2 W/G FEEDER CIRCUIT IN SIZE *** CONDUIT (2, TS-1.5)	195 M		
009C	5240000000-N	1411	ELECTRICAL JUNCTION BOXES ***** (PC 18)	3 EA		
0091	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0092	5262000000-M	SP	GENERIC LIGHTING ITEM HIGH MOUNT FOUNDATIONS	5.4 M3		
009E	5270000000-N	SP	GENERIC LIGHTING ITEM RELOCATE HIGH MOUNT STANDARD	1 EA		
0094	6000000000-M	1605	TEMPORARY SILT FENCE	160 M		
009E	6006000000-M	1610	STONE FOR EROSION CONTROL, CLASS A	165 MTN		
009E	6009000000-M	1610	STONE FOR EROSION CONTROL, CLASS B	105 MTN		
0097	6012000000-M	1610	SEDIMENT CONTROL STONE	150 MTN		
009E	6015000000-M	1615	TEMPORARY MULCHING	2 HA		
009E	6018000000-M	1620	SEED FOR TEMPORARY SEEDING	100 KG		
010C	6021000000-M	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.75 MTN		
0101	6030000000-M	1630	SILT EXCAVATION	475 M3		
0102	6036000000-M	1631	MATTING FOR EROSION CONTROL	1,030 M2		
010E	6042000000-M	1632	6.4MM HARDWARE CLOTH	16 M		
0104	6084000000-M	1660	SEEDING & MULCHING	2 HA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
010E	6087000000-M	1660	MOWING	1.5	HA	
010E	6090000000-M	1661	SEED FOR REPAIR SEEDING	25	KG	
0107	6093000000-M	1661	FERTILIZER FOR REPAIR SEEDING	0.25	MTN	
010E	6096000000-M	1662	SEED FOR SUPPLEMENTAL SEEDING	75	KG	
010E	6108000000-M	1665	FERTILIZER TOPDRESSING	3.25	MTN	
011C	6114000000-N	SP	SPECIALIZED HAND MOWING	2	HR	
0111	6132000000-N	SP	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL	8	EA	
0112	7288000000-M	1715	TRENCHING (PAVED)	13	M	
0113	7300000000-M	1715	TRENCHING (UNPAVED)	101	M	
0114	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	2	EA	
011E	7444000000-M	1725	INDUCTIVE LOOP SAWCUT	77	M	
011E	7456000000-M	1726	LEAD-IN CABLE	207	M	
0117	7636000000-N	1745	SIGN FOR SIGNALS	1	EA	

0750/Nov03/Q23232.78/D441055700000/E117

Total Amount Of Bid For Entire Project :

C201545 (U-2905A)  
COUNTY: ALAMANCE

2/16/99

Contract No: C201545  
County: Alamance

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General