

County : Avery

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|---|------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 0000400000-N | 801 | CONSTRUCTION SURVEYING | Lump Sum | L.S. | |
| 0003 | 0029000000-N | SP | REINFORCED BRIDGE APPROACH FILL, STATION ***** (13+44.00) | Lump Sum | L.S. | |
| 0004 | 0043000000-N | 226 | GRADING | Lump Sum | L.S. | |
| 000E | 0050000000-E | 226 | SUPPLEMENTARY CLEARING & GRUB- BING | 1 ACR | | |
| 000E | 0057000000-E | 226 | UNDERCUT EXCAVATION | 200 CY | | |
| 0007 | 0080000000-E | SP | CLASS IV SUBGRADE STABILIZA- TION | 100 TON | | |
| 000E | 0195000000-E | 265 | SELECT GRANULAR MATERIAL | 100 CY | | |
| 000E | 0196000000-E | 270 | FABRIC FOR SOIL STABILIZATION | 100 SY | | |
| 001C | 0318000000-E | 300 | FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS | 11 TON | | |
| 0011 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 50 TON | | |
| 0012 | 1489000000-E | 610 | ASPHALT CONC BASE COURSE, TYPE B25.0B | 390 TON | | |
| 0013 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 65 TON | | |
| 0014 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 220 TON | | |
| 001E | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 35 TON | | |
| 001E | 2000000000-N | 806 | RIGHT OF WAY MARKERS | 14 EA | | |
| 0017 | 2022000000-E | 815 | SUBDRAIN EXCAVATION | 22.4 CY | | |
| 001E | 2033000000-E | 815 | SUBDRAIN FINE AGGREGATE | 16.8 CY | | |

County : Avery

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|------------|-----------|--------|
| 0019 | 2043000000-E | 815 | 4" PERFORATED SUBDRAIN PIPE | 100 LF | | |
| 002C | 2054000000-E | 815 | 4" SUBDRAIN PIPE WYES, TEES, & ELBOWS | 3 EA | | |
| 0021 | 2066000000-N | 815 | CONCRETE PAD FOR SUBDRAIN PIPE OUTLET | 1 EA | | |
| 0022 | 2076000000-E | 815 | 4" OUTLET PIPE (SUBDRAINS) | 6 LF | | |
| 0023 | 2286000000-N | 840 | MASONRY DRAINAGE STRUCTURES | 4 EA | | |
| 0024 | 2366000000-N | 840 | FRAME WITH TWO GRATES, STD 840.24 | 1 EA | | |
| 0025 | 2367000000-N | 840 | FRAME WITH TWO GRATES, STD 840.29 | 3 EA | | |
| 0026 | 2529000000-E | SP | GENERIC GRADING ITEM (SF) TEMPORARY FABRIC WALL | 67.5 SF | | |
| 0027 | 2556000000-E | 846 | SHOULDER BERM GUTTER | 10 LF | | |
| 002E | 3215000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE III | 1 EA | | |
| 0029 | 3270000000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 | 1 EA | | |
| 003C | 3380000000-E | 862 | TEMPORARY STEEL BM GUARDRAIL | 87.5 LF | | |
| 0031 | 3387000000-N | 862 | GUARDRAIL ANCHOR UNITS, TYPE ***** TEMPORARY (B-77) | 4 EA | | |
| 0032 | 3389100000-N | SP | GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY | 4 EA | | |
| 0033 | 3435000000-N | SP | GENERIC GUARDRAIL ITEM IMPACT ATTENUATOR, TYPE TL-2 | 3 EA | | |
| 0034 | 3635000000-E | 876 | RIP RAP, CLASS II | 200 TON | | |
| 003E | 3649000000-E | 876 | RIP RAP, CLASS B | 5 TON | | |

County : Avery

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|----------|-----------|--------|
| 0036 | 3656000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 475 | SY | |
| 0037 | 4025000000-E | 901 | CONTRACTOR FURNISHED, TYPE *** SIGN (E) | 49.5 | SF | |
| 003E | 4072000000-E | 903 | SUPPORTS, 3-LB STEEL U-CHANNEL | 90 | LF | |
| 003E | 4102000000-N | 904 | SIGN ERECTION, TYPE E | 12 | EA | |
| 004C | 4400000000-E | 1110 | WORK ZONE SIGNS (STATIONARY) | 144 | SF | |
| 0041 | 4405000000-E | 1110 | WORK ZONE SIGNS (PORTABLE) | 112 | SF | |
| 0042 | 4410000000-E | 1110 | WORK ZONE SIGNS (BARRICADE MOUNTED) | 36 | SF | |
| 0043 | 4430000000-N | 1130 | DRUMS | 35 | EA | |
| 0044 | 4445000000-E | 1145 | BARRICADES (TYPE III) | 48 | LF | |
| 004E | 4450000000-N | 1150 | FLAGGER | 240 | HR | |
| 004E | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 8,000 | LF | |
| 0047 | 4835000000-E | 1205 | PAINT PAVEMENT MARKING LINES (24") | 160 | LF | |
| 004E | 4850000000-E | 1205 | REMOVAL OF PAVEMENT MARKING LINES (4") | 1,800 | LF | |
| 0049 | 5871200000-E | 1550 | TRENCHLESS INSTALLATION OF 3" IN SOIL | 11 | LF | |
| 005C | 5871210000-E | 1550 | TRENCHLESS INSTALLATION OF 3" NOT IN SOIL | 11 | LF | |
| 0051 | 5888000000-E | SP | GENERIC UTILITY ITEM 3/4" PE WATER TUBING, SDR 9, 200 PSI WP | 262 | LF | |
| 0052 | 6000000000-E | 1605 | TEMPORARY SILT FENCE | 750 | LF | |

County : Avery

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---------------------------------------|-------------|-----------|--------|
| 0053 | 6006000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS A | 75 TON | | |
| 0054 | 6009000000-E | 1610 | STONE FOR EROSION CONTROL, CLASS B | 225 TON | | |
| 005E | 6012000000-E | 1610 | SEDIMENT CONTROL STONE | 90 TON | | |
| 0056 | 6015000000-E | 1615 | TEMPORARY MULCHING | 1.5 ACR | | |
| 0057 | 6018000000-E | 1620 | SEED FOR TEMPORARY SEEDING | 50 LB | | |
| 005E | 6021000000-E | 1620 | FERTILIZER FOR TEMPORARY SEED- ING | 0.25 TON | | |
| 0059 | 6029000000-E | SP | SAFETY FENCE | 300 LF | | |
| 006C | 6030000000-E | 1630 | SILT EXCAVATION | 430 CY | | |
| 0061 | 6036000000-E | 1631 | MATTING FOR EROSION CONTROL | 140 SY | | |
| 0062 | 6042000000-E | 1632 | 1/4" HARDWARE CLOTH | 80 LF | | |
| 0063 | 6084000000-E | 1660 | SEEDING & MULCHING | 2.5 ACR | | |
| 0064 | 6087000000-E | 1660 | MOWING | 1 ACR | | |
| 006E | 6090000000-E | 1661 | SEED FOR REPAIR SEEDING | 50 LB | | |
| 0066 | 6093000000-E | 1661 | FERTILIZER FOR REPAIR SEEDING | 0.25 TON | | |
| 0067 | 6096000000-E | 1662 | SEED FOR SUPPLEMENTAL SEEDING | 50 LB | | |
| 006E | 6108000000-E | 1665 | FERTILIZER TOPDRESSING | 1 TON | | |
| 0069 | 6114000000-N | SP | SPECIALIZED HAND MOWING | 2 HR | | |
| 007C | 6117000000-N | SP | RESPONSE FOR EROSION CONTROL | 8 EA | | |
| 0071 | 6123000000-E | 1670 | REFORESTATION | 0.5 ACR | | |

County : Avery

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|-------------|-------|-------------|----------|-----------|--------|
|--------|-------------|-------|-------------|----------|-----------|--------|

***** BEGIN SCHEDULE AA *****
***** (3 ALTERNATES) *****

| | | | | | | |
|-------------|--------------|-----|---------------------------------|----|----|--|
| 0072 AA1 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 96 | LF | |
|-------------|--------------|-----|---------------------------------|----|----|--|

*** OR ***

| | | | | | | |
|-------------|--------------|-----|---------------------------------|----|----|--|
| 0073 AA2 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 64 | LF | |
|-------------|--------------|-----|---------------------------------|----|----|--|

| | | | | | | |
|-------------|--------------|----|-------------------------------|----|----|--|
| 0074 AA2 | 0536000000-E | SP | **** HDPE PIPE CULVERTS (15") | 32 | LF | |
|-------------|--------------|----|-------------------------------|----|----|--|

*** OR ***

| | | | | | | |
|-------------|--------------|-----|---------------------------------|----|----|--|
| 0075 AA3 | 0366000000-E | 310 | 15" RC PIPE CULVERTS, CLASS III | 64 | LF | |
|-------------|--------------|-----|---------------------------------|----|----|--|

| | | | | | | |
|-------------|--------------|----|--|----|----|--|
| 0076 AA3 | 0540000000-E | SP | **** ALUMINIZED CORRUGATED STEEL PIPE CULVERTS, **** THICK (15", 0.064") | 32 | LF | |
|-------------|--------------|----|--|----|----|--|

***** END SCHEDULE AA *****

STRUCTURE ITEMS

| | | | | | | |
|------|--------------|----|---|----------|------|--|
| 0077 | 8007000000-N | SP | CONSTRUCTION, MAINTENANCE, & REMOVAL OF TEMP STRUCTURE AT STA ***** (13+44.00 -L-) | Lump Sum | L.S. | |
|------|--------------|----|---|----------|------|--|

| | | | | | | |
|------|--------------|-----|--|----------|------|--|
| 007E | 8035000000-N | 402 | REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+44.00 -L-) | Lump Sum | L.S. | |
|------|--------------|-----|--|----------|------|--|

| | | | | | | |
|------|--------------|----|-------------------------|----|----|--|
| 0079 | 8096000000-E | SP | PILE EXCAVATION IN SOIL | 60 | LF | |
|------|--------------|----|-------------------------|----|----|--|

| | | | | | | |
|------|--------------|----|-----------------------------|----|----|--|
| 008C | 8097000000-E | SP | PILE EXCAVATION NOT IN SOIL | 40 | LF | |
|------|--------------|----|-----------------------------|----|----|--|

| | | | | | | |
|------|--------------|-----|---|----------|------|--|
| 0081 | 8121000000-N | 412 | UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (13+44.00-L-) | Lump Sum | L.S. | |
|------|--------------|-----|---|----------|------|--|

| | | | | | | |
|------|--------------|-----|---------------------------|------|----|--|
| 0082 | 8182000000-E | 420 | CLASS A CONCRETE (BRIDGE) | 22.5 | CY | |
|------|--------------|-----|---------------------------|------|----|--|

| | | | | | | |
|------|--------------|-----|--|----------|------|--|
| 0083 | 8210000000-N | 422 | BRIDGE APPROACH SLABS, STATION ***** (13+44.00 -L-) | Lump Sum | L.S. | |
|------|--------------|-----|--|----------|------|--|

| | | | | | | |
|------|--------------|-----|----------------------------|-------|----|--|
| 0084 | 8217000000-E | 425 | REINFORCING STEEL (BRIDGE) | 3,494 | LB | |
|------|--------------|-----|----------------------------|-------|----|--|

County : Avery

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|--|--------------|-----------|--------|
| 008E | 8364000000-E | 450 | HP12X53 STEEL PILES | 100 LF | | |
| 008E | 8468000000-E | 460 | ONE BAR METAL RAIL | 59.75 LF | | |
| 0087 | 8517000000-E | 460 | 1'-***X ***** CONCRETE PARA- PET (1'-0" X 1'-9") | 75.34 LF | | |
| 008E | 8608000000-E | 876 | RIP RAP CLASS II (2'-0" THICK) | 28 TON | | |
| 008E | 8622000000-E | 876 | FILTER FABRIC FOR DRAINAGE | 30 SY | | |
| 009C | 8657000000-N | 430 | ELASTOMERIC BEARINGS | Lump Sum | L.S. | |
| 0091 | 8755000000-E | 430 | 3'-0" X 1'-6" PRESTRESSED CONC CORED SLABS | 376.67 LF | | |

1038/Nov13/Q20151.96/D384799010000/E91

Total Amount Of Bid For Entire Project :

Contract No: C 201582

County: Avery

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General