

County : Cumberland, Harnett

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|----------------------|--------------|-------|--|---------------|-----------|--------|
| ROADWAY ITEMS | | | | | | |
| 0001 | 0000100000-N | 800 | MOBILIZATION | Lump Sum | L.S. | |
| 0002 | 1220000000-E | 545 | INCIDENTAL STONE BASE | 1,836 TON | | |
| 0003 | 1245000000-E | SP | SHOULDER RECONSTRUCTION | 164.88 SMI | | |
| 0004 | 1297000000-E | 607 | MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2") | 28,976 SY | | |
| 0005 | 1308000000-E | 607 | MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1") | 2,646 SY | | |
| 0006 | 1308000000-E | 607 | MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2") | 82,082 SY | | |
| 0007 | 1308000000-E | 607 | MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/4") | 5,703 SY | | |
| 0008 | 1308000000-E | 607 | MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 3") | 9,856 SY | | |
| 0009 | 1498000000-E | 610 | ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B | 360 TON | | |
| 0010 | 1519000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S9.5B | 55,750 TON | | |
| 0011 | 1520000000-E | SP | ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE) | 43 TON | | |
| 0012 | 1525000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE SF9.5A | 53,162 TON | | |
| 0013 | 1526000000-E | 610 | ASPHALT CONC SURFACE COURSE, TYPE S4.75A | 4,092 TON | | |
| 0014 | 1560000000-E | 620 | ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22 | 7,111 TON | | |
| 0015 | 1704000000-E | SP | PATCHING EXISTING PAVEMENT | 1,239 TON | | |
| 0016 | 2605000000-N | 848 | CONCRETE WHEELCHAIR RAMPS | 12 EA | | |

County : Cumberland, Harnett

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|---|---------------|-----------|--------|
| 0017 | 2655000000-E | 852 | 5" MONOLITHIC CONCRETE ISLANDS (KEYED IN) | 1,280 SY | | |
| 0018 | 2830000000-N | 858 | ADJUSTMENT OF MANHOLES | 150 EA | | |
| 0019 | 2845000000-N | 858 | ADJUSTMENT OF METER BOXES OR VALVE BOXES | 185 EA | | |
| 0020 | 4685000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 475,350 LF | | |
| 0021 | 4686000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS) | 361,170 LF | | |
| 0022 | 4695000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS) | 4,010 LF | | |
| 0023 | 4697000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS) | 4,680 LF | | |
| 0024 | 4705000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (16", 120 MILS) | 1,100 LF | | |
| 0025 | 4710000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS) | 5,045 LF | | |
| 0026 | 4721000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING CHARACTER (120 MILS) | 200 EA | | |
| 0027 | 4725000000-E | 1205 | THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS) | 1,101 EA | | |
| 0028 | 4810000000-E | 1205 | PAINT PAVEMENT MARKING LINES (4") | 700,400 LF | | |
| 0029 | 4820000000-E | 1205 | PAINT PAVEMENT MARKING LINES (8") | 450 LF | | |
| 0030 | 4835000000-E | 1205 | PAINT PAVEMENT MARKING LINES (24") | 310 LF | | |
| 0031 | 4900000000-N | 1251 | PERMANENT RAISED PAVEMENT MARKERS | 10,606 EA | | |
| 0032 | 6084000000-E | 1660 | SEEDING & MULCHING | 207 ACR | | |
| 0033 | 7288000000-E | 1715 | PAVED TRENCHING (***** (1") | 110 LF | | |

County : Cumberland, Harnett

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|--------------|-------|-----------------------------------|--------------|-----------|--------|
| 0034 | 7300000000-E | 1715 | UNPAVED TRENCHING (*****) (2") | 1,100 LF | | |
| 0035 | 7324000000-N | 1716 | JUNCTION BOX (STANDARD SIZE) | 22 EA | | |
| 0036 | 7420000000-E | 1722 | 2" RISER WITH WEATHERHEAD | 22 EA | | |
| 0037 | 7444000000-E | 1725 | INDUCTIVE LOOP SAWCUT | 43,150 LF | | |
| 0038 | 7456000000-E | 1726 | LEAD-IN CABLE (*****) (18-2) | 1,650 LF | | |

0838/Nov14/Q1865331.88/D138086100000/E38

Total Amount Of Bid For Entire Project :

Contract No: C 201688

County: Cumberland-Harnett

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General