

County : New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0106000000-E	230	BORROW EXCAVATION	266 CY		
0003	0996000000-N	350	PIPE CLEAN-OUT	4 EA		
0004	1220000000-E	545	INCIDENTAL STONE BASE	125 TON		
0005	1245000000-E	SP	SHOULDER RECONSTRUCTION	2.42 SMI		
0006	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	14,560 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 4-1/2")	6,600 SY		
0008	1330000000-E	607	INCIDENTAL MILLING	1,800 SY		
0009	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	50 TON		
0010	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	2,374 TON		
0011	1520000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE S9.5B (LEVELING COURSE)	125 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,394 TON		
0013	1525000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	508 TON		
0014	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	185 TON		
0015	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	83 TON		
0016	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH)	820 TON		
0017	1880000000-E	SP	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (MILL)	7,345 TON		

County : New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2355000000-N	840	FRAME WITH GRATE, STD 840.29	1 EA		
0019	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0020	2473000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING DROP INLET TO TRAFFIC BEARING DROP INLET	1 EA		
0021	2473000000-N	SP	GENERIC DRAINAGE ITEM CONVERT EXISTING OPEN THROAT CB TO CATCH BASIN	1 EA		
0022	2605000000-N	848	CONCRETE WHEELCHAIR RAMPS	1 EA		
0023	2753000000-E	846	GENERIC PAVING ITEM 2'-6" CURB & GUTTER, REPAIR	625 LF		
0024	2753000000-E	846	GENERIC PAVING ITEM CURB & GUTTER REMOVAL	60 LF		
0025	2815000000-N	858	ADJUSTMENT OF DROP INLETS	3 EA		
0026	2830000000-N	858	ADJUSTMENT OF MANHOLES	6 EA		
0027	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	5 EA		
0028	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	15,000 LF		
0029	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	27,300 LF		
0030	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	600 LF		
0031	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	270 LF		
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	47 EA		
0033	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	18,875 LF		
0034	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	600 LF		

County : New Hanover, Pender

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	150 LF		
0036	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	23 EA		
0037	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	165 EA		
0038	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	210 EA		
0039	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	
0040	6000000000-E	1605	TEMPORARY SILT FENCE	16 LF		
0041	6012000000-E	1610	SEDIMENT CONTROL STONE	0.7 TON		
0042	6042000000-E	1632	1/4" HARDWARE CLOTH	16 LF		
0043	6084000000-E	1660	SEEDING & MULCHING	1.94 ACR		
0044	7312000000-N	1716	JUNCTION BOX (***** (PULL BOX)	1 EA		
0045	7372000000-N	1721	GUY ASSEMBLY	1 EA		
0046	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	750 LF		
0047	7456000000-E	1726	LEAD-IN CABLE (***** (18-2)	350 LF		
0048	7816000000-N	1751	DETECTOR CARD (NEMA TS-1)	1 EA		

0759/Nov20/Q101325.06/D167650100000/E48

Total Amount Of Bid For Entire Project :

Contract No: C 201686

County: New Hanover & Pender

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General