

PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.20921.9	5	5

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1 1/2" MILLING SY	SURFACE COURSE, S9.5B TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	ADJ. OF MANHOLES EA	MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	METER OR VALVE BOX EA	SEED & MULCHING AC	INDUCTIVE LOOP LF
5CR.20921.9	Wake	1	SR1011 - HILLSBOROUGH ST.	FROM SR3700 - GORMAN ST. TO CONCRETE SECTION WEST OF POWELL DR.	1,4,5	1.82	35	14	2.92	46900	4,942	297	200	7		5		2.11	1,200
		2	SR1774 - DISTRICT DR.	FROM SR1664 - BLUE RIDGE RD. TO END OF MAINT.	6	0.25	40				544	33	33			3			
		3	SR1664 - BLUE RIDGE RD.	FROM SR 3009 - EDWARDS MILL RD TO SR 3036 - WESTCHASE BLVD	2, 3, 4	1.54	48	8	1.25	32990	5,668	340	41	10		40		0.92	
		4	SR 1664 - BLUE RIDGE RD	SR 3036 - WESTCHASE BLVD TO SR 3007 - HILLSBOROUGH RD	2, 5	0.53	58	3	0.44	11577	1,992	120	14		4		8	0.32	
		5	SR 1656 - TRINTY RD.	FROM SR 3009 - EDWARDS MILL RD. TO SR 1664 - BLUE RDIGE RD.	7	1.1	60		0.92		3,422	205					8	1.25	
TOTAL FOR PROJ NO. 5CR.20921.9						5.24		25	5.53	91467	16,568	995	288	17	4	48	8	4.60	1,200
GRAND TOTAL						5.24		25	5.53	91467	16,568	995	288	17	4	48	8	4.60	1,200

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	4685000000-E	4686000000-E			4695000000-E	4697000000-E			4710000000-E	4721000000-E	4725000000-E			4810000000-E		4900000000-N		
					4" X 90 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	4" X 120 M WHITE THERMO LF	8" X 90 M WHITE THERMO LF	8" X 120 M YELLOW THERMO LF	8" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG ONLY 120 M EA	THERMO LT ARROW 90 M EA	THERMO RT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO STR & RT ARROW 90 M EA	THERMO LT STR RT ARROW 90 M EA	4" WHITE PAINT LF	4" YELLOW PAINT LF	CRYSTAL & RED MARKERS EA	YELLOW & YELLOW MARKERS EA	
5CR.20921.9	Wake	1	SR1011 - HILLSBOROUGH ST.	FROM SR3700 - GORMAN ST. TO CONCRETE SECTION WEST OF POWELL DR.	15,641	17,037	2,835		300	440	142		40	8	37	10		18,476	17,037	145	133	
		2	SR1774 - DISTRICT DR.	FROM SR1664 - BLUE RIDGE RD. TO END OF MAINT.	100	2,640	660				22									33	17	
		3	SR1664 - BLUE RIDGE RD.	FROM SR 3009 - EDWARDS MILL RD TO SR 3036 - WESTCHASE BLVD	7,160	12,160	4,580			490			39	13	69	18		3,207	3,872	230	122	
		4	SR 1664 - BLUE RIDGE RD	SR 3036 - WESTCHASE BLVD TO SR 3007 - HILLSBOROUGH RD	2,512	4,266	1,610			172	250		21	4	16	1		1,125	1,352	81	43	
		5	SR 1656 - TRINTY RD.	FROM SR 3009 - EDWARDS MILL RD. TO SR 1664 - BLUE RDIGE RD.	5,808	14,920	8,712	100			2,770	8	38	10	7	2	3				25	135
TOTAL FOR PROJ NO. 5CR.20921.9					31,221	51,023	18,397	100	300	1,102	3,184	8	138	35	129	31	3	22,808	22,261	514	450	
GRAND TOTAL						69,420				1,402					336		45,069		964			

* MILLING ASPHALT PAVEMENT 0"-1.5"
AT PAVEMENT TIE-INS = 530 SY