

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (1-1/2")	324,315 SY		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	4,592 SY		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	47,488 SY		
0005	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4-1/2")	422 SY		
0006	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	1,566 SY		
0007	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 2")	4,133 SY		
0008	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (1-1/2" TO 2")	7,470 SY		
0009	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (3" TO 4-1/2")	4,500 SY		
001C	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	769.26 TON		
0011	1508000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D	8,434 TON		
0012	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	2,671.78 TON		
0013	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	40 TON		
0014	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	576 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	1570000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22	2,628	TON	
001E	1704000000-E	SP	PATCHING EXISTING PAVEMENT	228	TON	
0017	1840000000-E	665	MILLED RUMBLE STRIPS	102,000	LF	
001E	1880000000-E	SP	GENERIC PAVING ITEM ASPHALT CONC SURFACE COURSE, TYPE S9.5D	43,840	TON	
001E	2815000000-N	858	ADJUSTMENT OF DROP INLETS	10	EA	
002C	2830000000-N	858	ADJUSTMENT OF MANHOLES	2	EA	
0021	4412000000-E	SP	WORK ZONE SIGNS (STATIONARY)	682	SF	
0022	4412100000-E	SP	WORK ZONE SIGNS (PORTABLE)	888	SF	
002E	4415000000-N	1115	FLASHING ARROW PANELS, TYPE C	3	EA	
0024	4420000000-N	1120	CHANGEABLE MESSAGE SIGN	3	EA	
002E	4430000000-N	1130	DRUMS	600	EA	
002E	4480000000-N	1165	TRUCK MOUNTED IMPACT ATTENUA- TOR (60 MPH)	3	EA	
0027	4688000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)	110,844	LF	
002E	4690000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)	41,433	LF	
002E	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	1,622	LF	
003C	4700000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)	6,812	LF	
0031	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	189	LF	
0032	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	41	EA	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0033	4815000000-E	1205	PAINT PAVEMENT MARKING LINES (6")	304,554 LF		
0034	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	3,244 LF		
0035	4825000000-E	1205	PAINT PAVEMENT MARKING LINES (12")	13,624 LF		
0036	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	378 LF		
0037	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	82 EA		
003E	4860000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (8")	100 LF		
003E	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	100 LF		
004C	4875000000-N	1205	REMOVAL OF PAVEMENT MARKING SYMBOLS & CHARACTERS	4 EA		
0041	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	2,309 EA		
0042	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

1528/Jan06/Q1043202.04/D134400200000/E42

Total Amount Of Bid For Entire Project :

C201537  
COUNTY: Alamance

2/16/99

Contract No: C201537  
County: Alamance

ACCEPTED BY THE  
DEPARTMENT OF TRANSPORTATION

---

Contract Officer

---

Date

Execution of Contract and Bonds  
Approved as to Form:

---

Attorney General