

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	628 TON		
0003	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (3")	18,480 SY		
0004	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (0" TO 1-1/2")	39,059 SY		
0005	1308000000-E	607	MILLING ASPHALT PAVEMENT, **** TO ***** DEPTH (3" TO 4-1/2")	1,000 SY		
0006	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	195 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	13,390 TON		
0008	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	14,716 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	1,759 TON		
0010	2605000000-N	SP	WHEELCHAIR RAMPS	70 EA		
0011	2815000000-N	858	ADJUSTMENT OF DROP INLETS	5 EA		
0012	2830000000-N	858	ADJUSTMENT OF MANHOLES	57 EA		
0013	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	16 EA		
0014	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	47,990 LF		
0015	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	99,998 LF		
0016	4697000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 120 MILS)	1,200 LF		
0017	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	1,468 LF		

County : Buncombe

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	4721000000-E	1205	THERMOPLASTIC PAVEMENT MARKING CHARACTER (120MIL)	12 EA		
0019	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	36 EA		
0020	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	346,144 LF		
0021	4835000000-E	1205	PAINT PAVEMENT MARKING LINES (24")	48 LF		
0022	4840000000-N	1205	PAINT PAVEMENT MARKING CHARACTER	6 EA		
0023	5255000000-N	1413	PORTABLE LIGHTING	Lump Sum	L.S.	

1107/Feb08/Q586279.0/D70294100000/E23

Total Amount Of Bid For Entire Project :