


EDI MODEL 2010ECL CONFLICT MONITOR

PROGRAMMING DETAIL



- NOTES:
- Card is provided with all diode jumpers in place. Removal of any jumper allows its channels to run concurrently.
 - Make sure jumpers SEL1-SEL5 are present on the monitor board.

NOTES

- To prevent "flash-conflict" problems, insert red flash program blocks for all unused vehicle load switches in the output file. The installer shall verify that signal heads flash in accordance with the Signal Plans.
- Ensure that Red Enable is active at all times during normal operation. To prevent Red Failures on unused monitor channels, tie unused red monitor inputs 3,7,9,10,11,12,13,14,15 & 16 to load switch AC+ per the cabinet manufacturer's instructions.
- Program controller to start up in phases 2 and 6 green.
- Enable Simultaneous Gap-Out, on the controller unit, for all phases.
- Program phases 4 and 8, on the controller unit, for Dual Entry.
- Program phase 8 for 'STARTUP PED CALL'.
- The cabinet and controller are part of the Gastonia City System.

EQUIPMENT INFORMATION

CONTROLLER.....CONTRACTOR SUPPLIED 2070L
 CABINET.....CONTRACTOR SUPPLIED 332
 SOFTWARE.....ECONOLITE OASIS
 CABINET MOUNT.....BASE
 OUTPUT FILE POSITIONS...12
 LOAD SWITCHES USED.....S1,S2,S4,S5,S6,S8,S8P
 PHASES USED.....1,2,4,5,6,8,8 PED
 OVERLAPS.....NONE


FIELD CONNECTION HOOK-UP CHART

LOAD SWITCH NO.	S1	S2	S2P	S3	S4	S4P	S5	S6	S6P	S7	S8	S8P
PHASE	1	2	2 PED	3	4	4 PED	5	6	6 PED	7	8	8 PED
SIGNAL HEAD NO.	11	21,22	NU	NU	41,42	NU	51	61,62	NU	NU	81,82	P81, P82
GREEN		130			103			136				109
YELLOW		129			102			135				108
RED		128			101			134				107
RED ARROW	125							131				
YELLOW ARROW	126							132				
GREEN ARROW	127							133				
												112
												110

NU = Not Used

INPUT FILE POSITION LAYOUT


(front view)



INPUT FILE CONNECTION & PROGRAMMING CHART

LOOP NO.	LOOP TERMINAL	INPUT FILE POS.	PIN NO.	INPUT ASSIGNMENT NO.	DETECTOR NO.	NEMA PHASE	CALL	EXTEND	FULL TIME DELAY	STRETCH TIME	DELAY TIME
1A	TB2-1,2	I1U	56	18	1	1	Y	Y			
2A,2B	TB2-5,6	I2U	39	1	2	2	Y	Y		1.8	
2C,2D	TB2-7,8	I2L	43	5	12	2	Y	Y			
4A	TB4-9,10	I6U	41	3	4	4	Y	Y		3.0	
4B	TB4-11,12	I6L	45	7	14	4	Y	Y			5
5A	TB3-1,2	J1U	55	17	5	5	Y	Y			
6A,6B	TB3-5,6	J2U	40	2	6	6	Y	Y		1.8	
6C,6D	TB3-7,8	J2L	44	6	16	6	Y	Y			
8A	TB5-9,10	J6U	42	4	8	8	Y	Y		3.0	
8B	TB5-11,12	J6L	46	8	18	8	Y	Y			5
PED PUSH BUTTONS											
P81,P82	TB8-8,9	I13L	70	32	PED 8	8 PED					

NOTE:
 INSTALL DC ISOLATOR IN INPUT FILE SLOT 113.



THIS ELECTRICAL DETAIL IS FOR THE SIGNAL DESIGN: 12-1459
 DESIGNED: February 2005
 SEALED: 2/28/05
 REVISED:

Signal Upgrade

Electrical and Programming Details For: SR 1255 (Hudson Boulevard) at SR 3217 (Bradford Heights)

Division 12 Gaston County Gastonia

PLAN DATE: February 2005 REVIEWED BY: T. Joyce

PREPARED BY: William Hairston REVIEWED BY:

REVISIONS INIT. DATE

122 N. McDowell St., Raleigh, NC 27603

Seal: NORTH CAROLINA PROFESSIONAL ENGINEER SEAL 022013 ENGINEER GEORGE C. BROWN

Signature: George C. Brown 5/13/05

SIG. INVENTORY NO. 12-1459

13-MAY-2005 08:35
 summins and staff\ingestek\c02\edsk\top\gastonia\121459_20050314e.dgn
 06/10/05