

STATE OF NORTH CAROLINA  
DIVISION OF HIGHWAYS

**SUMMARY OF EARTHWORK**  
IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT+%	BORROW	WASTE
-L-					
10+00 TO 14+20 (BEGIN BRIDGE)	2147	0	1135	0	1012
<b>SUBTOTAL</b>	<b>2147</b>	<b>0</b>	<b>1135</b>	<b>0</b>	<b>1012</b>
-L-					
15+20 (END BRIDGE) TO 20+50	1393	0	465	0	928
<b>SUBTOTAL</b>	<b>1393</b>	<b>0</b>	<b>465</b>	<b>0</b>	<b>928</b>
<b>TOTAL</b>	<b>3540</b>	<b>0</b>	<b>1600</b>	<b>0</b>	<b>1940</b>
<b>LOSS DUE TO CLEAR &amp; GRUB</b>	<b>-177</b>				<b>-177</b>
<b>PROJECT TOTAL</b>	<b>3363</b>	<b>0</b>	<b>1600</b>	<b>0</b>	<b>1763</b>
<b>SAY</b>	<b>3400</b>			<b>0</b>	

UNDERCUT 200 CY  
SHOULDER BORROW 384 CY  
SELECT MATERIAL, CLASS II 100 CY

APPROXIMATE QUANTITIES ONLY. BORROW EXCAVATION, SHOULDER BORROW, FINE GRADING, CLEARING AND GRUBBING, BREAKING OF EXISTING PAVEMENT AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR AT THE LUMP SUM PRICE FOR "GRADING".

**SUMMARY OF ASPHALT PAVEMENT REMOVAL**

STATION	WIDTH	AREA (SY)
-L-		
11+50.00 TO 14+47.50	20	661
14+87.50 TO 16+50.00	20	361
<b>TOTAL</b>		<b>1022</b>
<b>SAY</b>		<b>1080</b>

**FENCE SUMMARY**

STATION	LT/RT	LENGTH (FT)
WOVEN WIRE FENCE W/2 STRAND BARBED WIRE		
-L- STA 14+72.05 TO STA 20+20.01	RT	550
4 STRAND ELECTRIC FENCE		
-L- STA 17+68.38 TO STA 20+50.00	LT	350

5/28/99

25-AUG-2005 14:17  
s:\projects\B-4152-rdy-sum-040908.dgn