

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201293

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0022000000-E	225	3,400	CY	UNCLASSIFIED EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (14+70.00)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUB- BING
0057000000-E	226	200	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0195000000-E	265	100	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	20	TON	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRS
0343000000-E	310	24	LF	15" SIDE DRAIN PIPE
0366000000-E	310	64	LF	15" RC PIPE CULVERTS, CLASS III
0453000000-E	310	1	EA	*** PIPE END SECTION (15")
0708000000-E	310	48	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	4	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1110000000-E	510	50	TON	STABILIZER AGGREGATE
1330000000-E	607	250	SY	INCIDENTAL MILLING
1489000000-E	610	753	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	490	TON	ASPHALT CONC SURFACE COURSE, TYPE SP9.5A
1560000000-E	620	65	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2000000000-N	806	16	EA	RIGHT OF WAY MARKERS
2286000000-N	840	4	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	4	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	380	LF	SHOULDER BERM GUTTER

ItemNumber	Sec #	Quantity	Unit	Description
3030000000-E	862	575	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3566000000-E	867	550	LF	WOVEN WIRE FENCE RESET
3635000000-E	876	230	TON	PLAIN RIP RAP, CLASS II
3649000000-E	876	30	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	3,595	SY	FILTER FABRIC FOR DRAINAGE
4412000000-E	SP	128	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	94	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	10	EA	DRUMS
4435000000-N	1135	15	EA	CONES
4446100000-E	SP	64	LF	BARRICADES (TYPE III)
4450000000-N	1150	32	HR	FLAGGER
4810000000-E	1205	8,800	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	17	EA	PERMANENT RAISED PAVEMENT MARKERS
5300000000-E	1505	35	TON	FOUNDATION CONDITIONING MATE- RIAL, UTILITIES CLASS ***** (VI)
5306000000-E	SP	35	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
5450000000-E	1510	572	LF	8" PVC WATER PIPE, SDR ***** (SDR 21)
5480000000-E	1510	1,050	LB	DUCTILE IRON WATER PIPE FIT- TINGS, 250# MIN WP
5546000000-E	1510	2	EA	8" GATE VALVE & VALVE BOX, *****WP (200# WP)
5888000000-E	SP	80	LF	GENERIC UTILITY ITEM 8" DI RES JOINT WATER PIPE PC 350

ItemNumber	Sec #	Quantity	Unit	Description
5906000000-E	SP	1,050	LB	GENERIC UTILITY ITEM 8" DI RES JOINT WATER PIPE FITTINGS, PC 350
6000000000-E	1605	825	LF	TEMPORARY SILT FENCE
6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	165	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	75	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	2.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEED- ING
6029000000-E	SP	400	LF	SAFETY FENCE
6030000000-E	1630	620	CY	SILT EXCAVATION
6036000000-E	1631	2,750	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	100	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	2.5	ACR	SEEDING & MULCHING
6087000000-E	1660	1.5	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL

5/28/99

I:\AUG-2005 09h9
r:\roadwork\p\01\B4152-rdly-sum-040908.dgn
B4152-ROADWAY