

PROJECT NO.	SHEET NO.	TOTAL NO.
13CR.10611.4, 13CR.20611.3 13CR.306124.2, ETC.	5	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	SHOULDER RECONSTRUCTION SMI	1½" MILLING SY	BASE COURSE, B25.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TON	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	WHEELCHAIR RAMPS EA	METER OR VALVE BOX EA
13CR.10611.4	Mitchell	1	NC 226	SR 1337 TO SR 1352	1	2.91	19	146	5.82			3,017		181	150		
TOTAL FOR PROJ NO. 13CR.10611.4						2.91		146	5.82			3,017		181	150		
13CR.20611.3	Mitchell	2	SR 1164	SR 1168 TO SR 1171	2	0.71	19	36				723		47	50		
		3	SR 1171	SR 1164 TO SR 1172	2	0.31	19	16				316		21	30		
		4	SR 1172	SR 1171 TO SR 1170	2	0.36	19	18				367		24	50		
		5	SR 1250	SR 1167 TO NC 226	2	0.38	18	19				367		24	20		
		6	SR 1117	NC 226 TO SR 1226	2	1.54	20	77				1,650		107	80		
		7	SR 1116	NC 226 TO NC 226	3	0.73	18	37			403.00			704	63	15	
TOTAL FOR PROJ NO. 13CR.20611.3						4.03		203			403.00	4,127		286	245		
13CR.306124.2	Mitchell	8	SR 1275	WARD STREET TO US 19E	2	0.48	22	24				565		37	10		
TOTAL FOR PROJ NO. 13CR.306124.2						0.48		24				565		37	10		
13CR.11001.4	Yancey	9	US 19W	NEW PVMT SOUTH TO SR 1415	2	3.35	18	168				3,233		210	40		
		10	US 19W	SR 1415 TO SR 1414	2	0.7	18	35				675		44	20		
TOTAL FOR PROJ NO. 13CR.11001.4						4.05		203				3,908		254	60		
13CR.21001.3	Yancey	11	SR 1333	NC 197 TO EOM	3	1.7	18	85			938.00		1,640	147	75		
		12	SR 1331	SR 1333 TO EOM	3	0.55	18	28			303.00		531	48	40		
		13	SR 1440	NC 80N TO EOM	1	0.55	22	28				660		40	10		
		14	SR 1186	US 19E TO NC 80S	1	0.5	22	25				600		36	10		
		15	SR 1374	SR 1428 TO EOM	2	0.33	20	17					354	23	80		2
TOTAL FOR PROJ NO. 13CR.21001.3						3.63		183			1,241.00	1,260	2,525	294	215		2
38163	Yancey	16	SR 1428	SR 1373 TO SR 1373	4	0.2	36			4,928.00			495	32	10	5	
TOTAL FOR PROJ NO. 38163						0.2				4,928.00			495	32	10	5	
39817	Yancey	17	SR 1454	US 19-E IN NW DIRECTION 1200 FT	1	0.23	24	12				438		26	10		
TOTAL FOR PROJ NO. 39817						0.23		12				438		26	10		
GRAND TOTAL						15.53		771	5.82	4,928.00	1,644.00	4,715	11,620	1,110	700	5	2

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	4685000000-E	4686000000-E	4710000000-E	4721000000-E	4725000000-E	4810000000-E	4820000000-E
					4" X 90 M THERMO LF	4" X 120 M THERMO LF	24" X 120 M WHITE THERMO LF	THERMO MSG SCHOOL 120 M EA	THERMO RT ARROW 90 M EA	4" PAINT LF	8" WHITE PAINT LF
13CR.10611.4	Mitchell	1	NC 226	SR 1337 TO SR 1352	30,730	30,730	38	12			
TOTAL FOR PROJ NO. 13CR.10611.4					30,730	30,730	38	12			
13CR.20611.3	Mitchell	2	SR 1164	SR 1168 TO SR 1171						29,990	
		3	SR 1171	SR 1164 TO SR 1172						13,094	
		4	SR 1172	SR 1171 TO SR 1170						15,206	
		5	SR 1250	SR 1167 TO NC 226						16,051	
		6	SR 1117	NC 226 TO SR 1226			40	12		65,050	
		7	SR 1116	NC 226 TO NC 226						30,835	
TOTAL FOR PROJ NO. 13CR.20611.3							40	12		170,226	
13CR.306124.2	Mitchell	8	SR 1275	WARD STREET TO US 19E					2	20,275	
TOTAL FOR PROJ NO. 13CR.306124.2									2	20,275	
13CR.11001.4	Yancey	9	US 19W	NEW PVMT SOUTH TO SR 1415	35,376	35,376					
		10	US 19W	SR 1415 TO SR 1414	7,392	7,392					
TOTAL FOR PROJ NO. 13CR.11001.4					42,768	42,768					
13CR.21001.3	Yancey	11	SR 1333	NC 197 TO EOM						71,808	
		12	SR 1331	SR 1333 TO EOM						23,232	
		13	SR 1440	NC 80N TO EOM						23,232	
		14	SR 1186	US 19E TO NC 80S						21,120	
		15	SR 1374	SR 1428 TO EOM						13,939	
TOTAL FOR PROJ NO. 13CR.21001.3										153,331	
38163	Yancey	16	SR 1428	SR 1373 TO SR 1373							504
TOTAL FOR PROJ NO. 38163											504
39817	Yancey	17	SR 1454	US 19-E IN NW DIRECTION 1200 FT						9,715	
TOTAL FOR PROJ NO. 39817										9,715	
GRAND TOTAL					73,498	73,498	78	24	2	353,547	504