

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	1220000000-E	545	INCIDENTAL STONE BASE	400 TON		
0003	1245000000-E	SP	SHOULDER RECONSTRUCTION	14.8 SMI		
0004	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (4")	15,770 SY		
0005	1330000000-E	607	INCIDENTAL MILLING	2,200 SY		
0006	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE 119.0C	2,250 TON		
0007	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	5,160 TON		
0008	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	4,855 TON		
0009	1560000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22	415 TON		
0010	1565000000-E	620	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22	292 TON		
0011	1704000000-E	SP	PATCHING EXISTING PAVEMENT	150 TON		
0012	2815000000-N	858	ADJUSTMENT OF DROP INLETS	2 EA		
0013	2830000000-N	858	ADJUSTMENT OF MANHOLES	5 EA		
0014	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	7 EA		
0015	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	56,700 LF		
0016	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	29,580 LF		
0017	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	22 EA		

County : Richmond

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
001E	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	90,000 LF		
001S	4905000000-N	1253	SNOWPLOWABLE PAVEMENT MARKERS	515 EA		
002C	6084000000-E	1660	SEEDING & MULCHING	10.95 ACR		
0750/Jan19/Q208349.75/D52851100000/E20			Total Amount Of Bid For Entire Project :			

C201556
COUNTY: Richmond

2/16/99

Contract No: C201556
Counties: Richmond

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General