

## Note to Contractor for Robeson County

Secondary Package		
Map 12	SR 1571 (From ECL Pembroke to R/R)	Mill R/R approach on north side of Railroad
Map 15	SR 2115 (From ECL Lumberton to SR 2117)	Mill R/R approaches and bridge approaches
Primary Package		
Map 1	NC 41 (From SCL Lumberton to SR 1749)	Exclude 0.30 mi. for widening at SR 2235
Map 2	NC 71 (NCL Red Springs to SR 1749)	Mill and resurface bridge deck located approximately 0.4 mi. from SR 1749, exclude turn lanes at intersection of SR 1001 and NC 71, exclude bridge replacement project 0.60 mi. north of SR 1701 and exclude turn lanes at Mountaire Farms; Mill R/R approaches.
Map 5	NC 130 (SR 2225 to US 74)	Mill and resurface bridge deck
Map 4	NC 130 (From NC 130 to WCL Fairmont)	Replace rumble strips at SR 2442
Map 9	NC 710 (From US 74 to SR 1134)	Replace rumble strips at US 74, exclude US 74 project (approximately 0.40 mi., Mill and resurface bridge decks, school zone.
Urban Package		
Map 20	NC 71 (From NCL Lumber Bridge to SCL Lumber Bridge)	No milling at curb and gutter, Fill curb and gutter section.
Map 21	SR 1997 (CJ east of I-95 to SR 1005)	Construction shall start at grade separation at I-95, micro surface (rut filling) will be required, work shall be between 7:00 p.m. and 6:00 a.m. the next morning.