REVISIONS

PROJECT REFERENCE NO.	SHEET NO.
I-4700	3
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

7/2/99

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201326

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0063000000-N	SP	Lump Sum		GRADING
0106000000-E	230	1,600	CY	BORROW EXCAVATION
0372000000-E	310	20	LF	18" RC PIPE CULVERTS, CLASS III
0378000000-E	310	8	LF	24" RC PIPE CULVERTS, CLASS III
1245000000-E	SP	66.4	SMI	SHOULDER RECONSTRUCTION
1297000000-E	607	236,000	SY	MILLING ASPHALT PAVEMENT, ***" DEPTH (2-1/2")
1308000000-E	607	~~28,800~~ 48,900	SY	MILLING ASPHALT PAVEMENT, ***" TO *******" DEPTH (2-1/2" TO 4-1/2")
1330000000-E	607	500	SY	INCIDENTAL MILLING
1491000000-E	610	1,700	TON	ASPHALT CONC BASE COURSE, TYPE B25.0C
1508000000-E	610	~~22,000~~ 36,800	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0D
1550000000-E	610	91,000	TON	ASPHALT CONC SURFACE COURSE, TYPE S12.5D
1560000000-E	620	73	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1565000000-E	620	~~[illegible]~~ 1730	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 70-22
1570000000-E	620	4,368	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 76-22
1704000000-E	SP	50	TON	PATCHING EXISTING PAVEMENT
1840000000-E	665	350,000	LF	MILLED RUMBLE STRIPS
1880000000-E	SP	750	TON	GENERIC PAVING ITEM PATCHING EXISTING PAVEMENT (FULL DEPTH REPAIR)
2154000000-N	820	70	EA	METAL FUNNELS
2165000000-E	820	3,150	LF	12" FUNNEL DRAIN PIPE
2176000000-E	820	62	EA	12" FUNNEL DRAIN PIPE ELBOWS
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2354000000-N	840	1	EA	FRAME WITH GRATE, STD 840.22

ItemNumber	Sec #	Quantity	Unit	Description
2486000000-E	SP	160	SF	GENERIC DRAINAGE ITEM PATCH CONCRETE APRON FOR DROP INLET
2486000000-E	SP	280	SF	GENERIC DRAINAGE ITEM PATCH DRAINAGE STRUCTURE
2486000000-E	SP	14	SF	GENERIC DRAINAGE ITEM PATCH RC PIPE CULVERT
2647000000-E	852	650	SY	5" MONOLITHIC CONCRETE ISLANDS (SURFACE MOUNTED)
2655000000-E	852	580	SY	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)
3030000000-E	862	7,000	LF	STEEL BM GUARDRAIL
3045000000-E	862	450	LF	STEEL BM GUARDRAIL, SHOP CURVED
3075000000-E	862	660	LF	TRIPLE CORRUGATED STEEL BM GUARDRAIL
3135000000-N	862	5	EA	W-TR STEEL BM GUARDRAIL TRANSITION SECTIONS
3150000000-N	862	20	EA	ADDITIONAL GUARDRAIL POSTS
3180000000-N	862	8	EA	GUARDRAIL ANCHOR UNITS, TYPE ********** III Modified
3210000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE CAT-1
3270000000-N	SP	17	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3285000000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE M-350
3503000000-E	866	5,000	LF	WOVEN WIRE FENCE, 47" FABRIC
3506000000-E	866	350	EA	4" TIMBER FENCE POSTS, ***** LONG (8')
3515000000-E	866	20	EA	5" TIMBER FENCE POSTS, 8'-0" LONG
4412100000-E	SP	400	SF	WORK ZONE SIGNS (PORTABLE)
4415000000-N	1115	2	EA	FLASHING ARROW PANELS, TYPE C
4420000000-N	1120	6	EA	CHANGEABLE MESSAGE SIGN
4430000000-N	1130	200	EA	DRUMS
4465000000-N	1160	1	EA	TEMPORARY CRASH CUSHIONS

ItemNumber	Sec #	Quantity	Unit	Description
4480000000-N	1165	2	EA	TRUCK MOUNTED IMPACT ATTENUATOR (60 MPH)
4490000000-E	1170	1,600	LF	PORTABLE CONCRETE BARRIER (ANCHORED)
4600000000-N	SP	80	EA	GENERIC TRAFFIC CONTROL ITEM SKINNY DRUMS
4620000000-E	1205	4,000	LF	REMOVABLE TAPE PAVEMENT MARKING LINES (6")
4685000000-E	1205	19,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)
4688000000-E	1205	360,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 90 MILS)
4690000000-E	1205	47,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (6", 120 MILS)
4695000000-E	1205	1,022	LF	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)
4700000000-E	1205	8,000	LF	THERMOPLASTIC PAVEMENT MARKING LINES (12", 90 MILS)
4810000000-E	1205	451,000	LF	PAINT PAVEMENT MARKING LINES (4")
4825000000-E	1205	2,000	LF	PAINT PAVEMENT MARKING LINES (12")
4855000000-E	1205	4,000	LF	REMOVAL OF PAVEMENT MARKING LINES (6")
4900000000-N	1252	200	EA	PERMANENT RAISED PAVEMENT MARKERS
4905000000-N	1253	2,500	EA	SNOWPLOWABLE PAVEMENT MARKERS
5255000000-N	1413	Lump Sum		PORTABLE LIGHTING
6012000000-E	1610	20	TON	SEDIMENT CONTROL STONE
6042000000-E	1632	100	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	82.48	ACR	SEEDING & MULCHING
6090000000-E	1661	25	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.13	TON	FERTILIZER FOR REPAIR SEEDING

$$$$SYSTIME$$$$DGN$$$$$$$$$$$$$$$$
$$$$USERNAME$$