

8/17/99

INDEX OF SHEETS	
SHEET NUMBER	SHEET
1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
2 THRU 2A	PAVEMENT SCHEDULE, TYPICAL SECTIONS, AND MILLING DETAILS
2B	RUMBLE STRIPS DETAIL
2C THRU 2D	DETAIL OF GUARDRAIL ANCHOR UNIT TYPE <u>III MODIFIED</u>
2E THRU 2H	DETAIL OF GUARDRAIL INSTALLATION
3	SUMMARY OF QUANTITIES
3A	GUARDRAIL SUMMARY
3B	DRAINAGE SUMMARY
4 THRU 6	PLAN SHEETS
TCP-1 THRU TCP-12	TRAFFIC CONTROL PLANS

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.03	Deceleration and Acceleration Lanes
225.05	Method of Obtaining Superelevation - Divided Highways
DIVISION 3 - PIPE CULVERTS	
300.01	Method of Pipe Installation - Method 'A'
DIVISION 6 - ASPHALT BASES AND PAVEMENTS	
610.01	Guide for Paving Shoulders Under Bridges - Method I
610.02	Guide for Paving Shoulders Under Bridges - Method II
DIVISION 8 - INCIDENTALS	
820.01	Funnel and Funnel Drain - 12" Metal Funnel
840.00	Concrete Base Pad for Drainage Structures
840.18	Concrete Median Drop Inlet Type 'B' - 12" thru 36" Pipe
840.22	Frames and Wide Slot Sag Grates
840.45	Precast Drainage Structure
840.66	Drainage Structure Steps
852.01	Concrete Islands
862.01	Guardrail Placement
866.02	Woven Wire Fence - with Wood Post

GENERAL NOTES:

GRADING AND SURFACING OR RESURFACING AND WIDENING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

SYSTEM GENERATED  
 ON 08/17/99 10:51 AM  
 BY: [unreadable]