P:\4100\MA05001B\Roadway\Xsc\Copy of ear_L.log

PROJ. REFERENCE NO.	SHEET NO.
MA05001B	X-0

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

Approximate quantities only. Unclassified excavation, borrow excavation, shoulder borrow, fine grading, clearing and grubbing, breaking of existing pavement and removal of existing pavement will be paid for at the lump sum price for "Grading".

NOTE: EMBANKMENT COLUMN INCLUDES BACKFILL FOR UNDERCUT

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
12+00.00	0	0
12+50.00	0	22
13+00.00	0	30
15+00.00	0	0
15+50.00	0	125
16+00.00	0	112
16+50.00	100	220
17+00.00	226	359
17+50.00	257	460
18+00.00	195	391
18+50.00	128	144

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00	0	0
10+50.00	15	28

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

RALEIGH

BRIDGE #133 ON SR 1930
OVER RICHLAND CREEK

REVISIONS			SHEET NO.
NO.	BY	DATE	
			TOTAL SHEETS