

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0248000000-N	SP	GENERIC GRADING ITEM EXCAVATION & EMBANKMENT	Lump Sum	L.S.	
0003	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRS	10 TON		
0004	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	72 LF		
0005	0995000000-E	340	PIPE REMOVAL	40 LF		
0006	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	544 TON		
0007	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	250 TON		
0008	1525000000-E	SP	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A	515 TON		
0009	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0010	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (E)	1 EA		
0011	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** (G)	2 EA		
0012	2484000000-E	SP	GENERIC DRAINAGE ITEM REMOVE & RESET EXISTING 18" RCP CULVERT	40 LF		
0013	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	30 LF		
0014	2591000000-E	848	4" CONCRETE SIDEWALK	17 SY		
0015	2830000000-N	858	ADJUSTMENT OF MANHOLES	1 EA		
0016	2995000000-N	SP	GENERIC DRAINAGE ITEM ADJUSTMENT OF EXISTING DRAINAGE STRUCTURE	1 EA		
0017	3422000000-N	SP	GENERIC GUARDRAIL ITEM STEEL BEAM GUARDRAIL	Lump Sum	L.S.	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	3628000000-E	876	PLAIN RIP RAP, CLASS I	423 TON		
0019	3635000000-E	876	PLAIN RIP RAP, CLASS II	380 TON		
0020	3656000000-E	876	FILTER FABRIC FOR DRAINAGE	689 SY		
0021	6000000000-E	1605	TEMPORARY SILT FENCE	1,250 LF		
0022	6133000000-N	SP	GENERIC EROSION CONTROL ITEM EROSION CONTROL	Lump Sum	L.S.	
0023	8056000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (13+37.012 -L-)	Lump Sum	L.S.	
0024	8105540000-E	SP	3'-6" DIA DRILLED PIERS IN SO IL	121 LF		
0025	8105640000-E	SP	3'-6" DIA DRILLED PIERS NOT IN SOIL	26 LF		
0026	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+04.00 -L-)	Lump Sum	L.S.	
0027	8364000000-E	450	HP12X53 STEEL PILES	494 LF		
0028	8475000000-E	460	TWO BAR METAL RAIL	245 LF		
0029	8860000000-N	SP	GENERIC STRUCTURE ITEM PLACEMENT OF SUBSTRUCTURE	Lump Sum	L.S.	
0030	8860000000-N	SP	GENERIC STRUCTURE ITEM PLACEMENT OF SUPERSTRUCTURE	Lump Sum	L.S.	
0031	8867000000-E	SP	GENERIC STRUCTURE ITEM PARAPET & END POSTS	261 LF		
0032	5912000000-N	SP	GENERIC UTILITY ITEM 8" SANITARY SEWER	Lump Sum	L.S.	
0033	5912000000-N	SP	GENERIC UTILITY ITEM 12" WATER LINE	Lump Sum	L.S.	

C201562
COUNTY: Wake

2/16/99

Contract No: C201562
County: Wake

ACCEPTED BY THE
DEPARTMENT OF TRANSPORTATION

Contract Officer

Date

Execution of Contract and Bonds
Approved as to Form:

Attorney General