

PROJECT NO.	SHEET NO.	TOTAL NO.
5CR.10931.4, 5CR.20931.4, & 5CR.309318.4	9	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LENGTH MI	WIDTH FT	INCIDENTAL STONE BASE TONS	1½" MILLING SY	2½" MILLING SY	INCIDENTAL MILLING SY	INTERMEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	SURFACE COURSE, SF9.5A TONS	PG 64-22 PLANT MIX TONS	INDUCTIVE LOOP LF
5CR.10931.4	Warren	1	US 1/401	FROM NORLINA CL TO VA LINE	1	7.08	22	170			2,200		8,105		486	
		2	NC 43	FROM SR 1507 (DAVIS ROAD) TO SR 1519 @ ARCOLA	3	5.66	20	136		2,900		500		5,513	382	
TOTAL FOR PROJ NO. 5CR.10931.4						12.74		306		2,900	2,200	500	8,105	5,513	868	
5CR.20931.4	Warren	3	SR 1309 (OAKVILLE ROAD)	FROM SR 1500 (DOC THOMPSON ROAD) TO SR 1306 (WISE FIVE FORKS ROAD)	4	3.14	22	75						2,799	182	
		4	SR 1320 (NORLINA-WARREN PLAINS ROAD)	FROM SR 1305 (WARREN PLAINS ROAD) TO EAST CITY LIMIT NORLINA	5	1.54	22	37						1,679	109	
		5	SR 1323 (CONNELL ROAD)	FROM SR 1305 (WARREN PLAINS ROAD) TO US 401/158 BUS.	5	1.15	22	28						1,254	82	
		6	SR 1306 (ROBINSON FERRY ROAD)	FROM SR 1335 (CHURCH HILL ROAD) TO SR 1389 (PASTURE GATE ROAD)	5	0.84	20	20						833	54	
TOTAL FOR PROJ NO. 5CR.20931.4						6.67		160						6,565	427	
5CR.309318.4	Warren	7	US 158/401	FROM US 1/401 TO MAIN STREET/CHERRY STREET	2	0.16	28.5	4	2,675				226		14	800
TOTAL FOR PROJ NO. 5CR.309318.4						0.16		4	2,675				226		14	800
GRAND TOTAL						19.57		470	2,675	2,900	2,200	500	8,331	12,078	1,309	800