STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201399

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0000400000-N	801	Lump Sum		CONSTRUCTION SURVEYING
0022000000-E	225	14,400	CY	UNCLASSIFIED EXCAVATION
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ********** (17-03.50-L-)
0050000000-E	226	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
0057000000-E	226	100	CY	UNDERCUT EXCAVATION
0063000000-N	SP	Lump Sum		GRADING
0080000000-E	SP	500	TON	CLASS IV SUBGRADE STABILIZATION
0134000000-E	240	50	CY	DRAINAGE DITCH EXCAVATION
0195000000-E	265	500	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
0199000000-E	SP	1,280	SF	TEMPORARY SHORING
0318000000-E	300	67	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0360000000-E	310	8	LF	12" RC PIPE CULVERTS, CLASS III
0366000000-E	310	92	LF	15" RC PIPE CULVERTS, CLASS III
0372000000-E	310	104	LF	18" RC PIPE CULVERTS, CLASS III
0378000000-E	310	48	LF	24" RC PIPE CULVERTS, CLASS III
0708000000-E	310	120	LF	15" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0714000000-E	310	192	LF	18" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0720000000-E	310	28	LF	24" BIT COAT CS PIPE CULVERTS, TYPE B 0.064" THICK
0806000000-E	310	6	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0807000000-E	310	6	EA	18" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0808000000-E	310	2	EA	24" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
0995000000-E	340	200	LF	PIPE REMOVAL
1121000000-E	520	1,100	TON	AGGREGATE BASE COURSE
1220000000-E	545	50	TON	INCIDENTAL STONE BASE
1489000000-E	610	270	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1498000000-E	610	150	TON	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B
1525000000-E	SP	880	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	74	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
1693000000-E	654	30	TON	ASPHALT PLANT MIX, PAVEMENT REPAIR
2000000000-N	806	10	EA	RIGHT OF WAY MARKERS
2022000000-E	815	225	CY	SUBDRAIN EXCAVATION
2033000000-E	815	170	CY	SUBDRAIN FINE AGGREGATE
2044000000-E	815	1,000	LF	6" PERFORATED SUBDRAIN PIPE
2055000000-E	815	30	EA	6" SUBDRAIN PIPE WYES, TEES, & ELBOWS
2066000000-N	815	2	EA	CONCRETE PAD FOR SUBDRAIN PIPE OUTLET
2077000000-E	815	12	LF	6" OUTLET PIPE (SUBDRAINS)
2154000000-N	820	1	EA	METAL FUNNELS
2165000000-E	820	24	LF	12" FUNNEL DRAIN PIPE
2176000000-E	820	2	EA	12" FUNNEL DRAIN PIPE ELBOWS
2190000000-N	828	1	EA	TEMPORARY STEEL PLATE COVERS FOR MASONRY DRAINAGE STRUCTURE
2264000000-E	840	1	CY	PIPE PLUGS
2286000000-N	840	8	EA	MASONRY DRAINAGE STRUCTURES
2319000000-N	840	1	EA	FRAME WITH GRATE, DETAIL 840.***** (840.16)
2366000000-N	840	2	EA	FRAME WITH TWO GRATES, STD 840.24
2367000000-N	840	5	EA	FRAME WITH TWO GRATES, STD 840.29
2500000000-E	842	15	CY	CONCRETE RETAINING WALLS
2556000000-E	846	10	LF	SHOULDER BERM GUTTER
2577000000-E	846	200	LF	CONCRETE EXPRESSWAY GUTTER
2619000000-E	850	115	SY	4" CONCRETE PAVED DITCH
2724000000-E	857	270	LF	PRECAST REINFORCED CONCRETE BARRIER, SINGLE FACED
3000000000-N	SP	1	EA	IMPACT ATTENUATOR UNIT, TYPE 350
3030000000-E	862	400	LF	STEEL BM GUARDRAIL
3045000000-E	862	37.5	LF	STEEL BM GUARDRAIL, SHOP CURVED
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3195000000-N	862	1	EA	GUARDRAIL ANCHOR UNITS, TYPE AT-1
3215000000-N	862	3	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	3	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3360000000-E	863	665	LF	REMOVE EXISTING GUARDRAIL
3380000000-E	862	675	LF	TEMPORARY STEEL BM GUARDRAIL
3387000000-N	862	2	EA	GUARDRAIL ANCHOR UNITS, TYPE ********** TEMPORARY (B-77)
3387000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE ********** TEMPORARY (III)
3389100000-N	SP	1	EA	GUARDRAIL ANCHOR UNITS, TYPE 350 TEMPORARY
3559000000-E	866	550	LF	** STRAND BARBED WIRE FENCE WITH POSTS (3)
3649000000-E	876	50	TON	PLAIN RIP RAP, CLASS B
3656000000-E	876	570	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	3	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON
4025000000-E	901	12.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	54	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	2	EA	SIGN ERECTION, TYPE E
4129000000-N	906	1	EA	RELOCATE SIGN, TYPE ***** (E)
4155000000-N	907	1	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4158000000-N	907	4	EA	DISPOSAL OF SIGN SYSTEM, WOOD
4192000000-N	907	1	EA	DISPOSAL OF SUPPORT, U-CHANNEL
4412000000-E	SP	128	SF	WORK ZONE SIGNS (STATIONARY)
4412100000-E	SP	96	SF	WORK ZONE SIGNS (PORTABLE)
4412200000-E	SP	52	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4430000000-N	1130	55	EA	DRUMS
4446100000-E	SP	64	LF	BARRICADES (TYPE III)
4450000000-N	1150	480	HR	FLAGGER
4465000000-N	1160	2	EA	TEMPORARY CRASH CUSHIONS
4490000000-E	1170	230	LF	PORTABLE CONCRETE BARRIER (ANCHORED)
4495000000-E	1170	80	LF	PORTABLE CONCRETE BARRIER (DRAINAGE)
4650000000-N	1251	29	EA	TEMPORARY RAISED PAVEMENT MARKERS
4810000000-E	1205	16,576	LF	PAINT PAVEMENT MARKING LINES (4")
4847000000-E	SP	4,620	LF	POLYUREA PAVEMENT MARKING LINES (4")
4905000000-N	1253	29	EA	SNOWPLOWABLE PAVEMENT MARKERS
6000000000-E	1605	900	LF	TEMPORARY SILT FENCE
6006000000-E	1610	115	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	315	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	325	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	3.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	150	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	200	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	1,540	LF	SAFETY FENCE
6030000000-E	1630	1,180	CY	SILT EXCAVATION
6036000000-E	1631	1,200	SY	MATTING FOR EROSION CONTROL
6038000000-E	SP	10	SY	PERMANENT SOIL REINFORCEMENT MAT
6042000000-E	1632	500	LF	1/4" HARDWARE CLOTH
6070000000-N	SP	3	EA	SPECIAL STILLING BASINS
6084000000-E	1660	3.5	ACR	SEEDING & MULCHING
6087000000-E	1660	2	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	75	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	2.75	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2.5	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL
6123000000-E	1670	0.8	ACR	REFORESTATION

5/28/99
6/24/2005
11:26:49
H:\projects\c-4007_rdy_PSH_03.dgn