

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	ROUTE	DESCRIPTION	TYP	LENGTH MI	WIDTH FT	CON-STRUC-TION SURVEY LS	GRADING LS	SUPPL. CLEARING & GRUBBING AC	UNDERCUT EXCAV. CY	DITCHING LF	FOUND. COND. MATERIAL TONS	15" RC PIPE CULVERT CLASS III LF	18" RC PIPE CULVERT CLASS III LF	PIPE REMOVAL LF	SEAL. EXIST. PAVEMENT CRACKS LBS	INCIDENTAL STONE BASE TONS	SHOULDER RECON-STRUCTION SMI	INCIDENTAL MILLING SY	0" TO 3" MILLING SY
31339	Bladen	SR 1300	FROM CUMBERLAND CO. LINE TO NC 20	1	2.5	24	0	0	0	0	0	0	0	0	0	4,500	50	5.00	100	400
TOTAL FOR PROJ NO. 31339					2.5	24	0	0	0	0	0	0	0	0	0	4,500	50	5.00	100	400
37969	Cumberland	SR 2252	FROM SR 3925 (BYERLY DR.) TO SR 2241 (CLIFTON MCNEILL RD.)	5	0.49	40	1	1	1	250	0	40	60	272	180	0	30	0	100	0
TOTAL FOR PROJ NO. 37969					0.49	40	1	1	1	250	0	40	60	272	180	0	30	0	100	0
37977	Cumberland	SR 2252	FROM I-95 SR 3925 (BYERLY DR.) AND FROM SR 2241 (CLIFTON MCNEILL RD.) TO BLADEN CO. LINE	2, 3, 6, 7 (See Typical Sections)	7.2	28 - 39	0	0	0	0	1,000	0	0	0	0	9,500	200	14.37	100	0
TOTAL FOR PROJ NO. 37977					7.2	28 - 39	0	0	0	0	1,000	0	0	0	0	9,500	200	14.37	100	0
GRAND TOTAL					10.19		1	1	1	250	1,000	40	60	272	180	14,000	280	19.37	300	400

PROJECT NO	COUNTY	ROUTE	DESCRIPTION	TYP	BASE COURSE, B25.0B TONS	INTER-MEDIATE COURSE, I19.0B TONS	SURFACE COURSE, S9.5B TONS	PG 64-22 PLANT MIX TONS	PATCHING EXISTING PAVEMENT TONS	PIPE COLLAR CY	6" DRIVE-WAYS SY	ADJ. OF MANHOLES EA	ADJ. OF METER OR VALVE BOX EA	SILT FENCE LF	STONE FOR EROSION CONTROL TONS	SEDIMENT CONTROL STONE TONS	SEED & MULCHING AC	SEED FOR REPAIR SEEDING LBS	FERTILIZER FOR REPAIR SEEDING TONS
31339	Bladen	SR 1300	FROM CUMBERLAND CO. LINE TO NC 20	1	3,200	0	3,200	330	0	0.0	40	1	1	200	20	20	9.09	25	0.13
TOTAL FOR PROJ NO. 31339					3,200	0	3,200	330	0	0.0	40	1	1	200	20	20	9.09	25	0.13
37969	Cumberland	SR 2252	FROM SR 3925 (BYERLY DR.) TO SR 2241 (CLIFTON MCNEILL RD.)	5	1,100	700	1,700	182	0	1.0	0	1	1	200	20	20	1.77	25	0.13
TOTAL FOR PROJ NO. 37969					1,100	700	1,700	182	0	1.0	0	1	1	200	20	20	1.77	25	0.13
37977	Cumberland	SR 2252	FROM I-95 SR 3925 (BYERLY DR.) AND FROM SR 2241 (CLIFTON MCNEILL RD.) TO BLADEN CO. LINE	2, 3, 6, 7 (See Typical Sections)	4,250	0	13,700	1,005	50	0.0	310	1	1	400	40	40	27.44	25	0.13
TOTAL FOR PROJ NO. 37977					4,250	0	13,700	1,005	50	0.0	310	1	1	400	40	40	27.44	25	0.13
GRAND TOTAL					8,550	700	18,600	1,517	50	1.0	350	3	3	800	80	80	38.3	75	0.39

THERMOPLASTIC AND PAINT QUANTITIES

PROJECT NO	COUNTY	ROUTE	DESCRIPTION	4685000000-E		4686000000-E		4695000000-E		4697000000-E		4705000000-E		4710000000-E		4721000000-E		4725000000-E		
				4" X 90 M WHITE THERMO LF	4" X 120 M WHITE THERMO LF	4" X 120 M YELLOW THERMO LF	8" X 90 M WHITE THERMO LF	8" X 120 M YELLOW THERMO LF	16" X 120 M WHITE THERMO LF	24" X 120 M WHITE THERMO LF	THERMO RXR 120 M EA	THERMO SCHOOL 120 M EA	THERMO LT ARROW 90 M EA	THERMO STR ARROW 90 M EA	THERMO RT ARROW 90 M EA					
31339	Bladen	SR 1300	FROM CUMBERLAND CO. LINE TO NC 20	26,400	36	11,300						88	40	4						
TOTAL FOR PROJ NO. 31339				26,400	36	11,300						88	40	4						
37969	Cumberland	SR 2252	FROM SR 3925 (BYERLY DR.) TO SR 2241 (CLIFTON MCNEILL RD.)	6,200	85	6,940						220					10			
TOTAL FOR PROJ NO. 37969				6,200	85	6,940						220					10			
37977	Cumberland	SR 2252	FROM I-95 SR 3925 (BYERLY DR.) AND FROM SR 2241 (CLIFTON MCNEILL RD.) TO BLADEN CO. LINE	75,112	2,000	63,341	212	535				252		12	12	16	4	4	6	6
TOTAL FOR PROJ NO. 37977				75,112	2,000	63,341	212	535				252		12	12	16	4	4	6	6
GRAND TOTAL				107,712	83,914	212	755	88	292	16	36									

PROJECT NO	COUNTY	ROUTE	DESCRIPTION	4810000000-E		4820000000-E		4830000000-E		4835000000-E		4840000000-N			4845000000-N			4900000000-N	
				4" WHITE PAINT LF	4" YELLOW PAINT LF	8" YELLOW PAINT LF	8" WHITE PAINT LF	16" WHITE PAINT LF	24" WHITE PAINT LF	PAINT MSG RXR EA	PAINT MSG SCHOOL EA	PAINT LT ARROW EA	PAINT STR ARROW EA	PAINT RT ARROW EA	CYAN & RED MARKERS EA	YELLOW & YELLOW MARKER EA			
31339	Bladen	SR 1300	FROM CUMBERLAND CO. LINE TO NC 20	36	11,300					88	40	4							180
TOTAL FOR PROJ NO. 31339				36	11,300					88	40	4							180
37969	Cumberland	SR 2252	FROM SR 3925 (BYERLY DR.) TO SR 2241 (CLIFTON MCNEILL RD.)	85	6,940	220									10			4	140
TOTAL FOR PROJ NO. 37969				85	6,940	220									10			4	140
37977	Cumberland	SR 2252	FROM I-95 SR 3925 (BYERLY DR.) AND FROM SR 2241 (CLIFTON MCNEILL RD.) TO BLADEN CO. LINE	2,000	63,341	535	212			252		12	16	4	6	6	86	1,344	1,344
TOTAL FOR PROJ NO. 37977				2,000	63,341	535	212			252		12	16	4	6	6	86	1,344	1,344
GRAND TOTAL				83,702	967	88	292	16	36										