

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201470

ItemNumber	Sec #	Quantity	Unit	Description
0000100000-N	800	Lump Sum		MOBILIZATION
0008000000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUB-BING
0029000000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (17+59.40)
0036000000-E	225	200	CY	UNDERCUT EXCAVATION
0043000000-N	226	Lump Sum		GRADING
0195000000-E	265	300	CY	SELECT GRANULAR MATERIAL
0196000000-E	270	100	SY	FABRIC FOR SOIL STABILIZATION
0318000000-E	300	6	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
0684000000-E	310	48	LF	*** BIT COAT CS PIPE CULVERTS, TYPE B ***** THICK 15", 0.064" THICK
0806000000-E	310	2	EA	15" BIT COAT CS PIPE ELBOWS, TYPE B 0.064" THICK
1489000000-E	610	327	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
1525000000-E	SP	228	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
1560000000-E	620	30	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
2000000000-N	806	16	EA	RIGHT OF WAY MARKERS
2286000000-N	840	1	EA	MASONRY DRAINAGE STRUCTURES
2367000000-N	840	1	EA	FRAME WITH TWO GRATES, STD 840.29
2556000000-E	846	241	LF	SHOULDER BERM GUTTER
3030000000-E	862	500	LF	STEEL BM GUARDRAIL
3150000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
3215000000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III
3270000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
3656000000-E	876	300	SY	FILTER FABRIC FOR DRAINAGE
3659000000-N	SP	1	EA	PREFORMED SCOUR HOLES WITH LEVEL SPREADER APRON

ItemNumber	Sec #	Quantity	Unit	Description
4025000000-E	901	8.5	SF	CONTRACTOR FURNISHED, TYPE *** SIGN (E)
4072000000-E	903	16	LF	SUPPORTS, 3-LB STEEL U-CHANNEL
4102000000-N	904	2	EA	SIGN ERECTION, TYPE E
4155000000-N	907	7	EA	DISPOSAL OF SIGN SYSTEM, U-CHANNEL
4158000000-N	907	2	EA	DISPOSAL OF SIGN SYSTEM, WOOD
4412000000-E	SP	286	SF	WORK ZONE SIGNS (STATIONARY)
4412200000-E	SP	69	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
4425000000-N	1125	1	EA	WARNING FLAG SETS
4446100000-E	SP	96	LF	BARRICADES (TYPE III)
4810000000-E	1205	6,640	LF	PAINT PAVEMENT MARKING LINES (4")
4900000000-N	1252	15	EA	PERMANENT RAISED PAVEMENT MARKERS
6000000000-E	1605	1,400	LF	TEMPORARY SILT FENCE
6006000000-E	1610	150	TON	STONE FOR EROSION CONTROL, CLASS A
6009000000-E	1610	210	TON	STONE FOR EROSION CONTROL, CLASS B
6012000000-E	1610	80	TON	SEDIMENT CONTROL STONE
6015000000-E	1615	1.5	ACR	TEMPORARY MULCHING
6018000000-E	1620	50	LB	SEED FOR TEMPORARY SEEDING
6021000000-E	1620	0.25	TON	FERTILIZER FOR TEMPORARY SEEDING
6024000000-E	1622	50	LF	TEMPORARY SLOPE DRAINS
6027000000-N	1622	2	EA	INLET PROTECTION AT TEMPORARY SLOPE DRAINS
6029000000-E	SP	150	LF	SAFETY FENCE
6030000000-E	1630	380	CY	SILT EXCAVATION
6036000000-E	1631	160	SY	MATTING FOR EROSION CONTROL
6042000000-E	1632	20	LF	1/4" HARDWARE CLOTH
6084000000-E	1660	1.5	ACR	SEEDING & MULCHING

ItemNumber	Sec #	Quantity	Unit	Description
6087000000-E	1660	1	ACR	MOWING
6090000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
6093000000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
6096000000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
6108000000-E	1665	1	TON	FERTILIZER TOPDRESSING
6114000000-N	SP	2	HR	SPECIALIZED HAND MOWING
6117000000-N	1675	8	EA	RESPONSE FOR EROSION CONTROL