

STATE OF NORTH CAROLINA  
 DIVISION OF HIGHWAYS

**SUMMARY OF EARTHWORK**  
 IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	EMBT + %	BORROW
-L- 14+00 TO 17+70	3	1554	1551
-L- 19+30 TO 23+00		1663	1663
PROJECT TOTALS	3	3216	3213
EST. 5% TO REPLACE TOPSOIL ON BORROW PITS			161
GRAND TOTAL	3		3374
SAY	100		3400

UNDERCUT EXCAVATION = 200 c.y.

Note: "Quantities are approximate only. The Resident Engineer will re-cross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid."

**SUMMARY OF PAVEMENT REMOVAL**  
 IN SQUARE YARDS

LINE	BEGIN STATION	END STATION	LOCATION	ASPHALT PAVEMENT REMOVAL
-L-	16+50.00	17+94.00	CL	288
-L-	19+14.00	21+50.00	CL	372
-L-	15+50.00	16+50.00	RT	11
			TOTAL	671
			SAY	700