

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF QUANTITIES

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
ROADWAY SUMMARY OF QUANTITIES FOR CONTRACT - C201441

ItemNumber	Sec #	Quantity	Unit	Description
000100000-N	800	Lump Sum		MOBILIZATION
000100000-E	200	Lump Sum		CLEARING & GRUBBING .. ACRE(S)
000800000-E	200	1	ACR	SUPPLEMENTARY CLEARING & GRUBBING
002200000-E	225	100	CY	UNCLASSIFIED EXCAVATION
002900000-N	SP	Lump Sum		REINFORCED BRIDGE APPROACH FILL, STATION ***** (18+50.00-L-)
003600000-E	225	200	CY	UNDERCUT EXCAVATION
010600000-E	230	3,400	CY	BORROW EXCAVATION
015600000-E	250	700	SY	REMOVAL OF EXISTING ASPHALT PAVEMENT
019500000-E	265	500	CY	SELECT GRANULAR MATERIAL
019600000-E	270	500	SY	FABRIC FOR SOIL STABILIZATION
031800000-E	300	6	TON	FOUNDATION CONDITIONING MATERIAL, MINOR STRS
066000000-E	310	52	LF	****BIT COAT CS PIPE CULVERTS, TYPE A ***** THICK (15", 0.064")
068000000-E	310	4	EA	*** BIT COAT CS PIPE ELBOWS, TYPE A ***** THICK (15", 0.064")
101100000-N	500	Lump Sum		FINE GRADING
148900000-E	610	400	TON	ASPHALT CONC BASE COURSE, TYPE B25.0B
152500000-E	SP	400	TON	ASPHALT CONC SURFACE COURSE, TYPE SF9.5A
156000000-E	620	44	TON	ASPHALT BINDER FOR PLANT MIX, GRADE PG 64-22
228600000-N	840	2	EA	MASONRY DRAINAGE STRUCTURES
235500000-N	840	2	EA	FRAME WITH GRATE, STD 840.29
255600000-E	846	130	LF	SHOULDER BERM GUTTER
303000000-E	862	575	LF	STEEL BM GUARDRAIL
315000000-N	862	5	EA	ADDITIONAL GUARDRAIL POSTS
321500000-N	862	4	EA	GUARDRAIL ANCHOR UNITS, TYPE III

ItemNumber	Sec #	Quantity	Unit	Description
327000000-N	SP	4	EA	GUARDRAIL ANCHOR UNITS, TYPE 350
364900000-E	876	4	TON	PLAIN RIP RAP, CLASS B
365600000-E	876	214	SY	FILTER FABRIC FOR DRAINAGE
441200000-E	SP	224	SF	WORK ZONE SIGNS (STATIONARY)
441220000-E	SP	70	SF	WORK ZONE SIGNS (BARRICADE MOUNTED)
444610000-E	SP	96	LF	BARRICADES (TYPE III)
530000000-E	1505	6	TON	FOUNDATION CONDITIONING MATERIAL, UTILITIES CLASS ***** (VI)
530600000-E	SP	6	TON	BEDDING MATERIAL, UTILITIES CLASS ***** (IV)
545000000-E	1510	108	LF	8" PVC WATER PIPE, SDR ***** (200# WP)
548000000-E	1510	530	LB	DUCTILE IRON WATER PIPE FITTINGS, 250# MIN WP
554600000-E	1510	1	EA	8" GATE VALVE & VALVE BOX, *****WP (200#)
588800000-E	SP	667	LF	GENERIC UTILITY ITEM 10" HDPE WATER PIPE, SDR 9 200# WP BY DIRECTIONAL BORE
600000000-E	1605	1,400	LF	TEMPORARY SILT FENCE
600600000-E	1610	75	TON	STONE FOR EROSION CONTROL, CLASS A
600900000-E	1610	80	TON	STONE FOR EROSION CONTROL, CLASS B
601200000-E	1610	30	TON	SEDIMENT CONTROL STONE
601500000-E	1615	2	ACR	TEMPORARY MULCHING
601800000-E	1620	100	LB	SEED FOR TEMPORARY SEEDING
602100000-E	1620	0.5	TON	FERTILIZER FOR TEMPORARY SEEDING
602900000-E	SP	3,000	LF	SAFETY FENCE
603000000-E	1630	100	CY	SILT EXCAVATION
603600000-E	1631	200	SY	MATting FOR EROSION CONTROL
604200000-E	1632	50	LF	1/4" HARDWARE CLOTH

ItemNumber	Sec #	Quantity	Unit	Description
604800000-E	SP	110	SY	FLOATING TURBIDITY CURTAIN
608400000-E	1660	2.5	ACR	SEEDING & MULCHING
608700000-E	1660	1.5	ACR	MOWING
609000000-E	1661	50	LB	SEED FOR REPAIR SEEDING
609300000-E	1661	0.25	TON	FERTILIZER FOR REPAIR SEEDING
609600000-E	1662	50	LB	SEED FOR SUPPLEMENTAL SEEDING
610800000-E	1665	1.75	TON	FERTILIZER TOPDRESSING
611400000-N	SP	2	HR	SPECIALIZED HAND MOWING
613200000-N	SP	4	EA	GENERIC EROSION CONTROL ITEM RESPONSE FOR EROSION CONTROL

5/28/99

27-DEC-2005 15:16
4027_rdy_sum.dgn