PROJECT REFERENCE NUMBER	SHEET NO.	TOTAL SHEETS
	3B	7
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION

Volumes in Cubic Yards

PROJECT: B-3445 COUNTY: CURRITUCK DATE: 1-12-06 COMPILED BY: T. Farr SHEET _____ OF _____ SHEETS

RD1050IC

STATION	STATION	EXCAVATION					EMBANKMENT				BORROW	WASTE			
		TOTAL UNCLASS.	ROCK	UNDERCUT	UNSUIT. UNCLASS.	SUITABLE UNCLASS.	TOTAL	ROCK	EARTH	EMBANK. (+)30%		ROCK	SUITABLE	UNSUIT.	TOTAL
SUMMARY 1															
PHASE 1															
19+65.00	23+28.00 Rt.	6			6		375		375	488	488			6	6
25+08.00	28+70.00 Rt.	4			4		350		350	455	455			4	4
SUMMARY 1 TOTALS		10			10		725		725	943	943			10	10
SUMMARY 2															
PHASE 2															
19+65.00	23+28.00 Lt.	2			2		764		764	993	993			2	2
25+08.00	28+70.00 Lt.						846		846	1100	1100				
SUMMARY 2 TOTALS		2			2		1610		1610	2093	2093			2	2
SUMMARY 3															
PHASE 3															
19+65.00	23+28.00 Lt.& Rt.	2			2		78		78	101	101			2	2
25+08.00	28+70.00 Lt.& Rt.						120		120	156	156				
SUMMARY 3 TOTALS		2			2		198		198	257	257			2	2
SUMMARY TOTALS		14			14		2533		2533	3293	3293			14	14
SUBTOTALS		14			14		2533		2533	3293	3293			14	14
EST. 5% TO REPLACE TOPSOIL IN BORROW PIT											165				
PROJECT TOTALS		14									3458				14
SAY:		20									3500				
EST. UNDERCUT EXCAVATION= 500 CY															