

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
SUMMARY OF EARTHWORK
IN CUBIC YARDS

LOCATION	UNCL. EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
SUMMARY 1					
PHASE 1					
-L- 19+65.00 TO 23+28.00 (RT.)	6		488	488	6
-L- 25+08.00 TO 28+70.00 (RT.)	4		455	455	4
SUMMARY 1 SUBTOTAL	10		943	943	10
SUMMARY 2					
PHASE 2					
-L- 19+65.00 TO 23+28.00 (LT.)	2		993	993	2
-L- 25+08.00 TO 28+70.00 (LT.)			1100	1100	
SUMMARY 2 SUBTOTAL	2		2093	2093	2
SUMMARY 3					
PHASE 3					
-L- 19+65.00 TO 23+28.00 (RT. & LT.)	2		101	101	2
-L- 25+08.00 TO 28+70.00 (RT. & LT.)			156	156	
SUMMARY 3 SUBTOTAL	2		257	257	2
SUBTOTAL SUMMARIES 1-3	14		3293	3293	14
EST. 5% TO REPLACE TOPSOIL IN BORROW PIT				165	
PROJECT TOTALS	14		3293	3458	14
SAY:	20			3500	

ESTIMATED UNDERCUT EXCAVATION = 500 CY